US Army Corps of Engineers
Hydrologic Engineering Center

Flood Control System Component Optimization: HEC-1 Capability

October 1974
revised: September 1977

Approved for Public Release. Distribution Unlimited.

TD-9

REPORT DOCUMENTATION PAGE

Form Approved OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the date needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY *(Leave blank)*	2. REPORT DATE	3. REPORT TYPE AND DATES COVERED
	October 1974 revised September 1977	Training Document No. 9

4. TITLE AND SUBTITLE
Flood Control System Component Optimization: HEC-1 Capability

5. FUNDING NUMBERS

6. AUTHOR(S)
CEIWR-HEC

7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)
US Army Corps of Engineers
Institute for Water Resources
Hydrologic Engineering Center (HEC)
609 Second Street
Davis, CA 95616-4687

8. PERFORMING ORGANIZATION REPORT NUMBER
TD-9

9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES)
N/A

10. SPONSORING / MONITORING AGENCY REPORT NUMBER
N/A

11. SUPPLEMENTARY NOTES
The capability described herein is included as a regular feature of the September 1981 version of HEC-1; however, the input data and output formats are different from the older versions of the program.

12a. DISTRIBUTION / AVAILABILITY STATEMENT
Approved for Public Release. Distribution of this document is unlimited.

12b. DISTRIBUTION CODE

13. ABSTRACT *(Maximum 200 words)*

This document presents detailed illustrated examples of facility optimization using HEC-1. The examples were designed to assist in data assembly and coding, output interpretation, and study management. Examples included were constructed in building block sequence to illustrate the relationships between the hydrologic, economic, and cost data to demonstrate selected capability. Examples illustrated include: (1) hydrologic model for existing conditions; (2) economic evaluation of existing conditions; (3) optimization of reservoir and pumping plant with no hydrologic constraints; (4) optimization of reservoir and pumping plant with hydrologic performance constraints; (5) optimization of reservoir, pumping plant, and diversion (unconstrained); (6) optimization of local projects, levee and channel modification (unconstrained); and, (7) optimization of reservoir, pumping plant, and local protection projects with uniform local protection level. The optimization algorithm (or search procedure discussed was developed to assist the planner in systematically and efficiently screening a large number of possible flood control alternatives. It should be emphasized that the optimization procedure of HEC-1 is a planning tool for determining potential and economically feasible flood control alternatives. Once those that have potential are selected, a more detailed simulation of the operational and hydraulic characteristics of a particular component will probably be required as various stages of study (leading to design) are undertaken.

14. SUBJECT TERMS
flood control, systems analysis, hydrologic systems, model studies, computer models, analytical techniques, analysis, computer programs, reservoirs, diversion, storage, pumping plants, economics, hydrographs, training, HEC-1

15. NUMBER OF PAGES
222

16. PRICE CODE

17. SECURITY CLASSIFICATION OF REPORT	18. SECURITY CLASSIFICATION OF THIS PAGE	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT
UNCLASSIFIED	UNCLASSIFIED	UNCLASSIFIED	UNLIMITED

Flood Control System Component Optimization: HEC-1 Capability

October 1974
revised: September 1977

US Army Corps of Engineers
Institute for Water Resources
Hydrologic Engineering Center
609 Second Street
Davis, CA 95616

(530) 756-1104
(530) 756-8250 FAX
www.hec.usace.army.mil

TD-9

TABLE OF CONTENTS

	Page
INTRODUCTION	1
BASIC EXAMPLE DESCRIPTION	2
HYDROLOGIC MODEL	2
ECONOMIC EVALUATION—EXISTING CONDITIONS	4
FLOOD CONTROL MEASURE OPTIMIZATION	5
SIZING RESERVOIR AND PUMPING PLANT—UNCONSTRAINED	6
a. Detention Storage	6
b. Pumping Plant	7
SIZING RESERVOIR AND PUMPING PLANT—HYDROLOGIC PERFORMANCE CONSTRAINED	12
SIZING RESERVOIR, PUMPING PLANT AND DIVERSION	14
SIZING LOCAL PROTECTION PROJECTS	15
SIZING RESERVOIR, PUMPING PLANT, DIVERSION, AND UNIFORM PROTECTION LOCAL PROJECTS	17
OBJECTIVE OF THE FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION UTILIZING HEC-1	18
REFERENCES	19
APPENDIX A - INPUT DATA	

EXHIBITS

1. Hydrologic Model (Existing Conditions)
2. Multiflood, Multiplan Model (Economic Evaluation of Existing Conditions)
3. Sizing Reservoir and Pumping Plant (Unconstrained)
4. Sizing Reservoir and Pumping Plant (Hydrologic Performance Constrained)
5. Sizing Reservoir, Pumping Plant and Diversion (Unconstrained)
6. Sizing Levee and Channel Modification (Unconstrained)
7. Sizing Reservoir, Pumping Plant, Diversion and Uniform Protection Local Projects (Unconstrained)

LIST OF FIGURES

Figure No.	Title	Page
1	Study Area and Schematic Representation	3
2	Adjustment of Component Size by Newton-Raphson Convergence Procedure	10
3	Effect of Diversion on Flood Hydrograph	15

INTRODUCTION

HEC-1 has been augmented to provide the capability of automatically determining the sizes of flood control system measures that result in maximizing total system net economic benefits subject to possible hydrologic performance targets. The system flood control measures that can be automatically sized are:

- Detention storage reservoir(s)
- Pumping plant(s)
- Diversion(s)
- Local protection(s), i.e., channel modification, levee, floodwall

This document presents detailed illustrated examples of facility optimization using HEC-1. The examples are designed to assist in data assembly and coding, output interpretation, and study management.

Examples included are constructed in building block sequence to illustrate the relationships between the hydrologic, economic and cost data and demonstrate selected capability. Examples illustrated include:

- Hydrologic Model for existing conditions.
- Economic evaluation of existing conditions.
- Optimization of Reservoir and Pumping Plant with no hydrologic constraints.
- Optimization of Reservoir and Pumping Plant with hydrologic performance constraints.
- Optimization of Reservoir, Pumping Plant and Diversion (unconstrained).
- Optimization of local protection projects; levee and channel modification (unconstrained).
- Optimization of Reservoir, Pumping Plant and local protection projects with uniform local protection level.

The basic reference for HEC-1 is the Users Manual listed as reference 1. The input data supplement, reference 2, updates Addendum 6 of reference 1 to include the facility optimization capability. Technical Paper No. 42, reference 3, describes the conceptual basis for the optimization problem and explains the characteristics of the flood control measures (except for the local protection capability that has recently been added) and a field application. Reference 4 summarizes various optimization algorithms and also includes a list of references pertinent to the subject matter presented herein. Reference 5 describes in detail the methodology involved in the calculation of expected annual damages.

BASIC EXAMPLE DESCRIPTION

The study area lies in the flood plain of a large river and is presently protected (to a degree) by a major levee. The levee greatly restricts outflow from the study area. Most of the storm runoff (within the study area) originates from the higher elevations (bluff areas), and most flooding occurs in the lower reaches of the study streams. Development in the flood hazard areas consists of agricultural crops, industrial-commercial areas and residential development. Figure 1 is a general map and schematization of the example area.

Proposals for protecting vulnerable areas from potential flooding include a detention storage reservoir at station 10, channel modification from station 10 to 30, levee from station 20 to 30, flow diversion (by-pass) from station 20 to 30, and a pumping facility with forebay ponding at the basin outlet, station 30 (see Figure 1-a).

HYDROLOGIC MODEL

The hydrologic model for existing conditions is needed to define the base hydrology and provide a mechanism for evaluating the performance of proposed alternatives. Care must be taken in developing the base model to assure that all feasible alternatives can be easily evaluated and that the pattern hydrologic event is reasonably representative for the area, i.e., will not bias evaluation of alternatives. Data required for coding the basic hydrologic model is given in reference 1.

Since the primary objective of this supplement is illustration of flood control system component optimization, the hydrologic model has been kept simple in that discharge hydrographs of a specific event are read in rather than computed from rainfall-runoff relations during the optimization. (The hydrographs were essentially computed in a previous run). A hypothetical event was synthesized that ranged in frequency from the annual event (1.0 exceedence frequency) in the upper basin reaches to about the 5-year event (.2 exceedence frequency) in the lower basin. Channel routing criteria has been developed for the streams from multiple water surface profile calculations and for the restricted outlet at station 30 from the geometry of the outflow culvert and local topography. Table 1 (Appendix A) contains a tabulation of the hydrologic data for existing conditions.

Exhibit 1, page 1 of 2, is a listing of the HEC-1 input data for the hydrologic model. The hydrologic simulation of existing conditions indicates that for the selected event, the peak flows at stations 10, 20 and 30 are 5,370 cfs, 5,370 cfs and 10,154 cfs, respectively. The maximum storage level achieved at station 30 is 9,557 ac.ft. (maximum storage at station 30 not shown in computer printout included) and the peak outflow is 1,200 cfs.



a. Study Area



b. Schematic Representation

Figure 1

ECONOMIC EVALUATION—EXISTING CONDITIONS

The economic evaluation for existing conditions provides the base from which economic benefits of alternatives may be evaluated. The economic evaluation of flood damages requires that flow-damage-frequency analysis be performed to develop "expected" (or average) annual damages. Reference 3 and Addendum 3 of reference 1 discuss the general application of flood damage frequency analysis to flood alternative evaluations and describe the concepts embodied in HEC-1.

The information required (in addition to the hydrologic model) is flow (or storage) - damage relationships and exceedence frequency relations at the damage centers. Additional coding is required to set up the multi-plan feature of HEC-1 and establish the range of floods needed to evaluate the hydrologic and economic effects of alternatives.

The damages in reaches 1030 and 2030 are mostly rural and result from overflow from the respective stream channels. Damage surveys have developed relationships between stage and damages for these reaches for a number of categories of damages. Water surface profile studies developed rating curves for the index stations as shown on Figure 1 so that flow-damage functions, as required by HEC-1, could be developed. The damages at location 305 are mostly urban, commercial and industrial (and are thus large) and occur because of ponding behind the levee. In HEC-1 storage is used instead of stage to represent level and thus a storage-damage function has been developed at this site. Storage is analogous to stage and the function is developed from the usual stage-damage relationship and a site stage-storage relationship.

The required exceedence frequency relationships for stations 10 and 20 were based on a partial duration series analysis because significant damages occur from events that occur more frequently than the annual event. These curves were developed from regional relationships developed in other studies. The required frequency relationship for station 30 is storage-exceedence frequency. This function was derived by developing synthetic events that would reproduce the regional curves at station 10 and 20, simulating the hydrologic operation of the system for these events, and plotting the resulting peak storage levels for these events versus their exceedence frequencies. Table 2 (Appendix A) contains the economic and frequency data for the damage centers.

The determination of the range of floods needed requires evaluation of the exceedence frequency relations, base hydrology and damage relations. The objective in developing the range of floods (multi-plan flood ratios) is to provide for <u>automatic</u> revision of the exceedence frequency relationship so that expected annual damages can be computed for alternative proposals. The procedure used for automatically revising the frequency curve is explained in Addendum 3 of reference 1. To accomplish this, the

ratios should develop floods that cover the range of damaging floods at all damage centers; in our example, the range extends from the six times per year event at damage centers 1030 and 2030 to above the .005 event at 305. The ratios contained in Table 2 (Appendix A) when applied to the synthetic event of the hydrologic model adequately cover the range.

The multi-plan coding has been prepared for two plans, which is necessary for the optimization examples following. The two plans are both for existing conditions which is of course redundant. If the multi-plan capability were being applied by itself, coding should be for as many alternatives as is desired for study. Exhibit 2, pages 1 and 2, are a complete listing of data input with notations as to revisions required from the basic hydrologic model and additions for the multi-plan evaluation.

The output for a multi-plan run includes complete hydrologic simulation for existing conditions and the proposed plan of improvement (none for example) for each of the range of runoff events (nine for the example) and integration of the damage relationships. The results indicate expected annual damages under existing conditions are $33,580, $33,580 and $1,110,210 for damage reaches 1030, 2030 and 305, respectively.

The economic output (printout for station 1030 is page 3 of Exhibit 2) begins with a printout of control codes and includes (1) a listing of data input (ECONOMIC DATA FOR STATION 1030 PLAN 1) which includes exceedance frequency in events per year, peak flow and damages, (2) computation of expected annual damages (FLOOD DAMAGES FOR STATION 1030 PLAN 1) which includes allocation of probability intervals (PROB INT) to the range of flood events (FLOW) and incremental computed damage contribution to expected annual damages (SUM, TYPE 1, etc.) that are based on the product of PROB INT and damage associated with FLOW, and (3) the same information for the alternative plan. If the alternative plan had reduced annual damages, then the benefits (AVG ANN BFT) would be positive and equal to the difference between PLAN 1 and PLAN 2.

FLOOD CONTROL MEASURE OPTIMIZATION

The information required in addition to the hydrologic model and multi-plan economic data for flood control measure optimization are the performance parameters and cost relationships for the flood control features being considered. The mathematical structure for the optimization and the search strategy are discussed in detail in reference 3. It should be remembered (or understood) that economic optimum is achieved when the facilities are sized such that the computed difference between expected annual benefits and expected annual costs is maximized. The solution may proceed unconstrained or it can be constrained such that a minimum hydrologic performance at specified control points must be accomplished simultaneously with the net benefit maximization.

The general technique used is to successively operate the multi-plan simulation in a controlled fashion while automatically adjusting component sizes toward optimum.

SIZING RESERVOIR AND PUMPING PLANT — UNCONSTRAINED

The first optimization example will be the determination of the optimum (economic) sizes for a reservoir located at station 10 and a pumping plant to be located at station 30 that discharges through (or over) the levee. There is no minimum constraining hydrologic performance required. Information must therefore be assembled and coded that will describe, in a general way, the cost and performance of the storage reservoir and a pumping facility.

a. Detention Storage. — The detention storage reservoirs that may be considered with HEC-1 are those for which it is possible to define the operating characteristics as unique functions of the storage contents within the reservoirs. A reservoir with an uncontrolled outlet works exactly meets this requirement. To provide capability for automatic adjustment of operating characteristics (as is required for automatic optimization), a reservoir is characterized by (1) the outflow characteristics of a low level outlet, which is defined by the centerline elevation of the outlet and an orifice equation of the form:

$$Q = CA\sqrt{2g}\,(H)^{EXP} \quad \ldots\ldots\ldots\ldots\ldots (1)$$

where

C = orifice discharge coefficient
A = outlet area
H = head on low level outlet
g = acceleration of gravity
EXP = exponent dependent on tailwater conditions, 0.5 if no tailwater

and (2) the overflow characteristics of a spillway which is defined by a weir equation of the form:

$$Q = C_{*}LH_{*}^{\,3/2} \quad \ldots\ldots\ldots\ldots\ldots\ldots (2)$$

where

C_{*} = weir discharge coefficient
L = length of spillway
H_{*} = head on spillway

and (3) the site storage characteristics which are defined by an elevation-storage capacity relationship. For an index storage to be optimized, which is the storage at the elevation of the spillway crest, the above relationships are merged to define the reservoir's outflow as a function of the storage level in the reservoir (Modified Puls method of routing).

Two modes are possible for a reservoir optimization. In the usual mode (for our example) a reservoir that can be characterized by a low level outlet and an overflow weir as described above will be automatically adjusted in its index storage capacity, along with all other system components, to achieve the minimum value of the objective function (defined in reference 3). The alternative mode, not illustrated, permits optimization of the size of the low level outlet assuming the reservoir does not spill, which is appropriate for pondage in low lying areas.

The cost relationships for the reservoir in the usual mode consists of a capital cost function and an associated capital recovery factor for converting the capital cost to annual cost, and the annual cost of operation, maintenance and replacement expressed as a proportion of capital cost. The capital cost function includes land acquisition and construction costs, interest during construction, etc., expressed as a function of the index storage size of the reservoir. The capital cost for a specific reservoir size being evaluated during optimization is interpolated from this function and the equivalent annual cost is computed as the product of the capital cost and the capital recovery factor for the appropriate discount rate. The annual cost of operation, maintenance and replacement is the product of the annual cost proportion and the interpolated capital cost. The total annual cost of the reservoir is the sum of these two costs. Table 3 (Appendix A) contains the data describing the performance and cost of the proposed reservoir.

b. Pumping Plant — A pumping facility removes volume from the system at a rate equal to the pumping capacity. The performance characteristics of a pumping plant are defined by an initial threshold water level at which the pump is activated and the discharge capacity of the pumping facility. In this analysis, it is assumed that water pumped from the system does not later appear at other locations in the system. The cost of a pumping facility is computed from a capital cost function and an associated capital recovery factor for converting to equivalent annual cost, the annual operation, maintenance and replacement cost that is a proportion of the capital cost, and the annual power cost. The power cost is adjusted if the volume to be pumped changes as the system components sizes are being optimized. It can be demonstrated that no matter the pumping capacity, the power costs would not materially change if the volume to be pumped does not change. The annual power costs are therefore adjusted only for water that is removed from the system by diversions or other pumping facilities. The annual cost is the sum of the equivalent annual cost, annual operation and maintenance cost, and annual power cost. Table 4 (Appendix A) contains the data describing the performance and cost of the proposed pumping plant.

The coding requires initial estimates for the facility sizes (starting values) and a number of control codes to indicate location and type of facility to be sized. The starting values selected were 10,000 ac.ft. and 4,000 cfs for the reservoir and pumping plant, respectively. Exhibit 3, pages 1 and 2, are a listing of the input data for this example including notations of revisions and additions to the data required for the multi-plan evaluation example.

Exhibit 3, pages 3 - 43, are reproductions of the complete output from the optimization run. The output of an optimization run includes:

1. The derived optimum size for each facility in the system included in the optimization (page 43).

2. Complete hydrologic simulation of the system with and without the optimally sized facilities for the range of floods processed (nine for this example) (pages 6 - 42).

3. Economic expected annual damage analysis with and without the optimally sized facilities for each damage center in the system (pages 17, 24 and 41).

4. Costs for the derived system facilities (pages 11 and 40).

5. A summary of system cost, performance and net benefits (page 42).

The derived optimum sizes are 9,119 ac.ft. for the reservoir and 2,885 cfs for the pumping plant (summary page 43). The total capital cost is $7,497,000 and system annual net benefits are $173,000 (benefit cost ratio of 1.26). The derived values were adjusted from the starting values of 10,000 ac.ft. and 4,000 cfs which corresponded to a capital cost of $8,740,000 and system net benefits of 158,000 (page 43). It is necessary, in each case, to test for possible local optima in the search procedure. This was accomplished by making a separate run with starting values of 3,000 ac.ft. and 500 cfs respectively. The derived sizes were 6,584 ac.ft. and 2,835 cfs costing $6,591,000 and resulting in annual system net benefits of $199.000. The results indicated that a local optimum did exist such that additional runs were made with different initial values until it could be reasonably concluded that the proper sizes were 6,584 ac.ft. for the reservoir and 2,835 cfs for the pumping plant.

The hydrologic performance can be characterized by the "degree of protection" provided, i.e., the exceedence frequency of the threshold of damaging flow. At damage center 1030, the zero damage exceedence frequency was reduced from about the 5 times per year event to about the annual event (deduced from page 17 and the additional runs made). Note that damages at station 1030 are quite small in relation to those at 305 and therefore probably had very little influence on the determination of the optimum sizes.

At damage center 305, the frequency of significant damages was reduced from about the 3-year exceedence interval event to about the 10-year event, which incidentally reduced expected annual damages by more than half.

Detailed study of the output can provide insight into the optimization methodology as well as the sensitivity of the system performance to a range of facility sizes. Pages 3 through 6 of Exhibit 3 contain detailed output on the progress of the optimazation. The variables for optimization printed on page 3 are defined below and a review of the search procedure (reference 3) and the corresponding results from the output are described.

Variable Definition

NC = Counter denoting stage in search cycle (1-3)

M = Variable that is being adjusted for this cycle (corresponds to fields on J2 card listed above as SYSTEM OPTIMIZATION)

M1 = Next variable to be adjusted (optimized)

VAR(M) = Current value of variable M

VAR(M1) = Current value of variable M1

OBJ DEV = Used in connection with hydrologic performance constraint; described in example in next section

TANCST = Total annual cost of facilities at current values

ANDMG = Total annual damage for all damage centers for facilities at current values

O FTN(NC) = Objective function that is being minimized; in this example it is the sum of TANCST and ANDMG

Search Procedure (see reference 3)

(1) First, trial sizes of all system components are nominated and the entire system is simulated in all of its hydrologic, costs, and economic detail to calculate the value of the objective function, which for unconstrained optimization is the sum of the equivalent annual cost (TANCST) and annual damage (ANDMG).

The first value (NC=1) of the objective function is 1018.883

(2) Then the size of one component is decreased by a small selected amount (1 percent) and the simulation is repeated for the entire system to compute a new value of the objective function. This is repeated again resulting in three unique values of the objective function for small changes in the size of one component.

The values of the variable and objective function are

NC	VAR(M)	0 FTN(NC)
1 $f(X_0)$	10000	1018.883
2 $f(X_0 - \Delta X)$	9900	1018.205
3 $f(X_0 - 2\Delta X)$	9800	1017.645

(3) From these three values, an estimate is made of the component size that would result in the minimum value of the objective function. The computation of the adjustment is shown in Figure 2 and proceeds as follows:



Figure 2.— Adjustment of Component Size by Newton-Raphson Convergence Procedure

$$f''\left(X_o - \frac{\Delta X}{2}\right) = \tan\theta = f'\left(X_o - \frac{\Delta X}{2}\right)\left[\left(X_o - \frac{\Delta X}{2}\right) - X^*\right]^{-1} \quad \ldots\ldots(3)$$

$$\text{or} \quad X^* = X_o - \left[f'\left(X_o - \frac{\Delta X}{2}\right)\right]\left[f''\left(X_o - \frac{\Delta X}{2}\right)\right]^{-1} - \frac{\Delta X}{2} \quad \ldots\ldots\ldots(4)$$

$$\text{in which} \quad f'\left(X_o - \frac{\Delta X}{2}\right) = [f(X_o) - f(X_o - \Delta X)](\Delta X)^{-1} \quad \ldots\ldots\ldots(5)$$

$$f''\left(X_o - \frac{\Delta X}{2}\right) = [f(X_o - 2\Delta X) - 2f(X_o - \Delta X) + f(X_o)](\Delta X)^{-2} \quad \ldots\ldots(6)$$

and ΔX = incremental change in X; X = size of variable being optimized; X_O = present size of component X; and X* = projected "new" size for X. The calculation for adjustment of VAR(M) is as follows:

$$f'\left(X_0 - \frac{\Delta X}{2}\right) = (1018.883 - 1018.205)/\Delta X = 0.678/\Delta X \quad \ldots\ldots(7)$$

$$f''\left(X_0 - \frac{\Delta X}{2}\right) = [1017.645 - 2(1018.205) + 1018.883]/\Delta X^2 \quad .118/\Delta X^2 \ldots(8)$$

$X_0 = 10000$; $\Delta X = (.01)\ (10000) = 100$

$$X^* = 10000 - \frac{0.678/100}{.118/(100)^2} - \frac{100}{2} = 9380. \text{ (to closest 10)} \ldots(9)$$

(4) After adjustment of the size of the system component, the entire system is simulated again in detail to compute the new value of the objective function and, provided the objective function has decreased, the procedure then moves to the second system component whose scale is to be optimized.

The output at this stage reads:

VAR 1 ADJ FROM 10000. to 9384.07

and one cycle for one variable has been completed.

(5) The above procedure is repeated for the second and all subsequent components to be optimized.

Note that the same procedure is repeated for variable 9.

(6) A single adjustment has now been made for each component for one complete search of the system component sizes. The procedure is then repeated for two more complete system searches.

(7) The component whose change contributed the most to decreasing the objective function is adjusted next before another complete system search is performed.

(8) The procedure is terminated when either no more improvement in the objective function can be made (within a tolerance) for the component making the greatest contribution to decreasing the objective function, or the complete search cycle is completed.

Note that occasionally no successful adjustment can be made. If the computed adjustment does not reduce the objective function, its value is successively reduced to the original value, testing for improvement at a number of steps (pages 5 and 6 of Exhibit 3).

The remaining output should be self-explanatory. Remember the output is for two plans (existing and the derived system) for nine flood events which results in 18 hydrologic simulations at each control point and two economic evaluations at all damage centers.

SIZING RESERVOIR AND PUMPING PLANT — HYDROLOGIC PERFORMANCE CONSTRAINED

The objective for this example is to determine the size of the facilities that will maximize the system net benefits while simultaneously meeting hydrologic performance targets expressed in terms of desired flow (storage) target and corresponding exceedence frequency. This example extends the previous example for the performance targets of

Reach	Target Value	Exceedence Frequency (Events per Year)
1030	1200 cfs	1.0
305	5000 ac.ft.	.05

The starting values were selected as 5000 ac.ft. and 5000 cfs, respectively.

Pages 1 and 2 of Exhibit 4 contain a listing of the input data with notations on coding revised and added. Pages 3 through 28 contain printout of selected pages of the output.

The derived optimum sizes are 7528 ac.ft. for the reservoir and 6044 cfs for the pumping plant (summary page 28). The total capital cost is $9,889,000 and system annual net benefits are $123,000 (benefit cost ratio

of 1.15). The derived values were adjusted from starting values of 5000 ac.ft. and 5000 cfs, respectively. The sensitivity of the solution to starting values was tested by making a separate run with starting values of 10,000 ac.ft. and 7000 cfs, respectively. The derived sizes were 6,007 ac.ft. and 6,570 cfs costing $9,832,000 and resulting in annual net benefits of $102,000. The hydrologic performance specified is achieved in that the degree of protection provided is 1.0 years (protection against the annual event) for reach 1030 and .05 (protection against the 20-year event) for reach 305 (see pages 15 and 26 of Exhibit 4).

The output detailing the progress of the optimization contains additional information related to the performance target constraints. The additional variables are (page 3, Exhibit 4):

Variable Definition

ISTA = Station where performance target specified

INT FLOW = Flow corresponding to the target exceedence frequency for the current values of the variables

TRG FLOW = Target flow for the target exceedence frequency

FLW OBJ = Component of penalty applied to objective function because of failure to meet target (illustrated later) for this station

FLW DEV = Difference between INT FLW and TRG FLW

OBJ DEV = Penalty applied to objective function because of failure to meet target (multiply)

The additional printout occurs for all stations where performance targets are specified (as many as desired). The optimization proceeds exactly as the previous (unconstrained) example except that the objective function is penalized whenever the performance targets are not met. Note that the first objective function is extremely large (.951E+06) because of the large penalty from not meeting the target for station 305 while the objective function when optimization is complete (page 10, Exhibit 4) essentially has no penalty (.106E+04). The computation of a value of the objective function for the condition blocked out on page 5 (Exhibit 4) will illustrate the role of the penalty assessment. See reference 3 for a description of the objective function.

$$\text{FLW OBJ} = [\ (\text{FLW DEV})/(.10\ \text{TRG FLOW})\ ]^4$$

Station 1030

$$\text{FLW OBJ} = \left(\frac{12.670}{120}\right)^4 = .0001$$

Station 305

$$\text{FLW OBJ} = \left(\frac{782.138}{500}\right)^4 = 5.988$$

Objective Function Assessment

OBJ DEV = .0001 + 5.988 = 5.988

O FTN(NC) = (TANCST + ANDMG) (OBJ DEV + 1)

O FTN(NC) = (774.217 + 265.434) (5.988 + 1) = 7264.80

The printout at the bottom of the pages on which economic output is shown (page 15 for example) summarizes the performance target and final regulated values.

SIZING RESERVOIR, PUMPING PLANT AND DIVERSION

A proposal offered at past public meetings has been to divert a portion of the runoff from subbasin 20 at station 20 into the adjacent watershed (which is presently undeveloped) both to reduce flooding in the downstream reaches and increase wetlands in the adjacent watershed to improve wildlife habitat. This example extends the previous reservoir and pumping plant example (unconstrained) to include a diversion from station 20.

A diversion transfers flow between locations within the system. The performance characteristics are defined by a threshold flow and a diversion capacity. The concept of the diversion relationship is indicated in figure 3. Water diverted may be returned to the system at any downstream location so that it is possible to characterize facilities which would bypass a portion of flood flows around a damage center. Flow may also be permanently diverted from the system, which will be done for this example. The cost is characterized similar to a pumping plant by a capital cost function, a capital recovery factor and annual operation, maintenance and replacement factor.

Table 5 (Appendix A) summarizes the performance and cost data for the proposed diversion.

The coding to include a diversion at station 20 is noted on the listing of input data, pages 1 and 2 of Exhibit 5. Note that it was necessary to include a dummy reservoir at station 20 in order to accommodate the requirements for a diversion.



Figure 3. — Effect of Diversion on Flood Hydrograph

Pages 3 through 34 of Exhibit 5 contain selected pages of the output. The derived optimum sizes are 6620 ac.ft. (index storage) for the reservoir, 863 cfs for the diversion and 2250 cfs for the pumping plant (summary page 34). The total capital cost is $7,099,000 and system net benefits are $197,000 (benefit cost ratio of 1.33). The derived values were adjusted from starting values of 4000 ac.ft., 500 cfs and 1000 cfs, respectively, for the reservoir, diversion, and pumping plant. The sensitivity of the solution to starting values was tested by making a separate run with new starting values of 10,000 ac.ft., 3000 cfs and 4000 cfs, respectively. The derived sizes were 6648 ac.ft., 1393 cfs and 2160 cfs, respectively, costing $7,617,000 and resulting in annual net benefits of $167,000. In comparison with the previously derived values, it appears the diversion should be the smaller size. Additional runs demonstrate the value of testing a few starting values in an effort to locate a reasonable optimum.

The hydrologic performance of the derived system can be characterized by the degree of protection provided, i.e., the exceedence frequency of the threshold of damaging flows. At control point 1030, the 0 damage exceedence frequency was reduced from about the five times per year event to about the annual event (about the same as the example without the diversion). At control point 2030, the 0 damage exceedence frequency was not materially changed from the five times per year event. At control point 305, the frequency of <u>significant</u> damage was reduced from about the 3-year exceedence interval event to between the 10 and 15-year events. The residual damages for the system are reduced to about 1/3 of the damages under existing conditions.

SIZING LOCAL PROTECTION PROJECTS

Local protection projects include levees, floodwalls and channel modifications. Ignoring for the moment natural valley storage effects, the hydrologic and economic effects of local projects are truly local,

i.e., do not interact with the system hydrology. If this is the case, and it will be unless the modification is extensive, then a local project can be completely characterized performance-wise by a design Q (or storage) and a flow (or storage) damage function. Damages are usually negligible below the design flow and follow a curve related to the local site hydraulics and damage potential above this point. A levee or floodwall essentially truncates the damage function below the design flow (basic hydraulic-economic relationship unchanged) while channel modifications lower the relationship in response to the improved conveyance characteristics.

The concept embodied in HEC-1 is that a design flow is associated with a unique damage relationship and therefore if the range of feasible design flows are known, the relationship for a specific design flow within the feasible range could be determined. The relationship (flow or storage-damage) for a specific design flow is determined by interpolating between the relationships defining the feasible range. The relationships defining the feasible range are termed "pattern functions;" the minimum design damage function corresponding to the design flow considered the lowest value feasible and the maximum design damage function corresponding to the design flow considered the highest value feasible.

The local projects considered for this example are a channel modification for reach 1030 and a levee for reach 2030. The pattern damage functions for reach 1030 were developed from water surface profile and economic studies. The minimum design damage function corresponds to a "clear and snag" alternative and was constructed by computing water surface profiles for a smoothed boundary to develop a rating curve at the index station that was subsequently combined with an area, elevation, damage relationship. The design flow associated with this function is 1700 cfs, the lower limit of design flow. The maximum design function corresponds to a 40 ft. bottom width, 2 to 1 side slope channel enlargement and was constructed by computing water surface profiles for modified hydraulic geometry to develop a rating curve that was subsequently combined with an area, elevation, damage relationship. The design flow associated with this function is 8300 cfs, the upper limit of design flow for the enlarged channel. Table 6 (Appendix A) summarizes the performance and cost data for the proposed channel modification for reach 1030. Table 6 also contains a generated damage function for a specific design flow to illustrate the interpolation concept.

The upper and lower pattern damage functions for reach 2030 are the same and correspond to existing conditions. The reason for the correspondence is that the effect of a levee is primarily to truncate the function at the design flow. Some change is possible for various designs if the flow area is greatly restricted by the levees. The example assumes no significant conveyance change from the levees, though the methodology does not require the assumption. Table 7 (Appendix A) summarizes the cost and performance data for the proposed levee reach.

The existing conditions damage relationships, cost and runoff hydrology for reaches 1030 and 2030 have been purposefully made the same so that

the methodology developed for handling local projects can be easily observed. The example contains only local projects (other damage centers and alternatives removed) so that the difference in the derived sizes of the two alternatives should only be due to differences in their performance, i.e., modified damage relationships. A listing of the input data for this example is contained on pages 1 and 2 of Exhibit 6.

Pages 3 through 15 of Exhibit 6 contain selected pages of the output of the optimization run.

The derived optimum sizes are about 5000 cfs design flow for both the channel modification reach and the levee reach. This amounts to about a 0.7 exceedence frequency degree of protection. The total capital cost is $207,000 and system annual net benefits of $30,000. The derived values were adjusted from starting values of 2000 cfs design flow for each facility. It is interesting to note that while both facilities began and ended with the same values, the adjustment route to the optimum was different. There was no requirement that they both end up the same size (see pages 3 through 5 of Exhibit 6). In addition, note that while the values derived were the same, the net benefits were different because the damage relationships were quite different. The channel modification cost $104,000 and had average annual benefits of 27,000 for annual net benefits of $19,000 (benefit cost ratio of approximately 3.4). The levee cost $103,000 and had average annual benefits of $19,000 for annual net benefits of $11,000 (benefit cost ratio of approximately 2.4).

SIZING RESERVOIR, PUMPING PLANT, DIVERSION, AND UNIFORM PROTECTION LOCAL PROJECTS

This final example includes all the proposed components that have been previously illustrated. The optimization will be unconstrained and the uniform protection level option for the local projects will be used. The uniform protection level option will in effect cause a "degree of protection" to be optimized for the two local protection projects. A complete listing of the input data is contained on pages 1 through 3 of Exhibit 7 and the complete output on pages 4 through 39.

The derived optimum sizes are 6701 ac.ft. for the reservoir, 0.2 exceedence frequency for the levee and channel projects (2947 cfs for the channel modification and 7660 cfs for the levee), 670 cfs for the diversion and 2450 cfs for the pumping plant for a total capital cost of $7,408,000 and system net benefits of $196,000 (benefit cost ratio of 1.31). The optimum sizes were adjusted from starting values of 4000 ac.ft. for the reservoir, 0.2 exceedence frequency (uniform protection) for local projects, 500 cfs for the diversion and 1000 cfs for the pumping plant. A comparison of Exhibits 5 and 7 indicates that the inclusion of local projects has very little effect on the optimum sizes of the major facilities (reservoir and pumping plant). The diversion capacity was lowered slightly from that derived in Exhibit 5 which probably means that it is more efficient to protect reach 2030 by the levee project.

OBJECTIVE OF THE FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION UTILIZING HEC-1

The optimization algorithm (or search procedure) discussed in this training document has been developed to assist the planner in systematically and efficiently screening a large number of possible flood control alternatives. Although there is an upper limit to the number which can be satisfactorily and economically optimized in one particular computer run, it is still possible to analyze a large number of components by grouping. In the Phoenix Urban Study, Los Angeles District Corps of Engineers (reference 6), there were eight upstream storage alternatives to be evaluated. Although each component was analyzed individually, it was possible to determine which component and combination of components were economically feasible by making several runs in groups of two and three components and comparing the economic and hydrologic consequences.

It should be emphasized that the optimization procedure of HEC-1 is a planning tool for determining potential and economically feasible flood control alternatives. Once those that have potential are selected, then a more detailed simulation of the operational and hydraulic characteristics of a particular component will probably be required as various stages of study (leading to design) are undertaken.

REFERENCES

1. HEC-1, Flood Hydrograph Package, Users Manual, U.S. Army Corps of Engineers, The Hydrologic Engineering Center, Davis, California, January 1973.

2. Input Data Description, Addendum 6 to HEC-1 Users Manual, September 1974.

3. Davis, Darryl W., "Optimal Sizing of Urban Flood Control Systems," Technical Paper No. 42, U.S. Army Corps of Engineers, The Hydrologic Engineering Center, Davis, California, March 1974.

4. Optimization Model for the Design of Urban Flood-Control Systems, Technical Report CRWR-141, Center for Research in Water Resources, College of Engineering, University of Texas, Austin, Texas, November 1976.

5. Expected Annual Flood Damage Computation, Users Manual, U.S. Army Corps of Engineers, The Hydrologic Engineering Center, Davis, California, June 1977.

6. Interagency Task Force on Orme Dam Alternatives, Preliminary Flood Control Summary Report, Phoenix Urban Study, Los Angeles District, U.S. Army Corps of Engineers, Los Angeles, California, September 1977.

APPENDIX A

INPUT DATA

TABLE 1

HYDROLOGIC DATA
(Existing Conditions)

DRAINAGE AREA

Subbasin	Area (square miles)
10	35.1
20	35.1
30	10.0
TOTAL	80.2

SUBBASIN RUNOFF
SYNTHETIC STORM EVENT
(hourly values)

Inflow to Sta. 10 (cfs)		Inflow to Sta. 20 (cfs)		Inflow to Sta. 30 (cfs)	
24	2200	24	2200	8	730
24	1840	24	1840	8	615
26	1540	26	1540	9	515
33	1250	33	1250	11	415
50	995	50	995	17	330
85	775	85	775	28	255
190	605	190	605	63	200
375	470	375	470	125	155
515	365	515	365	170	120
590	280	590	280	195	93
660	215	660	215	220	72
710	160	710	160	230	54
760	120	760	120	255	41
800	95	800	95	265	32
840	77	840	77	280	26
910	66	910	66	305	22
1040	59	1040	59	350	20
1290	53	1290	53	430	18
1920	49	1920	49	640	16
3000	42	3000	42	1000	14
3950	40	3950	40	1320	13
4600	38	4600	38	1540	12
5080	35	5080	35	1650	11
5360	33	5360	33	1800	11
5370	30	5370	30	1810	11
5100	30	5100	30	1690	10
4600	29	4600	29	1530	10
3980	27	3980	27	1330	9
3330	25	3330	25	1110	9
2720	25	2720	25	900	9

TABLE 1 (Continued)

HYDROLOGIC DATA
(Existing Conditions)

Reach 10-30 Mod. Puls Routing Criteria[1]

Storage (ac.ft.)	0	50	475	940	2135	3080	6300
Outflow (cfs)	0	200	1020	2050	6100	10250	24000

Reach 20-30 Mod Puls Routing Criteria[1]

Storage (ac.ft.)	0	50	475	940	2135	3080	6300
Outflow (cfs)	0	200	1020	2050	6100	10250	24000

Outflow Culvert (Sta. 30) Mod. Puls Routing Criteria[1]

Storage (ac.ft.)	0	400	100000[2]
Outflow (cfs)	0	1200	1200

1/ Storage-outflow data should extend beyond the maximum values computed in the multiflood-multiplan options.

2/ Note that the outflow becomes constant and equal to 1200 cubic feet per second when the detention storage equals or exceeds 400 acre feet.

TABLE 2
ECONOMIC DAMAGE-FREQUENCY DATA
(Existing Conditions)

Damage Center 1030

Exceedence Frequency (Events per Yr)	Flow (cfs)	Type 1 Damage ($1000)	Type 2 Damage ($1000)	Type 3 Damage ($1000)
6.000	1030	0.00	0.00	0.00
5.500	1130	0.00	0.00	0.00
4.500	1380	0.10	0.50	1.00
3.500	1740	0.20	0.70	1.50
2.500	2280	0.30	1.50	3.20
1.500	3200	0.30	2.20	4.70
.900	4220	0.40	2.90	6.50
.700	4800	0.50	3.50	7.80
.500	5620	0.60	4.00	9.30
.350	6480	0.70	4.70	11.00
.250	7340	0.80	5.80	13.70
.150	8540	0.90	6.60	15.60
.100	10000	1.00	8.00	19.00
.050	12100	1.20	10.30	23.00
.020	15100	1.50	15.00	27.80
.005	21000	1.80	18.10	30.20

Damage Center 2030

Exceedence Frequency (Events per Yr)	Flow (cfs)	Type 1 Damage ($1000)
6.000	1030	0.00
5.500	1130	0.00
4.500	1380	1.60
3.500	1740	2.40
2.500	2280	5.00
1.500	3200	7.20
.900	4220	9.80
.700	4800	11.80
.500	5620	13.90
.350	6480	16.40
.250	7340	20.30
.150	8540	23.10
.100	10000	28.00
.050	12100	34.50
.020	15100	44.30
.005	21000	50.10

TABLE 2 (Continued)
ECONOMIC DAMAGE-FREQUENCY DATA
(Existing Conditions)

Damage Center 305[1]

Exceedence Frequency (Events per yr)	Storage (ac-ft)	Type 1 Damage ($1000)	Type 2 Damage ($1000)
.700	1500	0.00	0.00
.600	2300	37.50	10.50
.450	4000	75.00	15.00
.250	7000	1125.00	52.50
.100	12500	3150.00	105.00
.050	20000	5850.00	202.50
.020	28000	7050.00	300.00
.010	37000	9000.00	390.00
.005	50000	10650.00	540.00
.002	76000	11250.00	585.00

Flood Ratios for Multiflood, Multiplan Evaluation

0.25	0.30	0.50	0.70	1.00	1.50	2.20	3.25	4.40

1/ Note that the damage-frequency relationship (for damage center 305) is a function of storage and not discharge.

TABLE 3
RESERVOIR PERFORMANCE AND COST DATA

Low Level Outlet

Area of Opening	= 35 ft^2
Orfice Coefficient, C, in the general expression $Q = C\ A\ (2gH)^{Exp.}$ (free discharge)	= 0.71
Cenderline Elevation of Orfice	= 975 ft
No Tailwater (no submergence) Exponent of head (Exp.)	= 0.5

Overflow Spillway

Type	= Ogee
Length	= 35 ft
Weir Coefficient, C, in the general expression $Q = C\ L\ H^{3/2}$	= 2.86

Cost and Site Characteristics[1]

Capacity (ac.ft.)	0	2500	4000	5200	6800	9000	11500	15500	21000	30000
Elevation (ft)	965	1000	1015	1030	1045	1060	1075	1090	1105	1120
Cost ($1000)	0	1500	2400	3000	3600	4350	4950	5550	6000	7200

Annual Cost Data

Annual Operation and Maintenance = 2.3% of Capital Cost
Discount Factor (Capital Recovery)= 5.04%

Constraints

Reservoir size must be in range of 0 to 25,000 ac.ft.

1/ Capacity-elevation data should extend beyond the maximum values computed in the multiflood-multiplan options and the maximum reservoir size designated.

TABLE 4
PUMPING PLANT PERFORMANCE AND COST DATA

Cost and Performance Data

Capacity (cfs)	0	250	500	1000	2000	6000	8000	10000
Cost ($1000)	0	670	1000	1600	2300	6000	7860	8670

Annual Cost Data

Annual Operation and Maintenance = 2.3% of Capital Cost
Discount Factor (Capital Recovery) = 5.04%
Annual Power Cost = $100,000[1]

Sizing and Operation Data

Pumping plant must be between 0 and 10,000 cfs.
Pumps activate at storage level (at station 30) = 1500 ac.ft.

1/ Annual power cost is adjusted based on the difference in computed volumes at the pumping facility as system component sizes vary from specified initial values to optimized values

TABLE 5
DIVERSION PERFORMANCE AND COST DATA

Performance and Cost Data

Capacity (cfs)	0	1250	2500	3750	5000	7500	10000	15000	20000
Cost ($1000)	0	1500	2600	3400	4200	5200	6100	7500	8300

Annual Cost Data

Annual Operation and Maintenance = 1.5% of Capital Cost
Discount Factor (Capital Recovery) = 5.04%

Operation and Constraints

Diversion activation threshold = 1,500 cfs
Size limit between 0 and 20,000 cfs

TABLE 6

CHANNEL MODIFICATION COST AND PERFORMANCE DATA

Damage Center 1030

Flow (cfs)	Minimum Design Damage Function Design Q = 1700cfs			Maximum Design Damage Function Design Q = 8300cfs			Flow (cfs)	Interpolated Damage Function Design Q = 4830cfs		
	Type 1 Damage ($1000)	Type 2 Damage ($1000)	Type 3 Damage ($1000)	Type 1 Damage ($1000)	Type 2 Damage ($1000)	Type 3 Damage ($1000)		Type 1 Damage ($1000)	Type 2 Damage ($1000)	Type 3 Damage ($1000)
1030	0.00	0.00	0.00	0.00	0.00	0.00	1030	0.00	0.00	0.00
1130	0.00	0.00	0.00	0.00	0.00	0.00	1130	0.00	0.00	0.00
1380	0.00	0.00	0.00	0.00	0.00	0.00	1380	0.00	0.00	0.00
1740	0.01	0.08	0.13	0.00	0.00	0.00	1740	0.00	0.00	0.00
2280	0.14	0.95	1.73	0.00	0.00	0.00	2280	0.00	0.00	0.00
3200	0.25	1.73	3.44	0.00	0.00	0.00	3200	0.00	0.00	0.00
4220	0.36	2.53	5.85	0.00	0.00	0.00	4825[1]	0.00	0.00	0.00
4800	0.43	2.73	7.23	0.00	0.00	0.00	4830[1]	0.11	0.38	1.07
5620	0.53	3.53	8.91	0.00	0.00	0.00	5620	0.20	1.15	2.69
6480	0.62	4.08	10.63	0.00	0.00	0.00	6480	0.29	1.70	4.41
7340	0.69	5.01	13.11	0.00	0.00	0.00	7340	0.36	2.63	6.89
8540	0.82	6.16	15.03	0.04	0.25	0.44	8540	0.45	3.36	8.11
10000	0.97	7.70	18.61	0.25	1.75	3.50	10000	0.63	4.88	11.44
12100	1.17	9.90	22.09	0.42	3.18	7.15	12100	0.81	6.71	15.01
15100	1.43	14.08	27.00	0.64	5.04	12.29	15100	1.06	9.79	20.02
21000	1.76	17.51	29.32	0.99	7.98	16.86	21000	1.40	12.99	23.41

1/ In the interpolation scheme zero damages are estimated to occur at a peak flow which is 99.9 percent of the design flow.

TABLE 6 (Continued)

CHANNEL MODIFICATION COST AND PERFORMANCE DATA

Performance and Cost Data

Capacity (cfs)	1700	5000	5500	7000	8300	9300
Cost ($1000)	42	103	149	222	283	340

Annual Cost Data

Annual Operation and Maintenance = 2.3% of Capital Cost
Discount Factor (Capital Recovery) = 5.04 %

Design Limits

Minimum Design Q = 1700 cfs
Maximum Design Q = 8300 cfs

TABLE 7

LEVEE COST AND PERFORMANCE DATA

Damage Center 2030

Flow (cfs)	Minimum Design Damage Function Damage ($1000)	Maximum Design Damage Function Damage ($1000)
1030	0.00	0.00
1130	0.00	0.00
1380	1.60	1.60
1740	2.40	2.40
2280	5.00	5.00
3200	7.20	7.20
4220	9.80	9.80
4800	11.80	11.80
5620	13.90	13.90
6480	16.40	16.40
7340	20.30	20.30
8540	23.10	23.10
10000	28.00	28.00
12100	34.50	34.50
15100	44.30	44.30
21000	50.10	50.10

Performance and Cost Data

Capacity (cfs)	1700	5000	5500	7000	8300	9300
Cost ($1000)	42	103	149	222	283	340

Annual Cost Data

Annual Operation and Maintenance = 2.3% of Capital Cost
Discount Factor (Captial Recovery) = 5.04%

Design Limits

Minimum design Q = 1700 cfs Maximum design Q = 8300 cfs

EXHIBIT 1

HYDROLOGIC MODEL

(Existing Conditions)

```
A       FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
A       HYDROLOGIC MODEL
A       EXISTING CONDITIONS
B     60       1                                                        4
1      3
K      0      10                                       1
1       POTENTIAL RESERVOIR INFLOW
M     -1             35.1                                               0
N     24      24      26      33      50      85     190     375     515     590
N    660     710     760     800     840     910    1040    1290    1920    3000
N   3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
N   2200    1840    1540    1250     995     775     605     470     365     280
N    215     160     120      95      77      66      59      53      49      42
N     40      38      35      33      30      30      29      27      25      25
K      1    1030                                       1
1       POTENTIAL CHANNEL MODIFICATION REACH
Y                              1
1      1                                              -1
2      0      50     475     940    2135    3080    6300
3      0     200    1020    2050    6100   10250   24000
K      0      20
M     -1             35.1                                               0
N     24      24      26      33      50      85     190     375     515     590
N    660     710     760     800     840     910    1040    1290    1920    3000
N   3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
N   2200    1840    1540    1250     995     775     605     470     365     280
N    215     160     120      95      77      66      59      53      49      42
N     40      38      35      33      30      30      29      27      25      25
K      1    2030                                       1
1       POTENTIAL LEVEE AND/OR BYPASS REACH
Y                              1
1      1                                              -1
2      0      50     475     940    2135    3080    6300
3      0     200    1020    2050    6100   10250   24000
K      0      30                                       1
1       LOCAL INFLOW TO FOREBAY POOL
M     -1             10.0                                               0
N      8       8       9      11      17      28      63     125     170     195
N    220     230     255     265     280     305     350     430     640    1000
N   1320    1540    1650    1800    1810    1690    1530    1330    1110     900
N    730     615     515     415     330     255     200     155     120      93
N     72      54      41      32      26      22      20      18      16      14
N     13      12      11      11      11      10      10       9       9       9
K      3      30                                       1
1       COMBINED INFLOW TO FOREBAY POOL
K      1     305                                       1
1       GRAVITY OUTLET THROUGH LEVEE
Y                              1
1      1                                              -1
2      0     400  100000
3      0    1200    1200
K     99
A
A
A
A
A
```

Exhibit 1
1 of 2

RUNOFF SUMMARY, AVERAGE FLOW IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES(SQUARE KILOMETERS)

		PEAK	6-HOUR	24-HOUR	72-HOUR	AREA
HYDROGRAPH AT	10	5370.	5018.	2635.	1158.	35.10
		(152.06)(	142.10)(	74.63)(	32.80)(	90.91)
ROUTED TO	1030	4312.	4092.	2471.	1158.	35.10
		(122.10)(	115.87)(	69.98)(	32.78)(	90.91)
HYDROGRAPH AT	20	5370.	5018.	2635.	1158.	35.10
		(152.06)(	142.10)(	74.63)(	32.80)(	90.91)
ROUTED TO	2030	4312.	4092.	2471.	1158.	35.10
		(122.10)(	115.87)(	69.98)(	32.78)(	90.91)
HYDROGRAPH AT	30	1810.	1670.	878.	386.	10.00
		(51.25)(	47.29)(	24.85)(	10.92)(	25.90)
3-COMBINED	30	10154.	9579.	5772.	2701.	80.20
		(287.53)(	271.25)(	163.46)(	76.47)(	207.72)
ROUTED TO	305	1200.	1200.	1200.	966.	80.20
		(33.98)(	33.98)(	33.98)(	27.36)(	207.72)

Exhibit 1
2 of 2

EXHIBIT 2

MULTIFLOOD, MULTIPLAN MODEL

(Economic Evaluation of Existing Conditions)

```
  A        FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
R-A        MULTIFLOOD, MULTIPLAN MODEL
R-A        ECONOMIC EVALUATION OF EXISTING CONDITIONS
  B     60       1                                                    4
R-1     (5)
N-J      2       9       1
N-1   0.25    0.30    0.50    0.70    1.00    1.50    2.20    3.25    4.40
  K      0      10                                       1
  1        POTENTIAL RESERVOIR INFLOW
R-M     -1              35.1                                         (1)
  N     24      24      26      33      50      85     190     375     515     590
  N    660     710     760     800     840     910    1040    1290    1920    3000
  N   3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N   2200    1840    1540    1250     995     775     605     470     365     280
  N    215     160     120      95      77      66      59      53      49      42
  N     40      38      35      33      30      30      29      27      25      25
R-K      1    1030     (1)                                 1
  1        POTENTIAL CHANNEL MODIFICATION REACH
R-Y                                1      (1)                           (0)
  1      1                                                -1
  2      0      50     475     940    2135    3080    6300
  3      0     200    1020    2050    6100   10250   24000
N-Z   1030      16       3       1
  1      6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
  1    .25     .15     .10     .05     .02    .005
  2   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  2   7340    8540   10000   12100   15100   21000
  3
  4      0       0      .1      .2      .3      .3      .4      .5      .6      .7
  4     .8      .9     1.0     1.2     1.5     1.8
  4      0       0      .5      .7     1.5     2.2     2.9     3.5     4.0     4.7
  4    5.8     6.6     8.0    10.3    15.0    18.1
  4      0       0     1.0     1.5     3.2     4.7     6.5     7.8     9.3    11.0
N-4   13.7    15.6    19.0    23.0    27.8    30.2
  K      0      20
R-M     -1              35.1                                         (1)
  N     24      24      26      33      50      85     190     375     515     590
  N    660     710     760     800     840     910    1040    1290    1920    3000
  N   3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N   2200    1840    1540    1250     995     775     605     470     365     280
  N    215     160     120      95      77      66      59      53      49      42
  N     40      38      35      33      30      30      29      27      25      25
R-K      1    2030     (1)                                 1
  1        POTENTIAL LEVEE AND/OR BYPASS REACH
R-Y                                1      (1)                           (0)
  1      1                                                -1
  2      0      50     475     940    2135    3080    6300
  3      0     200    1020    2050    6100   10250   24000
N-Z   2030      16       1       1
  1      6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
  1    .25     .15     .10     .05     .02    .005
  2   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  2   7340    8540   10000   12100   15100   21000
N-3
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

( ) = REVISED INPUT DATA



```
N- 4      0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
N- 4   20.3    23.1    28.0    34.5    44.3    50.1
   K      0      30                                      1
   1      LOCAL INFLOW TO FOREBAY POOL
R- M     -1            10.0                                          (1)
   N      8       8       9      11      17      28      63     125     170     195
   N    220     230     255     265     280     305     350     430     640    1000
   N   1320    1540    1650    1800    1810    1690    1530    1330    1110     900
   N    730     615     515     415     330     255     200     155     120      93
   N     72      54      41      32      26      22      20      18      16      14
   N     13      12      11      11      11      10      10       9       9       9
   K      3      30                                      1
   1      COMBINED INFLOW TO FOREBAY POOL
R- K      1     305     (1)                              1
   1      GRAVITY OUTLET THROUGH LEVEE
R- Y                             1      (1)                             (1)
   1      1
   2      0     400  100000                             -1
   3      0    1200    1200
N- Z    305      10       2       1
   1    .70     .60     .45     .25     .10     .05     .02     .01    .005    .002
   2   1500    2300    4000    7000   12500   20000   28000   37000   50000   76000
   3
   4      0    37.5      75    1125    3150    5850    7050    9000   10650   11250
N- 4      0    10.5      15    52.5     105   202.5     300     390     540     585
   K     99
   A
   A
   A
   A
   A
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

( ) = REVISED INPUT DATA

ECON DATA FOR STATION 1030 IDENTIFIED AS STATION 1030

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
1030	16	3	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 1030 PLAN 1

FREQ	PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
6.000	1030.	0.000	0.000	0.000	0.000
5.500	1130.	0.000	0.000	0.000	0.000
4.500	1380.	1.600	.100	.500	1.000
3.500	1740.	2.400	.200	.700	1.500
2.500	2280.	5.000	.300	1.500	3.200
1.500	3200.	7.200	.300	2.200	4.700
.900	4220.	9.800	.400	2.900	6.500
.700	4800.	11.800	.500	3.500	7.800
.500	5620.	13.900	.600	4.000	9.300
.350	6480.	16.400	.700	4.700	11.000
.250	7340.	20.300	.800	5.800	13.700
.150	8540.	23.100	.900	6.600	15.600
.100	10000.	28.000	1.000	8.000	19.000
.050	12100.	34.500	1.200	10.300	23.000
.020	15100.	44.300	1.500	15.000	27.800
.005	21000.	50.100	1.800	18.100	30.200

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.98	.07	.30	.61
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.31	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.49
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97

FLOOD DAMAGES FOR STATION 1030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.98	.07	.30	.61
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.31	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.49
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97
	AVG ANN BFT			0.00	.00	-.00	.00

ECON DATA FOR STATION 2030 IDENTIFIED AS STATION 2030

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
2030	16	1	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 2030 PLAN 1

FREQ	PEAK	SUM	TYPE 1
6.000	1030.	0.000	0.000
5.500	1130.	0.000	0.000
4.500	1380.	1.600	1.600
3.500	1740.	2.400	2.400
2.500	2280.	5.000	5.000
1.500	3200.	7.200	7.200
.900	4220.	9.800	9.800
.700	4800.	11.800	11.800
.500	5620.	13.900	13.900
.350	6480.	16.400	16.400
.250	7340.	20.300	20.300
.150	8540.	23.100	23.100
.100	10000.	28.000	28.000
.050	12100.	34.500	34.500
.020	15100.	44.300	44.300
.005	21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58

FLOOD DAMAGES FOR STATION 2030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58
	AVG ANN BFT			.00	0.00

ECON DATA FOR STATION 305 IDENTIFIED AS STATION 305

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
305	10	2	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 305 PLAN 1

FREQ	STOR	SUM	TYPE 1	TYPE 2
.700	1500.	0.000	0.000	0.000
.600	2300.	48.000	37.500	10.500
.450	4000.	90.000	75.000	15.000
.250	7000.	1177.500	1125.000	52.500
.100	12500.	3255.000	3150.000	105.000
.050	20000.	6052.500	5850.000	202.500
.020	28000.	7350.000	7050.000	300.000
.010	37000.	9390.000	9000.000	390.000
.005	50000.	11190.000	10650.000	540.000
.002	76000.	11835.000	11250.000	585.000

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 305 PLAN 1

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	1036.	.700	0.000	0.00	0.00	0.00
2	1486.	.700	.152	2.02	1.58	.44
3	3587.	.480	.197	21.19	18.50	2.69
4	5904.	.311	.150	112.78	107.26	5.51
5	9557.	.169	.119	240.14	231.56	8.58
6	15876.	.075	.075	311.36	300.95	10.41
7	24937.	.030	.037	232.61	223.56	9.06
8	38699.	.009	.013	110.98	106.13	4.85
9	53876.	.004	.008	79.14	75.28	3.86
	AVG ANN DMG			1110.21	1064.81	45.40

FLOOD DAMAGES FOR STATION 305 PLAN 2

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	1036.	.700	0.000	0.00	0.00	0.00
2	1486.	.700	.152	2.02	1.58	.44
3	3587.	.480	.197	21.19	18.50	2.69
4	5904.	.311	.150	112.78	107.26	5.51
5	9557.	.169	.119	240.14	231.56	8.58
6	15876.	.075	.075	311.36	300.95	10.41
7	24937.	.030	.037	232.61	223.56	9.06
8	38699.	.009	.013	110.98	106.13	4.85
9	53876.	.004	.008	79.14	75.28	3.86
	AVG ANN DMG			1110.21	1064.81	45.40
	AVG ANN BFT			.00	-.00	.00

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS RATIO 1 ,25	RATIO 2 ,30	RATIO 3 ,50	RATIO 4 ,70	RATIO 5 1,00	RATIO 6 1,50	RATIO 7 2,20	RATIO 8 3,25	RATIO 9 4,40
HYDROGRAPH AT	10	35,10	1	1343,	1611,	2685,	3759,	5370,	8055,	11814,	17453,	23628,
	(	90,91)	(	38,02)(	45,62)(	76,03)(	106,44)(	152,06)(	228,09)(	334,54)(	494,20)(	669,07)
			2	1343,	1611,	2685,	3759,	5370,	8055,	11814,	17453,	23628,
			(	38,02)(	45,62)(	76,03)(	106,44)(	152,06)(	228,09)(	334,54)(	494,20)(	669,07)
ROUTED TO	1030	35,10	1	941,	1139,	1940,	2921,	4312,	6699,	10191,	15177,	20603,
	(	90,91)	(	26,65)(	32,24)(	54,94)(	82,71)(	122,10)(	189,70)(	288,58)(	429,77)(	583,42)
			2	941,	1139,	1940,	2921,	4312,	6699,	10191,	15177,	20603,
			(	26,65)(	32,24)(	54,94)(	82,71)(	122,10)(	189,70)(	288,58)(	429,77)(	583,42)
HYDROGRAPH AT	20	35,10	1	1343,	1611,	2685,	3759,	5370,	8055,	11814,	17453,	23628,
	(	90,91)	(	38,02)(	45,62)(	76,03)(	106,44)(	152,06)(	228,09)(	334,54)(	494,20)(	669,07)
			2	1343,	1611,	2685,	3759,	5370,	8055,	11814,	17453,	23628,
			(	38,02)(	45,62)(	76,03)(	106,44)(	152,06)(	228,09)(	334,54)(	494,20)(	669,07)
ROUTED TO	2030	35,10	1	941,	1139,	1940,	2921,	4312,	6699,	10191,	15177,	20603,
	(	90,91)	(	26,65)(	32,24)(	54,94)(	82,71)(	122,10)(	189,70)(	288,58)(	429,77)(	583,42)
			2	941,	1139,	1940,	2921,	4312,	6699,	10191,	15177,	20603,
			(	26,65)(	32,24)(	54,94)(	82,71)(	122,10)(	189,70)(	288,58)(	429,77)(	583,42)
HYDROGRAPH AT	30	10,00	1	453,	543,	905,	1267,	1810,	2715,	3982,	5883,	7964,
	(	25,90)	(	12,81)(	15,38)(	25,63)(	35,88)(	51,25)(	76,88)(	112,76)(	166,57)(	225,52)
			2	453,	543,	905,	1267,	1810,	2715,	3982,	5883,	7964,
			(	12,81)(	15,38)(	25,63)(	35,88)(	51,25)(	76,88)(	112,76)(	166,57)(	225,52)
3 COMBINED	30	80,20	1	2219,	2676,	4563,	6859,	10154,	15693,	23748,	35345,	48011,
	(	207,72)	(	62,84)(	75,79)(	129,21)(	194,23)(	287,53)(	444,39)(	672,47)(	1000,86)(	1359,53)
			2	2219,	2676,	4563,	6859,	10154,	15693,	23748,	35345,	48011,
			(	62,84)(	75,79)(	129,21)(	194,23)(	287,53)(	444,39)(	672,47)(	1000,86)(	1359,53)
ROUTED TO	305	80,20	1	1200,	1200,	1200,	1200,	1200,	1200,	1200,	1200,	1200,
	(	207,72)	(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)
			2	1200,	1200,	1200,	1200,	1200,	1200,	1200,	1200,	1200,
			(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)(	33,98)
			PEAK STORAGES IN ACRE FEET (1000 CUBIC METERS)									
			1	1036,	1486,	3587,	5904,	9557,	15876,	24937,	38699,	53876,
			(	1278,)(	1833,)(	4424,)(	7283,)(	11788,)(	19583,)(	30760,)(	47734,)(	66455,)
			2	1036,	1486,	3587,	5904,	9557,	15876,	24937,	38699,	53876,
			(	1278,)(	1833,)(	4424,)(	7283,)(	11788,)(	19583,)(	30760,)(	47734,)(	66455,)

EXHIBIT 3

SIZING RESERVOIR AND PUMPING PLANT

(Unconstrained)

```
  A        FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
R-A        SIZING RESERVOIR AND PUMPING PLANT
R-A        UNCONSTRAINED
R-B      60       1                                                  (3)
R-1      (6)
  J       2       9       1
  1    0.25    0.30    0.50    0.70    1.00    1.50    2.20    3.25    4.40
N-2  -10000                                                          -4000
N-4
  K       0      10                                       1
  1        POTENTIAL RESERVOIR INFLOW
  M      -1            35.1                                             1
  N      24      24      26      33      50      85     190     375     515     590
  N     660     710     760     800     840     910    1040    1290    1920    3000
  N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N    2200    1840    1540    1250     995     775     605     470     365     280
  N     215     160     120      95      77      66      59      53      49      42
  N      40      38      35      33      30      30      29      27      25      25
N-K       1     110                                2       1
  1        PROPOSED RESERVOIR
  Y                              -1       0
  Y                               1       0       1
  1       1                                              -1
  $   25000       0     200   975.0      .5   100.0    .023   .0504
  1       0    2500    4000    5200    6800    9000   11500   15500   21000   30000
  2     965    1000    1015    1030    1045    1060    1075    1090    1105    1120
N-3       0    1500    2400    3000    3600    4350    4950    5550    6000    7200
  K       1    1030       1                                1
  1        POTENTIAL CHANNEL MODIFICATION REACH
  Y                               1       1                                0
  1       1                                              -1
  2       0      50     475     940    2135    3080    6300
  3       0     200    1020    2050    6100   10250   24000
  Z    1030      16       3       1
  1       6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
  1     .25     .15     .10     .05     .02    .005
  2    1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  2    7340    8540   10000   12100   15100   21000
  3
  4       0       0      .1      .2      .3      .3      .4      .5      .6      .7
  4      .8      .9     1.0     1.2     1.5     1.8
  4       0       0      .5      .7     1.5     2.2     2.9     3.5     4.0     4.7
  4     5.8     6.6     8.0    10.3    15.0    18.1
  4       0       0     1.0     1.5     3.2     4.7     6.5     7.8     9.3    11.0
  4    13.7    15.6    19.0    23.0    27.8    30.2
  K       0      20
  M      -1            35.1                                             1
  N      24      24      26      33      50      85     190     375     515     590
  N     660     710     760     800     840     910    1040    1290    1920    3000
  N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N    2200    1840    1540    1250     995     775     605     470     365     280
  N     215     160     120      95      77      66      59      53      49      42
  N      40      38      35      33      30      30      29      27      25      25
  K       1    2030       1                                1
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA



```
1        POTENTIAL LEVEE AND/OR BYPASS REACH
Y                                 1       1                                0
1      1                                                  -1
2      0      50     475     940    2135    3080    6300
3      0     200    1020    2050    6100   10250   24000
Z   2030      16       1       1
1      6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
1    .25     .15     .10     .05     .02    .005
2   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
2   7340    8540   10000   12100   15100   21000
3
4      0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
4   20.3    23.1    26.0    34.5    44.3    50.1
K      0      30                                         1
1        LOCAL INFLOW TO FOREBAY POOL
M     -1            10.0                                                  1
N      8       8       9      11      17      28      63     125     170     195
N    220     230     255     265     280     305     350     430     640    1000
N   1320    1540    1650    1800    1810    1690    1530    1330    1110     900
N    730     615     515     415     330     255     200     155     120      93
N     72      54      41      32      26      22      20      18      16      14
N     13      12      11      11      11      10      10       9       9       9
K      3      30                                         1
1        COMBINED INFLOW TO FOREBAY POOL
N- K      1     305       1                       2       1
1        PROPOSED PUMPING PLANT SITE
Y                                 1       0                                1
1      1                                                  -1
2      0     400  100000
3      0    1200    1200
Y                                 1                       9                1
1      1                                                  -1
2      0     400  100000
3      0    1200    1200
*  10000       0    1500     100    .023   .0504
1      0     250     500    1000    2000    6000    8000   10000
N- 2      0     670    1000    1600    2300    6000    7860    8670
Z    305      10       2       1
1    .70     .60     .45     .25     .10     .05     .02     .01    .005    .002
2   1500    2300    4000    7000   12500   20000   28000   37000   50000   76000
3
4      0    37.5     75.    1125    3150    5850    7050    9000   10650   11250
4      0    10.5      15    52.5     105   202.5     300     390     540     585
K     99
A
A
A
A
A
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA

FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
SIZING RESERVOIR AND PUMPING PLANT
UNCONSTRAINED

JOB SPECIFICATION

NQ	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
60	1	0	0	0	0	0	0	3	0

JOPER	NWT	LROPT	TRACE
6	0	0	0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 2 NRTIO= 9 LRTIO= 1

RTIOS= .25 .30 .50 .70 1.00 1.50 2.20 3.25 4.40

SYSTEM OPTIMIZATION

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
-10000.	0.	0.	0.	0.	0.	0.	0.	-4000.	0.

FIXED COST INPUT

FCAP	FDCNT	FAN
0.	0.0000	0.0000
0.	0.	0.

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.100E+05	.100E+05	0.000	741.516	277.367	.102E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.990E+04	.990E+04	0.000	739.917	278.288	.102E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.980E+04	.980E+04	0.000	738.325	279.320	.102E+04

OBJECTIVE FUNCTION FOR VARIABLE 1	.1019E+04	.1018E+04	.1018E+04

VAR 1 ADJ FROM	10000.00 TO	9384.07	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	1	.400E+04	.938E+04	0.000	731.737	284.417 .102E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	9	1	.396E+04	.938E+04	0.000	729.021	286.506 .102E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	9	1	.392E+04	.938E+04	0.000	726.305	288.618 .101E+04
OBJECTIVE FUNCTION FOR VARIABLE 9		.1016E+04	.1016E+04			.1015E+04				
VAR 9 ADJ FROM	4000.00 TO	2948.78	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	1	9	.938E+04	.295E+04	0.000	660.364	344.595 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	1	9	.929E+04	.295E+04	0.000	658.880	346.024 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	1	9	.920E+04	.295E+04	0.000	657.398	347.476 .100E+04
OBJECTIVE FUNCTION FOR VARIABLE 1		.1005E+04	.1005E+04			.1005E+04				
VAR 1 ADJ FROM	9384.07 TO	9118.64	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	1	.295E+04	.912E+04	0.000	656.170	348.714 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	9	1	.292E+04	.912E+04	0.000	654.168	350.656 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	9	1	.289E+04	.912E+04	0.000	652.166	352.606 .100E+04
OBJECTIVE FUNCTION FOR VARIABLE 9		.1005E+04	.1005E+04			.1005E+04				
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	1	9	.912E+04	.274E+04	0.000	641.808	363.145 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
VAR 9 ADJ FROM	2948.78 TO	2885.32	1	1	9	.912E+04	.289E+04	0.000	651.861	352.917 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	1	9	.903E+04	.289E+04	0.000	650.422	354.382 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	1	9	.894E+04	.289E+04	0.000	648.514	355.885 .100E+04
OBJECTIVE FUNCTION FOR VARIABLE 1		.1005E+04	.1005E+04			.1004E+04				

		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.137E+05	0.000	711.373	319.365 .103E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.105E+05	0.000	673.724	337.923 .101E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.953E+04	0.000	658.346	346.654 .101E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.912E+04	0.000	651.861	352.917 .100E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		2	9	1	.286E+04	.912E+04	0.000	649.902	354.917 .100E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		3	9	1	.283E+04	.912E+04	0.000	647.943	356.916 .100E+04
OBJECTIVE FUNCTION FOR VARIABLE 9	.1005E+04	.1005E+04			.1005E+04				
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	1	9	.912E+04	.433E+04	0.000	749.811	272.677 .102E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	1	9	.912E+04	.332E+04	0.000	681.246	325.665 .101E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	1	9	.912E+04	.302E+04	0.000	660.677	344.347 .101E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	1	9	.912E+04	.289E+04	0.000	651.861	352.917 .100E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		2	1	9	.903E+04	.289E+04	0.000	650.422	354.382 .100E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		3	1	9	.894E+04	.289E+04	0.000	648.514	355.885 .100E+04
OBJECTIVE FUNCTION FOR VARIABLE 1	.1005E+04	.1005E+04			.1004E+04				
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.137E+05	0.000	711.373	319.365 .103E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.105E+05	0.000	673.724	337.923 .101E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.953E+04	0.000	658.346	346.654 .101E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		1	9	1	.289E+04	.912E+04	0.000	651.861	352.917 .100E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		2	9	1	.286E+04	.912E+04	0.000	649.902	354.917 .100E+04
		NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
		3	9	1	.283E+04	.912E+04	0.000	647.943	356.916 .100E+04
OBJECTIVE FUNCTION FOR VARIABLE 9	.1005E+04	.1005E+04			.1005E+04				

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	1	9	.912E+04	.433E+04	0.000	749.811	272.677 .102E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	1	9	.912E+04	.332E+04	0.000	681.246	325.665 .101E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	1	9	.912E+04	.302E+04	0.000	660.677	344.347 .101E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	1	1	.912E+04	.912E+04	0.000	651.861	352.917 .100E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
2	1	1	.903E+04	.903E+04	0.000	650.422	354.382 .100E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
3	1	1	.894E+04	.894E+04	0.000	648.514	355.885 .100E+04

OBJECTIVE FUNCTION FOR VARIABLE 1 .1005E+04 .1005E+04 .1004E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	9	1	.289E+04	.137E+05	0.000	711.373	319.365 .103E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	9	1	.289E+04	.105E+05	0.000	673.724	337.923 .101E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
1	9	1	.289E+04	.953E+04	0.000	658.346	346.654 .101E+04

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

POTENTIAL RESERVOIR INFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
10	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

PROPOSED RESERVOIR

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
110	1	0	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	-1	0	0	0	0	0

PLAN 2
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	1	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

RESERVOIR DATA

CAPMX	CAPMN	COQL	ELEVL	EXPL	COQW	RANCST	RDSCNT	COQT	ELEVT	EXPT
25000.	0.	200.00	975.00	.50	100.00	.0230	.0504	0.00	975.00	0.00

CAPACITY=	0.	2500.	4000.	5200.	6800.	9000.	11500.	15500.	21000.	30000.
ELEVATION=	965.	1000.	1015.	1030.	1045.	1060.	1075.	1090.	1105.	1120.
COST=	0.	1500.	2400.	3000.	3600.	4350.	4950.	5550.	6000.	7200.

OUTLET CREST ELEVATION IS 1060.71 AT STORAGE OF 9119.

SYNTHETIC STORAGE OUTFLOW FUNCTION

STORAGE=	714.	1097.	2245.	4657.	9119.	13098.	16565.	20229.	25089.	30000.
OUTFLOW=	0.	463.	926.	1389.	1852.	11189.	20432.	29653.	38860.	48060.

STATION 110, PLAN 2, RTIO 1

OUTFLOW

6.	6.	6.	6.	7.	8.	10.	16.	25.	36.
47.	59.	71.	83.	94.	106.	119.	136.	161.	204.
267.	344.	426.	479.	507.	534.	556.	573.	584.	590.
590.	588.	582.	575.	565.	554.	541.	528.	514.	500.
485.	471.	445.	405.	369.	335.	305.	277.	252.	229.
208.	189.	172.	157.	142.	130.	118.	107.	98.	89.

STOR

719.	719.	719.	719.	720.	721.	723.	727.	735.	744.
753.	763.	773.	783.	792.	802.	813.	826.	847.	883.
935.	998.	1067.	1137.	1207.	1272.	1327.	1369.	1397.	1411.
1413.	1406.	1393.	1374.	1350.	1322.	1291.	1258.	1224.	1188.
1153.	1117.	1082.	1049.	1019.	991.	966.	943.	923.	904.
886.	871.	857.	844.	832.	821.	812.	803.	795.	788.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	590.	585.	513.	276.	16586.
CMS	17.	17.	15.	8.	470.
INCHES		.15	.54	.73	.73
MM		3.94	13.80	18.61	18.61
AC-FT		290.	1017.	1371.	1371.
THOUS CU M		358.	1255.	1692.	1692.

MAXIMUM STORAGE = 1413.

STATION 110, PLAN 2, RTIO 2

OUTFLOW

7.	7.	7.	7.	8.	9.	12.	19.	30.	43.
57.	71.	85.	99.	113.	127.	143.	163.	193.	245.
321.	413.	480.	515.	551.	585.	613.	635.	650.	659.
661.	659.	654.	647.	637.	624.	611.	596.	581.	565.
549.	533.	516.	501.	485.	470.	440.	400.	363.	330.
300.	272.	247.	225.	204.	186.	169.	154.	140.	127.

STOR

720.	720.	720.	720.	721.	722.	724.	730.	739.	750.
761.	773.	785.	796.	808.	820.	833.	849.	874.	917.
980.	1055.	1138.	1227.	1316.	1399.	1469.	1524.	1562.	1582.
1589.	1584.	1572.	1553.	1528.	1498.	1464.	1427.	1389.	1349.
1310.	1270.	1230.	1190.	1152.	1114.	1078.	1045.	1014.	987.
962.	939.	919.	900.	883.	868.	854.	841.	830.	819.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	661.	655.	582.	329.	19711.
CMS	19.	19.	16.	9.	558.
INCHES		.17	.62	.87	.87
MM		4.41	15.68	22.11	22.11
AC-FT		325.	1156.	1630.	1630.
THOUS CU M		401.	1425.	2010.	2010.

MAXIMUM STORAGE = 1589.

STATION 110, PLAN 2, RTIO 3

OUTFLOW

12.	12.	12.	12.	13.	15.	20.	32.	50.	71.
94.	118.	142.	165.	189.	212.	239.	271.	322.	408.
488.	542.	603.	669.	735.	797.	850.	893.	923.	934.
939.	940.	938.	934.	929.	916.	897.	876.	854.	832.
808.	785.	762.	738.	716.	693.	672.	650.	630.	610.
591.	572.	554.	536.	519.	503.	487.	471.	443.	402.

STOR

724.	724.	724.	724.	725.	727.	731.	741.	756.	773.
792.	812.	831.	851.	870.	890.	912.	939.	980.	1052.
1158.	1293.	1445.	1608.	1772.	1925.	2057.	2163.	2239.	2287.
2311.	2317.	2309.	2290.	2259.	2219.	2173.	2122.	2068.	2011.
1954.	1896.	1838.	1780.	1723.	1668.	1614.	1562.	1511.	1462.
1414.	1368.	1323.	1279.	1237.	1196.	1156.	1117.	1081.	1047.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	940.	936.	835.	517.	31041.
CMS	27.	26.	24.	15.	879.
INCHES		.25	.88	1.37	1.37
MM		6.30	22.47	34.83	34.83
AC-FT		464.	1656.	2567.	2567.
THOUS CU M		572.	2043.	3166.	3166.

MAXIMUM STORAGE = 2317.

STATION 110, PLAN 2, RTIO 4

OUTFLOW

17.	17.	17.	17.	18.	21.	28.	44.	70.	100.
132.	165.	198.	232.	264.	297.	334.	380.	451.	500.
564.	643.	733.	829.	925.	969.	1007.	1038.	1062.	1079.
1089.	1094.	1095.	1093.	1089.	1081.	1072.	1061.	1049.	1036.
1022.	1008.	994.	979.	965.	951.	936.	918.	889.	861.
834.	807.	782.	757.	733.	710.	687.	665.	644.	623.

STOR

728.	728.	728.	729.	729.	732.	738.	751.	772.	797.
824.	851.	878.	906.	933.	960.	990.	1028.	1087.	1190.
1347.	1544.	1767.	2005.	2243.	2467.	2666.	2830.	2955.	3041.
3094.	3121.	3128.	3118.	3093.	3055.	3005.	2948.	2885.	2818.
2747.	2674.	2600.	2524.	2449.	2374.	2299.	2226.	2154.	2085.
2017.	1951.	1888.	1826.	1766.	1709.	1653.	1598.	1546.	1495.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1095.	1090.	1025.	661.	39676.
CMS	31.	31.	29.	19.	1124.
INCHES		.29	1.09	1.75	1.75
MM		7.34	27.61	44.51	44.51
AC-FT		541.	2035.	3281.	3281.
THOUS CU M		667.	2510.	4047.	4047.

MAXIMUM STORAGE = 3128.

STATION 110, PLAN 2, RTIO 5

OUTFLOW

24.	24.	24.	25.	26.	30.	40.	63.	100.	143.
189.	236.	284.	331.	377.	425.	468.	491.	527.	591.
685.	803.	930.	998.	1066.	1132.	1191.	1239.	1277.	1305.
1323.	1334.	1340.	1340.	1337.	1330.	1320.	1308.	1294.	1278.
1262.	1245.	1228.	1210.	1192.	1175.	1157.	1140.	1123.	1106.
1089.	1073.	1056.	1040.	1024.	1009.	993.	978.	963.	948.

STOR

734.	734.	734.	735.	736.	739.	748.	767.	797.	832.
870.	909.	949.	988.	1026.	1065.	1109.	1166.	1256.	1413.
1648.	1940.	2268.	2620.	2978.	3320.	3625.	3879.	4077.	4220.
4315.	4372.	4401.	4406.	4388.	4351.	4298.	4234.	4161.	4082.
3997.	3909.	3818.	3726.	3634.	3542.	3451.	3361.	3272.	3183.
3096.	3010.	2925.	2841.	2758.	2677.	2597.	2517.	2439.	2362.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1340.	1334.	1253.	838.	50260.
CMS	38.	38.	35.	24.	1423.
INCHES		.35	1.33	2.22	2.22
MM		8.98	33.75	56.39	56.39
AC-FT		662.	2487.	4156.	4156.
THOUS CU M		816.	3068.	5126.	5126.

MAXIMUM STORAGE = 4406.

STATION 110, PLAN 2, RTIO 6

OUTFLOW

36.	36.	36.	37.	39.	45.	61.	95.	150.	214.
283.	354.	425.	474.	499.	526.	557.	596.	655.	754.
901.	1000.	1099.	1205.	1313.	1403.	1453.	1496.	1530.	1556.
1574.	1586.	1594.	1599.	1599.	1597.	1592.	1585.	1577.	1568.
1558.	1547.	1535.	1524.	1512.	1500.	1488.	1476.	1464.	1452.
1440.	1428.	1417.	1405.	1393.	1376.	1355.	1334.	1314.	1294.

STOR

744.	744.	744.	745.	747.	752.	764.	793.	838.	891.
948.	1007.	1066.	1125.	1187.	1253.	1329.	1426.	1573.	1820.
2182.	2634.	3147.	3699.	4260.	4797.	5280.	5690.	6018.	6265.
6441.	6561.	6639.	6680.	6687.	6665.	6618.	6554.	6475.	6385.
6286.	6181.	6071.	5958.	5843.	5728.	5612.	5497.	5381.	5267.
5152.	5038.	4925.	4813.	4701.	4591.	4481.	4374.	4267.	4163.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1599.	1595.	1540.	1059.	63511.
CMS	45.	45.	44.	30.	1798.
INCHES		.42	1.63	2.81	2.81
MM		10.73	41.47	71.25	71.25
AC-FT		791.	3056.	5252.	5252.
THOUS CU M		976.	3770.	6478.	6478.

MAXIMUM STORAGE = 6687.

STATION 110, PLAN 2, RTIO 7

OUTFLOW

53.	53.	53.	54.	58.	66.	89.	140.	219.	314.
415.	482.	520.	559.	600.	643.	692.	754.	845.	959.
1064.	1195.	1344.	1451.	1539.	1625.	1702.	1768.	1821.	2080.
2669.	2983.	3113.	3105.	2993.	2808.	2580.	2333.	2083.	1851.
1840.	1828.	1815.	1801.	1787.	1774.	1760.	1746.	1732.	1718.
1704.	1690.	1676.	1663.	1649.	1636.	1622.	1609.	1596.	1582.

STOR

758.	758.	758.	759.	762.	769.	788.	830.	896.	974.
1058.	1145.	1237.	1335.	1436.	1544.	1666.	1818.	2043.	2416.
2964.	3648.	4423.	5257.	6109.	6930.	7674.	8311.	8827.	9216.
9467.	9601.	9656.	9653.	9605.	9526.	9429.	9324.	9217.	9113.
9006.	8888.	8763.	8633.	8501.	8366.	8232.	8097.	7963.	7829.
7695.	7561.	7429.	7297.	7166.	7036.	6907.	6778.	6650.	6524.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3113.	2945.	2154.	1398.	83898.
CMS	88.	83.	61.	40.	2376.
INCHES		.78	2.28	3.71	3.71
MM		19.83	57.99	94.13	94.13
AC-FT		1461.	4274.	6937.	6937.
THOUS CU M		1802.	5272.	8557.	8557.

MAXIMUM STORAGE = 9656.

STATION 110, PLAN 2, RTIO 8

OUTFLOW

78.	78.	78.	80.	85.	98.	131.	206.	324.	463.
515.	571.	630.	693.	758.	826.	903.	960.	1027.	1137.
1297.	1446.	1568.	1700.	1834.	4171.	6220.	7586.	8345.	8608.
8499.	8157.	7686.	7129.	6513.	5870.	5229.	4613.	4038.	3509.
3031.	2603.	2223.	1892.	1840.	1826.	1812.	1798.	1784.	1770.
1756.	1742.	1729.	1715.	1701.	1687.	1674.	1660.	1647.	1633.

STOR

779.	779.	779.	780.	785.	795.	823.	885.	982.	1098.
1226.	1365.	1512.	1667.	1828.	1997.	2188.	2424.	2773.	3344.
4177.	5212.	6387.	7654.	8949.	10107.	10980.	11562.	11886.	11998.
11951.	11806.	11605.	11367.	11105.	10831.	10558.	10295.	10050.	9825.
9621.	9439.	9277.	9136.	9005.	8872.	8739.	8605.	8470.	8336.
8201.	8067.	7933.	7800.	7667.	7535.	7404.	7274.	7145.	7016.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	8608.	8147.	4793.	2520.	151184.
CMS	244.	231.	136.	71.	4281.
INCHES		2.16	5.08	6.68	6.68
MM		54.84	129.06	169.62	169.62
AC-FT		4042.	9512.	12501.	12501.
THOUS CU M		4985.	11733.	15420.	15420.

MAXIMUM STORAGE = 11998.

STATION 110, PLAN 2, RTIO 9

RESERVOIR	CAP COST	TOT ANN $
9118.6	4378.	321.

OUTFLOW

106.	106.	106.	108.	115.	133.	178.	279.	439.	520.
593.	672.	756.	844.	930.	976.	1028.	1093.	1187.	1338.
1480.	1628.	1796.	4450.	7836.	10523.	12588.	13836.	14282.	14089.
13441.	12537.	11525.	10536.	9546.	8547.	7573.	6652.	5801.	5026.
4330.	3710.	3163.	2688.	2279.	1932.	1841.	1828.	1814.	1800.
1786.	1773.	1759.	1745.	1731.	1718.	1704.	1691.	1677.	1664.

STOR

802.	802.	802.	804.	810.	824.	861.	945.	1077.	1238.
1420.	1616.	1825.	2042.	2267.	2507.	2778.	3114.	3604.	4394.
5541.	6967.	8586.	10226.	11669.	12814.	13623.	14091.	14258.	14185.
13942.	13603.	13224.	12819.	12398.	11972.	11557.	11164.	10801.	10471.
10175.	9911.	9678.	9475.	9301.	9153.	9020.	8888.	8756.	8624.
8490.	8357.	8225.	8092.	7960.	7829.	7698.	7568.	7438.	7309.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	14282.	13462.	7864.	3797.	227836.
CMS	404.	381.	223.	108.	6452.
INCHES		3.57	8.34	10.06	10.06
MM		90.62	211.75	255.62	255.62
AC-FT		6679.	15606.	18839.	18839.
THOUS CU M		8238.	19250.	23238.	23238.

MAXIMUM STORAGE = 14258.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL CHANNEL MODIFICATION REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 1030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 1030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

STATION 1030, PLAN 1, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1940.	1859.	1220.	579.	34733.
CMS	55.	53.	35.	16.	984.
INCHES		.49	1.29	1.53	1.53
MM		12.52	32.84	38.97	38.97
AC-FT		922.	2420.	2872.	2872.
THOUS CU M		1138.	2985.	3543.	3543.

MAXIMUM STORAGE = 890.

STATION 1030, PLAN 1, RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2921.	2743.	1715.	810.	48621.
CMS	83.	78.	49.	23.	1377.
INCHES		.73	1.82	2.15	2.15
MM		18.47	46.18	54.55	54.55
AC-FT		1361.	3403.	4020.	4020.
THOUS CU M		1679.	4198.	4959.	4959.

MAXIMUM STORAGE = 1197.

STATION 1030, PLAN 1, RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4312.	4092.	2471.	1158.	69450.
CMS	122.	116.	70.	33.	1967.
INCHES		1.08	2.62	3.07	3.07
MM		27.55	66.54	77.92	77.92
AC-FT		2030.	4904.	5743.	5743.
THOUS CU M		2504.	6049.	7083.	7083.

MAXIMUM STORAGE = 1607.

STATION 1030, PLAN 1, RTIO 6

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	6699.	6289.	3747.	1736.	104156.
CMS	190.	178.	106.	49.	2949.
INCHES		1.67	3.97	4.60	4.60
MM		42.34	100.88	116.86	116.86
AC-FT		3120.	7435.	8612.	8612.
THOUS CU M		3849.	9171.	10623.	10623.

MAXIMUM STORAGE = 2271.

STATION 1030, PLAN 1, RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	10191.	9555.	5550.	2545.	152725.
CMS	289.	271.	157.	72.	4325.
INCHES		2.53	5.88	6.75	6.75
MM		64.32	149.44	171.35	171.35
AC-FT		4741.	11014.	12628.	12628.
THOUS CU M		5848.	13585.	15577.	15577.

MAXIMUM STORAGE = 3067.

STATION 1030, PLAN 1, RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	15177.	14262.	8279.	3759.	225518.
CMS	430.	404.	234.	106.	6386.
INCHES		3.78	8.78	9.96	9.96
MM		96.00	222.93	253.02	253.02
AC-FT		7076.	16430.	18647.	18647.
THOUS CU M		8728.	20266.	23001.	23001.

MAXIMUM STORAGE = 4234.

STATION 1030, PLAN 1, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	20603.	19364.	11267.	5087.	305199.
CMS	583.	548.	319.	144.	8642.
INCHES		5.13	11.94	13.48	13.48
MM		130.35	303.38	342.41	342.41
AC-FT		9607.	22359.	25236.	25236.
THOUS CU M		11850.	27580.	31128.	31128.

MAXIMUM STORAGE = 5505.

STATION 1030, PLAN 2, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	529.	526.	472.	269.	16149.
CMS	15.	15.	13.	8.	457.
INCHES		.14	.50	.71	.71
MM		3.54	12.70	18.12	18.12
AC-FT		261.	936.	1335.	1335.
THOUS CU M		322.	1154.	1647.	1647.

MAXIMUM STORAGE = 221.

STATION 1030, PLAN 2, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	593.	590.	539.	315.	18904.
CMS	17.	17.	15.	9.	535.
INCHES		.16	.57	.84	.84
MM		3.97	14.51	21.21	21.21
AC-FT		293.	1069.	1563.	1563.
THOUS CU M		361.	1319.	1928.	1928.

MAXIMUM STORAGE = 254.

STATION 1030, PLAN 2, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	853.	847.	781.	473.	28405.
CMS	24.	24.	22.	13.	804.
INCHES		.22	.83	1.25	1.25
MM		5.71	21.02	31.87	31.87
AC-FT		420.	1549.	2349.	2349.
THOUS CU M		519.	1911.	2897.	2897.

MAXIMUM STORAGE = 388.

STATION 1030, PLAN 2, RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1018.	1015.	966.	595.	35697.
CMS	29.	29.	27.	17.	1011.
INCHES		.27	1.02	1.58	1.58
MM		6.83	26.00	40.05	40.05
AC-FT		504.	1917.	2952.	2952.
THOUS CU M		621.	2364.	3641.	3641.

MAXIMUM STORAGE = 474.

STATION 1030, PLAN 2, RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1260.	1255.	1196.	743.	44564.
CMS	36.	36.	34.	21.	1262.
INCHES		.33	1.27	1.97	1.97
MM		8.45	32.22	50.00	50.00
AC-FT		623.	2374.	3685.	3685.
THOUS CU M		768.	2929.	4545.	4545.

MAXIMUM STORAGE = 583.

STATION 1030, PLAN 2, RTIO 6

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1535.	1532.	1491.	932.	55937.
CMS	43.	43.	42.	26.	1584.
INCHES		.41	1.58	2.47	2.47
MM		10.31	40.14	62.76	62.76
AC-FT		760.	2958.	4625.	4625.
THOUS CU M		937.	3649.	5705.	5705.

MAXIMUM STORAGE = 707.

STATION 1030, PLAN 2, RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2601.	2505.	2078.	1247.	74837.
CMS	74.	71.	59.	35.	2119.
INCHES		.66	2.20	3.31	3.31
MM		16.87	55.96	83.96	83.96
AC-FT		1243.	4124.	6188.	6188.
THOUS CU M		1533.	5087.	7633.	7633.

MAXIMUM STORAGE = 1103.

STATION 1030, PLAN 2, RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	7263.	6959.	4622.	2363.	141772.
CMS	206.	197.	131.	67.	4015.
INCHES		1.84	4.90	6.26	6.26
MM		46.84	124.44	159.06	159.06
AC-FT		3452.	9171.	11723.	11723.
THOUS CU M		4259.	11313.	14460.	14460.

MAXIMUM STORAGE = 2400.

STATION 1030, PLAN 2, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	12276.	11802.	7596.	3637.	218226.
CMS	348.	334.	215.	103.	6179.
INCHES		3.13	8.05	9.64	9.64
MM		79.45	204.52	244.83	244.83
AC-FT		5855.	15074.	18044.	18044.
THOUS CU M		7222.	18593.	22258.	22258.

MAXIMUM STORAGE = 3555.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
1030	16	3	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 1030 PLAN 1

FREQ	PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
6.000	1030.	0.000	0.000	0.000	0.000
5.500	1130.	0.000	0.000	0.000	0.000
4.500	1380.	1.600	.100	.500	1.000
3.500	1740.	2.400	.200	.700	1.500
2.500	2280.	5.000	.300	1.500	3.200
1.500	3200.	7.200	.300	2.200	4.700
.900	4220.	9.800	.400	2.900	6.500
.700	4800.	11.800	.500	3.500	7.800
.500	5620.	13.900	.600	4.000	9.300
.350	6480.	16.400	.700	4.700	11.000
.250	7340.	20.300	.800	5.800	13.700
.150	8540.	23.100	.900	6.600	15.600
.100	10000.	28.000	1.000	8.000	19.000
.050	12100.	34.500	1.200	10.300	23.000
.020	15100.	44.300	1.500	15.000	27.800
.005	21000.	50.100	1.800	18.100	30.200

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.98	.07	.30	.61
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.51	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.49
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97

FLOOD DAMAGES FOR STATION 1030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	529.	6.000	.284	0.00	0.00	0.00	0.00
2	593.	5.462	1.752	0.00	0.00	0.00	0.00
3	853.	3.097	1.776	0.00	0.00	0.00	0.00
4	1018.	1.769	1.072	0.00	0.00	0.00	0.00
5	1260.	.867	.785	.63	.04	.20	.39
6	1535.	.323	.391	.84	.06	.25	.52
7	2601.	.095	.136	.88	.04	.26	.57
8	7263.	.020	.037	.68	.03	.19	.46
9	12276.	.006	.014	.44	.02	.13	.30
	AVG ANN DMG			3.46	.19	1.03	2.24
	AVG ANN BFT			30.12	1.40	8.99	19.73

SUB-AREA RUNOFF COMPUTATION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	0	0	2	0	0	0	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	-6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL LEVEE AND/OR BYPASS REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 2030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 2030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

STATION 2030, PLAN 1, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1940.	1859.	1220.	579.	34733.
CMS	55.	53.	35.	16.	984.
INCHES		.49	1.29	1.53	1.53
MM		12.52	32.84	38.97	38.97
AC-FT		922.	2420.	2872.	2872.
THOUS CU M		1138.	2985.	3543.	3543.

MAXIMUM STORAGE = 890.

STATION 2030, PLAN 1, RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2921.	2743.	1715.	810.	48621.
CMS	83.	78.	49.	23.	1377.
INCHES		.73	1.82	2.15	2.15
MM		18.47	46.18	54.55	54.55
AC-FT		1361.	3403.	4020.	4020.
THOUS CU M		1679.	4198.	4959.	4959.

MAXIMUM STORAGE = 1197.

STATION 2030, PLAN 1, RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4312.	4092.	2471.	1158.	69450.
CMS	122.	116.	70.	33.	1967.
INCHES		1.08	2.62	3.07	3.07
MM		27.55	66.54	77.92	77.92
AC-FT		2030.	4904.	5743.	5743.
THOUS CU M		2504.	6049.	7083.	7083.

MAXIMUM STORAGE = 1607.

STATION 2030, PLAN 1, RTIO 6

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	6699.	6289.	3747.	1736.	104156.
CMS	190.	178.	106.	49.	2949.
INCHES		1.67	3.97	4.60	4.60
MM		42.34	100.88	116.86	116.86
AC-FT		3120.	7435.	8612.	8612.
THOUS CU M		3849.	9171.	10623.	10623.

MAXIMUM STORAGE = 2271.

STATION 2030, PLAN 1, RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	10191.	9555.	5550.	2545.	152725.
CMS	289.	271.	157.	72.	4325.
INCHES		2.53	5.88	6.75	6.75
MM		64.32	149.44	171.35	171.35
AC-FT		4741.	11014.	12628.	12628.
THOUS CU M		5848.	13585.	15577.	15577.

MAXIMUM STORAGE = 3067.

STATION 2030, PLAN 1, RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	15177.	14262.	8279.	3759.	225518.
CMS	430.	404.	234.	106.	6386.
INCHES		3.78	8.78	9.96	9.96
MM		96.00	222.93	253.02	253.02
AC-FT		7076.	16430.	18647.	18647.
THOUS CU M		8728.	20266.	23001.	23001.

MAXIMUM STORAGE = 4234.

STATION 2030, PLAN 1, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	20603.	19364.	11267.	5087.	305199.
CMS	583.	548.	319.	144.	8642.
INCHES		5.13	11.94	13.48	13.48
MM		130.35	303.38	342.41	342.41
AC-FT		9607.	22359.	25236.	25236.
THOUS CU M		11850.	27580.	31128.	31128.

MAXIMUM STORAGE = 5505.

STATION 2030, PLAN 2, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 2030, PLAN 2, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

STATION 2030, PLAN 2, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1940.	1859.	1220.	579.	34733.
CMS	55.	53.	35.	16.	984.
INCHES		.49	1.29	1.53	1.53
MM		12.52	32.84	38.97	38.97
AC-FT		922.	2420.	2872.	2872.
THOUS CU M		1138.	2985.	3543.	3543.

MAXIMUM STORAGE = 890.

STATION 2030, PLAN 2, RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2921.	2743.	1715.	810.	48621.
CMS	83.	78.	49.	23.	1377.
INCHES		.73	1.82	2.15	2.15
MM		18.47	46.18	54.55	54.55
AC-FT		1361.	3403.	4020.	4020.
THOUS CU M		1679.	4198.	4959.	4959.

MAXIMUM STORAGE = 1197.

STATION 2030, PLAN 2, RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4312.	4092.	2471.	1158.	69450.
CMS	122.	116.	70.	33.	1967.
INCHES		1.08	2.62	3.07	3.07
MM		27.55	66.54	77.92	77.92
AC-FT		2030.	4904.	5743.	5743.
THOUS CU M		2504.	6049.	7083.	7083.

MAXIMUM STORAGE = 1607.

STATION 2030, PLAN 2, RTIO 6

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	6699.	6289.	3747.	1736.	104156.
CMS	190.	178.	106.	49.	2949.
INCHES		1.67	3.97	4.60	4.60
MM		42.34	100.88	116.86	116.86
AC-FT		3120.	7435.	8612.	8612.
THOUS CU M		3849.	9171.	10623.	10623.

MAXIMUM STORAGE = 2271.

STATION 2030, PLAN 2, RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	10191.	9555.	5550.	2545.	152725.
CMS	289.	271.	157.	72.	4325.
INCHES		2.53	5.88	6.75	6.75
MM		64.32	149.44	171.35	171.35
AC-FT		4741.	11014.	12628.	12628.
THOUS CU M		5848.	13585.	15577.	15577.

MAXIMUM STORAGE = 3067.

STATION 2030, PLAN 2, RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	15177.	14262.	8279.	3759.	225518.
CMS	430.	404.	234.	106.	6386.
INCHES		3.78	8.78	9.96	9.96
MM		96.00	222.93	253.02	253.02
AC-FT		7076.	16430.	18647.	18647.
THOUS CU M		8728.	20266.	23001.	23001.

MAXIMUM STORAGE = 4234.

STATION 2030, PLAN 2, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	20603.	19364.	11267.	5087.	305199.
CMS	583.	548.	319.	144.	8642.
INCHES		5.13	11.94	13.48	13.48
MM		130.35	303.38	342.41	342.41
AC-FT		9607.	22359.	25236.	25236.
THOUS CU M		11850.	27580.	31128.	31128.

MAXIMUM STORAGE = 5505.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
2030	16	1	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 2030 PLAN 1

FREQ	PEAK	SUM	TYPE 1
6.000	1030.	0.000	0.000
5.500	1130.	0.000	0.000
4.500	1380.	1.600	1.600
3.500	1740.	2.400	2.400
2.500	2280.	5.000	5.000
1.500	3200.	7.200	7.200
.900	4220.	9.800	9.800
.700	4800.	11.800	11.800
.500	5620.	13.900	13.900
.350	6480.	16.400	16.400
.250	7340.	20.300	20.300
.150	8540.	23.100	23.100
.100	10000.	28.000	28.000
.050	12100.	34.500	34.500
.020	15100.	44.300	44.300
.005	21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58

FLOOD DAMAGES FOR STATION 2030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58
	AVG ANN BFT			.00	0.00

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

2.	2.	2.	3.	4.	7.	16.	31.	43.	49.
55.	58.	64.	66.	70.	76.	88.	108.	160.	250.
330.	385.	413.	450.	453.	423.	383.	333.	278.	225.
183.	154.	129.	104.	83.	64.	50.	39.	30.	23.
18.	14.	10.	8.	7.	6.	5.	5.	4.	4.
3.	3.	3.	3.	3.	3.	3.	2.	2.	2.

********** ********** ********** ********** **********

COMBINE HYDROGRAPHS

COMBINED INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	3	0	0	0	0	1	0	0

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2219.	2137.	1433.	675.	40523.
CMS	63.	61.	41.	19.	1147.
INCHES		.25	.66	.78	.78
MM		6.30	16.89	19.90	19.90
AC-FT		1060.	2844.	3351.	3351.
THOUS CU M		1308.	3508.	4133.	4133.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2576.	2571.	1713.	810.	48626.
CMS	76.	73.	49.	23.	1377.
INCHES		.30	.79	.94	.94
MM		7.57	20.19	23.88	23.88
AC-FT		1275.	3400.	4021.	4021.
THOUS CU M		1573.	4194.	4960.	4960.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4563.	4375.	2851.	1351.	81034.
CMS	129.	124.	81.	38.	2295.
INCHES		.51	1.32	1.57	1.57
MM		12.89	33.60	39.79	39.79
AC-FT		2171.	5658.	6700.	6700.
THOUS CU M		2678.	6980.	8265.	8265.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	6859.	6463.	4009.	1891.	113438.
CMS	194.	183.	114.	54.	3212.
INCHES		.75	1.86	2.19	2.19
MM		19.04	47.25	55.70	55.70
AC-FT		3207.	7957.	9380.	9380.
THOUS CU M		3955.	9815.	11570.	11570.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	10154.	9579.	5772.	2701.	162037.
CMS	288.	271.	163.	76.	4588.
INCHES		1.11	2.68	3.13	3.13
MM		28.22	68.03	79.56	79.56
AC-FT		4752.	11455.	13398.	13398.
THOUS CU M		5862.	14130.	16527.	16527.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 6

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	15693.	14690.	8750.	4050.	243018.
CMS	444.	416.	248.	115.	6881.
INCHES		1.70	4.06	4.70	4.70
MM		43.28	103.12	119.33	119.33
AC-FT		7288.	17365.	20094.	20094.
THOUS CU M		8989.	21420.	24786.	24786.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	23748.	22393.	12956.	5939.	356352.
CMS	672.	634.	367.	168.	10091.
INCHES		2.60	6.01	6.89	6.89
MM		65.97	152.68	174.98	174.98
AC-FT		11110.	25712.	29466.	29466.
THOUS CU M		13704.	31715.	36345.	36345.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	35345.	33502.	19329.	8771.	526232.
CMS	1001.	949.	547.	248.	14901.
INCHES		3.89	8.97	10.17	10.17
MM		98.70	227.78	258.39	258.39
AC-FT		16621.	38357.	43513.	43513.
THOUS CU M		20502.	47313.	53672.	53672.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	48011.	45517.	26298.	11870.	712202.
CMS	1360.	1289.	745.	336.	20167.
INCHES		5.28	12.20	13.77	13.77
MM		134.10	309.90	349.71	349.71
AC-FT		22582.	52188.	58890.	58890.
THOUS CU M		27854.	64372.	72640.	72640.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1664.	1616.	1226.	655.	39303.
CMS	47.	46.	35.	19.	1113.
INCHES		.19	.57	.76	.76
MM		4.76	14.45	19.30	19.30
AC-FT		802.	2434.	3250.	3250.
THOUS CU M		989.	3002.	4009.	4009.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1968.	1906.	1434.	778.	46688.
CMS	56.	54.	41.	22.	1322.
INCHES		.22	.67	.90	.90
MM		5.62	16.90	22.92	22.92
AC-FT		946.	2846.	3860.	3860.
THOUS CU M		1166.	3511.	4762.	4762.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3196.	3092.	2266.	1245.	74707.
CMS	91.	88.	64.	35.	2115.
INCHES		.36	1.05	1.44	1.44
MM		9.11	26.70	36.68	36.68
AC-FT		1534.	4496.	6177.	6177.
THOUS CU M		1892.	5546.	7620.	7620.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 4

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4616.	4394.	3049.	1675.	100514.
CMS	131.	124.	86.	47.	2846.
INCHES		.51	1.41	1.94	1.94
MM		12.94	35.93	49.35	49.35
AC-FT		2180.	6051.	8311.	8311.
THOUS CU M		2689.	7464.	10252.	10252.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 5

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	6625.	6299.	4218.	2286.	137152.
CMS	188.	178.	119.	65.	3884.
INCHES		.73	1.96	2.65	2.65
MM		18.56	49.70	67.34	67.34
AC-FT		3125.	8370.	11341.	11341.
THOUS CU M		3855.	10324.	13989.	13989.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 6

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	9960.	9428.	6100.	3247.	194798.
CMS	282.	267.	173.	92.	5516.
INCHES		1.09	2.83	3.77	3.77
MM		27.78	71.89	95.65	95.65
AC-FT		4678.	12106.	16107.	16107.
THOUS CU M		5770.	14932.	19868.	19868.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 7

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	14769.	14017.	8974.	4641.	278464.
CMS	418.	397.	254.	131.	7885.
INCHES		1.63	4.16	5.38	5.38
MM		41.30	105.75	136.73	136.73
AC-FT		6954.	17809.	23025.	23025.
THOUS CU M		8578.	21967.	28401.	28401.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 8

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	22446.	21805.	14977.	7375.	442485.
CMS	636.	617.	424.	209.	12530.
INCHES		2.53	6.95	8.55	8.55
MM		64.24	176.50	217.27	217.27
AC-FT		10818.	29723.	36588.	36588.
THOUS CU M		13344.	36662.	45131.	45131.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 2 RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	34011.	32584.	21704.	10420.	625228.
CMS	963.	923.	615.	295.	17704.
INCHES		3.78	10.07	12.09	12.09
MM		96.00	255.77	307.00	307.00
AC-FT		16166.	43071.	51698.	51698.
THOUS CU M		19940.	53127.	63769.	63769.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

PROPOSED PUMPING PLANT SITE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
305	1	1	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	0	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	*1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

STATION 305, PLAN 1, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	17.	22.	33.	53.	81.
114.	150.	187.	225.	262.	298.	335.	374.	421.	492.
597.	735.	897.	1078.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1069.	855.
683.	546.	437.	350.	280.	225.	181.	147.	119.	97.

STOR

5.	5.	5.	5.	5.	6.	7.	11.	18.	27.
38.	50.	62.	75.	87.	99.	112.	125.	140.	164.
199.	245.	299.	359.	425.	499.	581.	665.	746.	821.
885.	939.	981.	1011.	1030.	1036.	1032.	1017.	992.	958.
916.	867.	811.	749.	681.	606.	525.	439.	356.	285.
228.	182.	146.	117.	93.	75.	60.	49.	40.	32.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	670.	40227.
CMS	34.	34.	34.	19.	1139.
INCHES		.14	.56	.78	.78
MM		3.54	14.14	19.75	19.75
AC-FT		595.	2381.	3326.	3326.
THOUS CU M		734.	2937.	4103.	4103.

MAXIMUM STORAGE = 1036.

STATION 305, PLAN 1, RTIO 2

OUTFLOW

17.	17.	17.	17.	18.	20.	26.	40.	64.	97.
137.	180.	225.	270.	314.	355.	394.	435.	489.	572.
698.	863.	1059.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1105.	870.	685.	541.	427.	338.

STOR

6.	6.	6.	6.	6.	7.	9.	13.	21.	32.
46.	60.	75.	90.	105.	118.	131.	145.	163.	191.
233.	288.	353.	429.	521.	629.	747.	869.	988.	1098.
1195.	1278.	1347.	1403.	1444.	1471.	1485.	1486.	1475.	1454.
1423.	1384.	1337.	1283.	1223.	1156.	1083.	1003.	919.	831.
740.	648.	554.	460.	368.	290.	228.	180.	142.	113.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	791.	47487.
CMS	34.	34.	34.	22.	1345.
INCHES		.14	.56	.92	.92
MM		3.54	14.14	23.32	23.32
AC-FT		595.	2381.	3927.	3927.
THOUS CU M		734.	2937.	4843.	4843.

MAXIMUM STORAGE = 1486.

STATION 305, PLAN 1, RTIO 3

OUTFLOW

28.	28.	28.	29.	30.	34.	43.	66.	106.	161.
227.	295.	359.	421.	479.	537.	597.	664.	754.	896.
1109.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

9.	9.	9.	10.	10.	11.	14.	22.	35.	54.
76.	98.	120.	140.	160.	179.	199.	221.	251.	299.
370.	471.	612.	798.	1025.	1280.	1553.	1830.	2100.	2355.
2587.	2794.	2976.	3132.	3262.	3367.	3448.	3509.	3551.	3577.
3587.	3583.	3567.	3540.	3504.	3459.	3407.	3349.	3285.	3215.
3137.	3054.	2968.	2879.	2788.	2695.	2602.	2507.	2412.	2317.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	895.	53692.
CMS	34.	34.	34.	25.	1520.
INCHES		.14	.56	1.04	1.04
MM		3.54	14.14	26.36	26.36
AC-FT		595.	2381.	4440.	4440.
THOUS CU M		734.	2937.	5476.	5476.

MAXIMUM STORAGE = 3587.

STATION 305, PLAN 1, RTIO 4

OUTFLOW

39.	39.	39.	40.	42.	47.	61.	92.	148.	224.
307.	389.	471.	553.	634.	715.	800.	896.	1025.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

13.	13.	13.	13.	14.	16.	20.	31.	49.	75.
102.	130.	157.	184.	211.	238.	267.	299.	342.	410.
525.	703.	946.	1252.	1625.	2053.	2512.	2976.	3423.	3835.
4204.	4524.	4800.	5040.	5246.	5420.	5562.	5675.	5761.	5825.
5868.	5894.	5904.	5900.	5883.	5855.	5818.	5773.	5721.	5663.
5599.	5529.	5451.	5369.	5284.	5195.	5105.	5015.	4920.	4827.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	929.	55761.
CMS	34.	34.	34.	26.	1579.
INCHES		.14	.56	1.08	1.08
MM		3.54	14.14	27.38	27.38
AC-FT		595.	2381.	4611.	4611.
THOUS CU M		734.	2937.	5687.	5687.

MAXIMUM STORAGE = 5904.

STATION 305, PLAN 1, RTIO 5

OUTFLOW

56.	56.	56.	57.	60.	67.	87.	132.	210.	308.
412.	522.	635.	750.	866.	983.	1106.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

19.	19.	19.	19.	20.	22.	29.	44.	70.	103.
137.	174.	212.	250.	289.	328.	369.	417.	491.	620.
831.	1135.	1547.	2077.	2708.	3408.	4140.	4872.	5572.	6218.
6798.	7306.	7745.	8118.	8428.	8685.	8901.	9080.	9224.	9338.
9423.	9485.	9526.	9550.	9557.	9550.	9532.	9503.	9465.	9419.
9367.	9309.	9245.	9175.	9099.	9017.	8933.	8845.	8756.	8665.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	966.	57963.
CMS	34.	34.	34.	27.	1641.
INCHES		.14	.56	1.12	1.12
MM		3.54	14.14	28.46	28.46
AC-FT		595.	2381.	4793.	4793.
THOUS CU M		734.	2937.	5912.	5912.

MAXIMUM STORAGE = 9557.

STATION 305, PLAN 1, RTIO 6

OUTFLOW

84.	84.	84.	86.	90.	101.	130.	198.	304.	433.
580.	738.	906.	1079.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

28.	28.	28.	29.	30.	34.	43.	66.	101.	144.
193.	246.	302.	360.	420.	491.	581.	696.	858.	1107.
1489.	2045.	2781.	3683.	4723.	5861.	7047.	8226.	9343.	10367.
11286.	12099.	12807.	13416.	13931.	14357.	14703.	14980.	15206.	15392.
15541.	15657.	15743.	15805.	15846.	15869.	15876.	15870.	15853.	15825.
15788.	15744.	15693.	15636.	15574.	15507.	15434.	15355.	15273.	15188.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1002.	60096.
CMS	34.	34.	34.	28.	1702.
INCHES		.14	.56	1.16	1.16
MM		3.54	14.14	29.51	29.51
AC-FT		595.	2381.	4969.	4969.
THOUS CU M		734.	2937.	6129.	6129.

MAXIMUM STORAGE = 15876.

STATION 305, PLAN 1, RTIO 7

OUTFLOW

123.	123.	124.	125.	132.	148.	190.	281.	422.	601.
810.	1040.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

41.	41.	41.	42.	44.	49.	63.	94.	141.	200.
270.	347.	432.	534.	661.	812.	994.	1215.	1505.	1939.
2601.	3524.	4706.	6153.	7827.	9639.	11499.	13325.	15046.	16609.
17990.	19185.	20215.	21103.	21866.	22508.	23040.	23473.	23818.	24091.
24311.	24490.	24631.	24739.	24819.	24875.	24912.	24932.	24937.	24930.
24912.	24884.	24848.	24804.	24754.	24699.	24640.	24575.	24505.	24430.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1029.	61719.
CMS	34.	34.	34.	29.	1748.
INCHES		.14	.56	1.19	1.19
MM		3.54	14.14	30.31	30.31
AC-FT		595.	2381.	5103.	5103.
THOUS CU M		734.	2937.	6295.	6295.

MAXIMUM STORAGE = 24937.

STATION 305, PLAN 1, RTIO 8

OUTFLOW

182.	182.	183.	185.	195.	219.	279.	401.	594.	850.
1154.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

61.	61.	61.	62.	65.	73.	93.	134.	198.	283.
385.	510.	673.	876.	1115.	1392.	1714.	2106.	2625.	3372.
4448.	5935.	7848.	10135.	12719.	15483.	18305.	21067.	23671.	26042.
28144.	29974.	31546.	32878.	33992.	34924.	35707.	36356.	36885.	37310.
37644.	37905.	38115.	38283.	38414.	38514.	38588.	38640.	38675.	38694.
38699.	38692.	38674.	38648.	38614.	38573.	38526.	38474.	38418.	38357.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1054.	63224.
CMS	34.	34.	34.	30.	1790.
INCHES		.14	.56	1.22	1.22
MM		3.54	14.14	31.04	31.04
AC-FT		595.	2381.	5228.	5228.
THOUS CU M		734.	2937.	6448.	6448.

MAXIMUM STORAGE = 38699.

STATION 305, PLAN 1, RTIO 9

OUTFLOW

246.	246.	247.	251.	264.	296.	370.	523.	778.	1119.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

82.	82.	82.	84.	88.	99.	123.	174.	259.	373.
525.	729.	990.	1304.	1677.	2117.	2629.	3234.	4000.	5069.
6624.	8760.	11438.	14601.	18158.	21952.	25817.	29601.	33166.	36415.
39299.	41814.	43983.	45834.	47387.	48670.	49718.	50581.	51294.	51875.
52340.	52706.	52988.	53212.	53392.	53535.	53646.	53730.	53792.	53835.
53862.	53875.	53876.	53866.	53848.	53821.	53787.	53747.	53701.	53651.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1072.	64341.
CMS	34.	34.	34.	30.	1822.
INCHES		.14	.56	1.24	1.24
MM		3.54	14.14	31.59	31.59
AC-FT		595.	2381.	5320.	5320.
THOUS CU M		734.	2937.	6562.	6562.

MAXIMUM STORAGE = 53876.

PLAN 2

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	9	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	*1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

PUMPING PLANT DATA

PMPMX	PMPMN	PMPON	PWRCST	PANCST	PDSCNT
10000.	0.	1500.	100.	.02300	.05040

CAPACITY=	0.	250.	500.	1000.	2000.	6000.	8000.	10000.	0.	0.
COST=	0.	670.	1000.	1600.	2300.	6000.	7860.	8670.	0.	0.

STATION 305, PLAN 2, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	16.	20.	28.	42.	60.
83.	107.	134.	161.	189.	217.	247.	279.	320.	381.
468.	579.	705.	840.	980.	1112.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1138.	1023.	921.	831.	752.	682.
620.	565.	516.	472.	433.	397.	365.	336.	308.	282.

STOR

5.	5.	5.	5.	5.	5.	7.	9.	14.	20.
28.	36.	45.	54.	63.	72.	82.	93.	107.	127.
156.	193.	235.	280.	327.	371.	411.	449.	486.	520.
548.	572.	589.	601.	607.	607.	601.	590.	573.	551.
524.	494.	459.	420.	379.	341.	307.	277.	251.	227.
207.	188.	172.	157.	144.	132.	122.	112.	103.	94.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1151.	638.	38278.
CMS	34.	34.	33.	18.	1084.
INCHES		.14	.53	.74	.74
MM		3.54	13.56	18.80	18.80
AC-FT		595.	2283.	3165.	3165.
THOUS CU M		734.	2817.	3904.	3904.

MAXIMUM STORAGE = 607.

STATION 305, PLAN 2, RTIO 2

OUTFLOW

17.	17.	17.	17.	18.	19.	23.	33.	50.	72.
99.	129.	161.	194.	227.	259.	292.	329.	376.	448.
552.	683.	831.	991.	1155.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1069.	925.	807.	708.	626.	557.	498.	447.

STOR

6.	6.	6.	6.	6.	6.	8.	11.	17.	24.
33.	43.	54.	65.	76.	86.	97.	110.	125.	149.
184.	228.	277.	330.	385.	442.	503.	566.	628.	685.
735.	779.	816.	847.	870.	886.	894.	897.	892.	882.
867.	846.	821.	792.	759.	721.	679.	633.	583.	529.
473.	413.	356.	308.	269.	236.	209.	186.	166.	149.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	751.	45047.
CMS	34.	34.	34.	21.	1276.
INCHES		.14	.56	.87	.87
MM		3.54	14.14	22.12	22.12
AC-FT		595.	2381.	3725.	3725.
THOUS CU M		734.	2937.	4594.	4594.

MAXIMUM STORAGE = 897.

STATION 305, PLAN 2, RTIO 3

OUTFLOW

28.	28.	28.	28.	29.	32.	39.	55.	83.	121.
165.	213.	260.	308.	356.	405.	457.	517.	596.	713.
880.	1090.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

9.	9.	9.	9.	10.	11.	13.	18.	28.	40.
55.	71.	87.	103.	119.	135.	152.	172.	199.	238.
293.	363.	448.	557.	692.	845.	1006.	1171.	1332.	1484.
1625.	1515.	1392.	1495.	1585.	1424.	1489.	1543.	1350.	1385.
1413.	1432.	1445.	1451.	1450.	1445.	1434.	1419.	1400.	1376.
1347.	1313.	1277.	1237.	1196.	1151.	1105.	1057.	1007.	956.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	2885.	2885.	0.	0.	2885.	0.	0.	2885.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	867.	52032.
CMS	34.	34.	34.	25.	1473.
INCHES		.14	.56	1.01	1.01
MM		3.54	14.14	25.55	25.55
AC-FT		595.	2381.	4302.	4302.
THOUS CU M		734.	2937.	5307.	5307.

MAXIMUM STORAGE = 1625.

STATION 305, PLAN 2, RTIO 4

OUTFLOW

39.	39.	39.	40.	41.	45.	55.	77.	116.	168.
226.	286.	348.	413.	480.	548.	620.	700.	806.	967.
1198.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

13.	13.	13.	13.	14.	15.	18.	26.	39.	56.
75.	95.	116.	138.	160.	183.	207.	233.	269.	322.
399.	509.	660.	850.	1081.	1342.	1620.	1662.	1693.	1705.
1692.	1655.	1596.	1517.	1422.	1548.	1419.	1514.	1356.	1425.
1484.	1533.	1336.	1369.	1395.	1415.	1430.	1439.	1445.	1446.
1443.	1436.	1423.	1407.	1387.	1364.	1338.	1310.	1279.	1247.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	0.	2885.	0.	2885.	0.
0.	0.	2885.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	901.	54053.
CMS	34.	34.	34.	26.	1531.
INCHES		.14	.56	1.04	1.04
MM		3.54	14.14	26.54	26.54
AC-FT		595.	2381.	4469.	4469.
THOUS CU M		734.	2937.	5513.	5513.

MAXIMUM STORAGE = 1705.

STATION 305, PLAN 2, RTIO 5

OUTFLOW

56.	56.	56.	57.	59.	64.	78.	110.	165.	234.
309.	391.	478.	570.	662.	755.	853.	965.	1114.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

19.	19.	19.	19.	20.	21.	26.	37.	55.	78.
103.	130.	159.	190.	221.	252.	284.	322.	371.	453.
589.	787.	1049.	1381.	1774.	1964.	2171.	2375.	2560.	2714.
2831.	2911.	2956.	2967.	2946.	2897.	2827.	2738.	2631.	2508.
2370.	2219.	2058.	1886.	1706.	1518.	1323.	1360.	1391.	1418.
1440.	1457.	1471.	1480.	1485.	1486.	1485.	1480.	1473.	1465.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	937.	56234.
CMS	34.	34.	34.	27.	1592.
INCHES		.14	.56	1.09	1.09
MM		3.54	14.14	27.61	27.61
AC-FT		595.	2381.	4650.	4650.
THOUS CU M		734.	2937.	5736.	5736.

MAXIMUM STORAGE = 2967.

STATION 305, PLAN 2, RTIO 6

OUTFLOW

84.	84.	84.	85.	88.	96.	117.	165.	242.	337.
445.	565.	692.	822.	953.	1087.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

28.	28.	28.	28.	29.	32.	39.	55.	81.	112.
148.	188.	231.	274.	318.	362.	411.	474.	572.	734.
988.	1351.	1819.	2146.	2553.	3012.	3494.	3967.	4402.	4784.
5107.	5373.	5585.	5744.	5853.	5916.	5936.	5921.	5879.	5816.
5734.	5634.	5519.	5391.	5252.	5103.	4946.	4782.	4611.	4434.
4252.	4065.	3874.	3680.	3482.	3280.	3075.	2865.	2653.	2438.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	979.	58746.
CMS	34.	34.	34.	28.	1664.
INCHES		.14	.56	1.14	1.14
MM		3.54	14.14	28.85	28.85
AC-FT		595.	2381.	4858.	4858.
THOUS CU M		734.	2937.	5992.	5992.

MAXIMUM STORAGE = 5936.

STATION 305, PLAN 2, RTIO 7

OUTFLOW

123.	123.	124.	125.	130.	141.	172.	238.	343.	476.
632.	801.	978.	1161.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

41.	41.	41.	42.	43.	47.	57.	79.	114.	159.
211.	267.	326.	387.	455.	539.	644.	778.	964.	1252.
1689.	2049.	2559.	3221.	4011.	4873.	5754.	6610.	7401.	8102.
8705.	9217.	9654.	10030.	10353.	10620.	10833.	10991.	11096.	11154.
11173.	11160.	11120.	11057.	10976.	10880.	10772.	10653.	10524.	10387.
10242.	10090.	9933.	9770.	9603.	9432.	9256.	9078.	8895.	8708.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1013.	60766.
CMS	34.	34.	34.	29.	1721.
INCHES		.14	.56	1.17	1.17
MM		3.54	14.14	29.84	29.84
AC-FT		595.	2381.	5025.	5025.
THOUS CU M		734.	2937.	6198.	6198.

MAXIMUM STORAGE = 11173.

STATION 305, PLAN 2, RTIO 8

OUTFLOW

182.	182.	182.	185.	191.	209.	252.	345.	493.	683.
904.	1143.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

61.	61.	61.	62.	64.	70.	84.	115.	164.	228.
301.	381.	474.	591.	732.	898.	1097.	1343.	1677.	1929.
2398.	3115.	4074.	5246.	6586.	8026.	9516.	11027.	12526.	13968.
15323.	16582.	17737.	18776.	19689.	20484.	21167.	21741.	22215.	22597.
22893.	23112.	23266.	23362.	23406.	23406.	23372.	23312.	23230.	23130.
23016.	22891.	22758.	22617.	22469.	22315.	22156.	21992.	21823.	21651.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1043.	62551.
CMS	34.	34.	34.	30.	1771.
INCHES		.14	.56	1.21	1.21
MM		3.54	14.14	30.71	30.71
AC-FT		595.	2381.	5172.	5172.
THOUS CU M		734.	2937.	6380.	6380.

MAXIMUM STORAGE = 23406.

STATION 305, PLAN 2, RTIO 9

VPMP=1934621.
VOLP=1905040.

PUMPING	CAP COST	PWR COST	TOT ANN $
2885.3	3119.	102.	330.

OUTFLOW

246.	246.	247.	250.	259.	283.	338.	457.	653.	904.
1195.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

82.	82.	82.	83.	86.	94.	113.	152.	218.	301.
398.	518.	674.	864.	1091.	1360.	1676.	1816.	2071.	2534.
3307.	4427.	5857.	7573.	9549.	11739.	14086.	16526.	18985.	21377.
23637.	25730.	27641.	29357.	30870.	32183.	33307.	34262.	35065.	35725.
36256.	36671.	36989.	37228.	37399.	37507.	37561.	37569.	37541.	37485.
37406.	37309.	37197.	37073.	36941.	36802.	36655.	36503.	36346.	36184.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.
2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.	2885.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1065.	63878.
CMS	34.	34.	34.	30.	1809.
INCHES		.14	.56	1.23	1.23
MM		3.54	14.14	31.37	31.37
AC-FT		595.	2381.	5282.	5282.
THOUS CU M		734.	2937.	6515.	6515.

MAXIMUM STORAGE = 37569.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
305	10	2	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 305 PLAN 1

FREQ	STOR	SUM	TYPE 1	TYPE 2
.700	1500.	0.000	0.000	0.000
.600	2300.	48.000	37.500	10.500
.450	4000.	90.000	75.000	15.000
.250	7000.	1177.500	1125.000	52.500
.100	12500.	3255.000	3150.000	105.000
.050	20000.	6052.500	5850.000	202.500
.020	28000.	7350.000	7050.000	300.000
.010	37000.	9390.000	9000.000	390.000
.005	50000.	11190.000	10650.000	540.000
.002	76000.	11835.000	11250.000	585.000

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 305 PLAN 1

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	1036.	.700	0.000	0.00	0.00	0.00
2	1486.	.700	.152	2.02	1.58	.44
3	3587.	.480	.197	21.19	18.50	2.69
4	5904.	.311	.150	112.78	107.26	5.51
5	9557.	.169	.119	240.14	231.56	8.58
6	15876.	.075	.075	311.36	300.95	10.41
7	24937.	.030	.037	232.61	223.56	9.06
8	38699.	.009	.013	110.98	106.13	4.85
9	53876.	.004	.008	79.14	75.28	3.86
	AVG ANN DMG			1110.21	1064.81	45.40

FLOOD DAMAGES FOR STATION 305 PLAN 2

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	607.	.700	0.000	0.00	0.00	0.00
2	897.	.700	.152	0.00	0.00	0.00
3	1625.	.480	.197	.87	.68	.19
4	1705.	.311	.150	2.84	2.21	.63
5	2967.	.169	.119	8.50	7.10	1.41
6	5936.	.075	.075	60.25	57.40	2.86
7	11173.	.030	.037	102.59	99.08	3.50
8	23406.	.009	.013	76.52	73.63	2.89
9	37569.	.004	.008	64.30	61.59	2.71
	AVG ANN DMG			315.88	301.70	14.19
	AVG ANN BFT			794.33	763.12	31.21

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS RATIO 1 .25	RATIO 2 .30	RATIO 3 .50	RATIO 4 .70	RATIO 5 1.00	RATIO 6 1.50	RATIO 7 2.20	RATIO 8 3.25	RATIO 9 4.40
HYDROGRAPH AT	10	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
			(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	110	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	590.	661.	940.	1095.	1340.	1599.	3113.	8608.	14282.
			(	16.72)(	18.73)(	26.61)(	31.01)(	37.96)(	45.29)(	88.15)(	243.74)(	404.42)
ROUTED TO	1030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
	(	90.91)	(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	529.	593.	853.	1018.	1260.	1535.	2601.	7263.	12276.
			(	14.98)(	16.80)(	24.15)(	28.84)(	35.67)(	43.47)(	73.67)(	205.67)(	347.63)
HYDROGRAPH AT	20	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
			(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	2030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
	(	90.91)	(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
			(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	563.42)
HYDROGRAPH AT	30	10.00	1	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
	(	25.90)	(	12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
			2	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
			(	12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
3 COMBINED	30	80.20	1	2219.	2676.	4563.	6859.	10154.	15693.	23748.	35345.	48011.
	(	207.72)	(	62.84)(	75.79)(	129.21)(	194.23)(	287.53)(	444.39)(	672.47)(	1000.86)(	1359.53)
			2	1664.	1968.	3196.	4616.	6625.	9960.	14769.	22446.	34011.
			(	47.13)(	55.74)(	90.51)(	130.72)(	187.60)(	282.04)(	418.21)(	635.59)(	963.08)
ROUTED TO	305	80.20	1	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
	(	207.72)	(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			2	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
			(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			**	PEAK STORAGES IN ACRE FEET (1000 CUBIC METERS) **								
			1	1036.	1486.	3587.	5904.	9557.	15876.	24937.	38699.	53876.
			(	1278.)(	1833.)(	4424.)(	7283.)(	11788.)(	19583.)(	30760.)(	47734.)(	66455.)
			2	607.	897.	1625.	1705.	2967.	5936.	11173.	23406.	37569.
			(	749.)(	1106.)(	2004.)(	2103.)(	3660.)(	7322.)(	13782.)(	28871.)(	46341.)

SYSTEM OPTIMIZATION RESULTS

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
9119.	0.	0.	0.	0.	0.	0.	0.	2885.	0.

SYSTEM COST AND PERFORMANCE SUMMARY
(UNITS SAME AS INPUT = NORMALLY 1000'S OF DOLLARS)

TOTAL SYSTEM CAPITAL COST * * * * * * * * * * * * * * *	7497.	
TOTAL SYSTEM AMORTIZED CAPITAL COST * * * * * * * * *	378.	
TOTAL SYSTEM ANNUAL O,M,POWER AND REPLACEMENT COST *	274.	
TOTAL SYSTEM ANNUAL COST * * * * * * * * * * * * * * *		652.
AVERAGE ANNUAL DAMAGES -- EXISTING CONDITIONS * * * *	1177.	
AVERAGE ANNUAL DAMAGES -- OPTIMIZED SYSTEM * * * * *	353.	
AVERAGE ANNUAL DAMAGE REDUCTION (BENEFITS) * * * * *		824.
AVERAGE ANNUAL SYSTEM NET BENEFITS * * * * * * * * *		173.

***** OPTIMIZATION OBJECTIVE = MAXIMIZE SYSTEM NET BENEFITS *****

TFCST	ANFCST	ANOMPR	TANCST	ANDGBS	ANDMG	TBNFTS	NTBNFT
8740.	440.	301.	742.	1177.	277.	900.	158.

EXHIBIT 4

SIZING RESERVOIR AND PUMPING PLANT

(Hydrologic Performance Constrained)

```
  A        FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
R-A        SIZING RESERVOIR AND PUMPING PLANT
R-A        HYDROLOGIC PERFORMANCE CONSTRAINED
  B      60       1                                                   3
R-1      (7)
  J       2       9       1
  1    0.25    0.30    0.50    0.70    1.00    1.50    2.20    3.25    4.40
R-2   -5000                                                         -5000
N-3
  4
  K       0      10                                       1
  1        POTENTIAL RESERVOIR INFLOW
  M      -1            35.1                                            1
  N      24      24      26      33      50      85     190     375     515     590
  N     660     710     760     800     840     910    1040    1290    1920    3000
  N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N    2200    1840    1540    1250     995     775     605     470     365     280
  N     215     160     120      95      77      66      59      53      49      42
  N      40      38      35      33      30      30      29      27      25      25
  K       1     110                                2       1
  1        PROPOSED RESERVOIR
  Y                              -1       0
  Y                               1       0       1
  1       1                                              -1
  $   25000       0     200   975.0      .5   100.0    .023   .0504
  1       0    2500    4000    5200    6800    9000   11500   15500   21000   30000
  2     965    1000    1015    1030    1045    1060    1075    1090    1105    1120
  3       0    1500    2400    3000    3600    4350    4950    5550    6000    7200
  K       1    1030       1                                1
  1        POTENTIAL CHANNEL MODIFICATION REACH
  Y                               1       1                               0
  1       1                                              -1
  2       0      50     475     940    2135    3080    6300
  3       0     200    1020    2050    6100   10250   24000
R-Z    1030      16       3       1    (1200)    (1.)
  1       6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
  1     .25     .15     .10     .05     .02    .005
  2    1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  2    7340    8540   10000   12100   15100   21000
  3
  4       0       0      .1      .2      .3      .3      .4      .5      .6      .7
  4      .8      .9     1.0     1.2     1.5     1.8
  4       0       0      .5      .7     1.5     2.2     2.9     3.5     4.0     4.7
  4     5.8     6.6     8.0    10.3    15.0    18.1
  4       0       0     1.0     1.5     3.2     4.7     6.5     7.8     9.3    11.0
  4    13.7    15.6    19.0    23.0    27.8    30.2
  K       0      20
  M      -1            35.1                                            1
  N      24      24      26      33      50      85     190     375     515     590
  N     660     710     760     800     840     910    1040    1290    1920    3000
  N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N    2200    1840    1540    1250     995     775     605     470     365     280
  N     215     160     120      95      77      66      59      53      49      42
  N      40      38      35      33      30      30      29      27      25      25
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

( ) = REVISED INPUT DATA



```
K      1    2030       1                                  1
1       POTENTIAL LEVEE AND/OR BYPASS REACH
Y                                 1       1                                  0
1      1                                                 -1
2      0      50     475     940    2135    3080    6300
3      0     200    1020    2050    6100   10250   24000
Z   2030      16       1       1
1      6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
1    .25     .15     .10     .05     .02    .005
2   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
2   7340    8540   10000   12100   15100   21000
3
4      0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
4   20.3    23.1    28.0    34.5    44.3    50.1
K      0      30                                          1
1       LOCAL INFLOW TO FOREBAY POOL
M     -1            10.0                                                   1
N      8       8       9      11      17      28      63     125     170     195
N    220     230     255     265     280     305     350     430     640    1000
N   1320    1540    1650    1800    1810    1690    1530    1330    1110     900
N    730     615     515     415     330     255     200     155     120      93
N     72      54      41      32      26      22      20      18      16      14
N     13      12      11      11      11      10      10       9       9       9
K      3      30                                          1
1       COMBINED INFLOW TO FOREBAY POOL
K      1     305       1                       2          1
1       PROPOSED PUMPING PLANT SITE
Y                                 1       0                                  1
1      1                                                 -1
2      0     400  100000
3      0    1200    1200
Y                                 1                       9                  1
1      1                                                 -1
2      0     400  100000
3      0    1200    1200
*  10000       0    1500     100    .023   .0504
1      0     250     500    1000    2000    6000    8000   10000
2      0     670    1000    1600    2300    6000    7860    8670
R- Z  305      10       2       1    5000     .05
1    .70     .60     .45     .25     .10     .05     .02     .01    .005    .002
2   1500    2300    4000    7000   12500   20000   28000   37000   50000   76000
3
4      0    37.5     75.    1125    3150    5850    7050    9000   10650   11250
4      0    10.5      15    52.5     105   202.5     300     390     540     585
K     99
A
A
A
A
A
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA

FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
SIZING RESERVOIR AND PUMPING PLANT
HYDROLOGIC PERFORMANCE CONSTRAINED

JOB SPECIFICATION

NQ	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
60	1	0	0	0	0	0	0	3	0

JOPER	NWT	LROPT	TRACE
7	0	0	0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 2 NRTIO= 9 LRTIO= 1

RTIOS=	.25	.30	.50	.70	1.00	1.50	2.20	3.25	4.40

SYSTEM OPTIMIZATION

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
-5000.	0.	0.	0.	0.	0.	0.	0.	-5000.	0.

ANORM	CNST
.10	1.00

FIXED COST INPUT

FCAP	FDCNT	FAN
0.	0.0000	0.0000
0.	0.	0.

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1224.953	1200.000	.002	24.953

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	7762.425	5000.000	931.715	2762.425

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.500E+04	.500E+04	931.715	685.365	334.300	.951E+06

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1225.118	1200.000	.002	25.118

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	7815.023	5000.000	1004.728	2815.023

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.495E+04	.495E+04	1004.728	683.630	336.115	.103E+07

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1225.233	1200.000	.002	25.233

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	7867.667	5000.000	1082.021	2867.667

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.490E+04	.490E+04	1082.021	681.895	337.930	.110E+07

OBJECTIVE FUNCTION FOR VARIABLE 1	.9511E+06	.1026E+07	.1104E+07

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214,982	1200,000	,000	14,982
305	6997,027	5000,000	254,482	1997,027

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	1	,500E+04	,583E+04	254,482	708,257	307,809	,260E+06

VAR 1 ADJ FROM 5000,00 TO 5826,40

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214,982	1200,000	,000	14,982
305	7061,828	5000,000	289,154	2061,828

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	9	1	,495E+04	,583E+04	289,154	704,862	309,993	,294E+06

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214,982	1200,000	,000	14,982
305	7126,578	5000,000	327,224	2126,578

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	9	1	,490E+04	,583E+04	327,224	701,468	311,125	,332E+06

OBJECTIVE FUNCTION FOR VARIABLE 9 ,2596E+06 ,2945E+06 ,3324E+06

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214,982	1200,000	,000	14,982
305	6307,512	5000,000	46,763	1307,512

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	,583E+04	,555E+04	46,763	745,838	285,003	,492E+05

VAR 9 ADJ FROM 5000,00 TO 5553,52

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1215,496	1200,000	,000	15,496
305	6349,331	5000,000	53,039	1349,331

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	9	,577E+04	,555E+04	53,039	744,354	286,520	,557E+05

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1216,060	1200,000	,000	16,060
305	6391,365	5000,000	59,963	1391,365

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	9	,571E+04	,555E+04	59,963	742,870	288,041	,628E+05

OBJECTIVE FUNCTION FOR VARIABLE 1 ,4924E+05 ,5571E+05 ,6285E+05

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,351	1200,000	,000	12,351
305	6019,769	5000,000	17,303	1019,769

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	1	,555E+04	,636E+04	17,303	759,453	272,327	,189E+05

VAR 1 ADJ FROM 5826,40 TO 6360,80

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,351	1200,000	,000	12,351
305	6083,313	5000,000	22,036	1083,313

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	9	1	,550E+04	,636E+04	22,036	755,682	274,393	,237E+05

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,351	1200,000	,000	12,351
305	6146,839	5000,000	27,678	1146,839

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	9	1	,544E+04	,636E+04	27,678	751,912	276,459	,295E+05

OBJECTIVE FUNCTION FOR VARIABLE 9 ,1889E+05 ,2373E+05 ,2949E+05

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,351	1200,000	,000	12,351
305	5731,269	5000,000	4,576	731,269

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	,636E+04	,582E+04	4,576	777,459	262,641	,580E+04

VAR 9 ADJ FROM 5553,52 TO 5818,71

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,488	1200,000	,000	12,488
305	5756,224	5000,000	5,233	756,224

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	9	,630E+04	,582E+04	5,233	775,838	264,030	,648E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,670	1200,000	,000	12,670
305	5782,138	5000,000	5,988	782,138

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	9	,623E+04	,582E+04	5,988	774,217	265,434	,726E+04

OBJECTIVE FUNCTION FOR VARIABLE 1 ,5799E+04 ,6481E+04 ,7265E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,494	1200,000	,000	12,494
305	5587,516	5000,000	1,906	587,516

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	9	1	,582E+04	,676E+04	1,906	787,613	254,297	,303E+04

VAR 1 ADJ FROM 6360,80 TO 6757,05

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,494	1200,000	,000	12,494
305	5650,189	5000,000	2,860	650,189

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
2	9	1	,576E+04	,676E+04	2,860	783,663	256,439	,401E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,494	1200,000	,000	12,494
305	5712,839	5000,000	4,131	712,839

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
3	9	1	,570E+04	,676E+04	4,131	779,712	258,607	,533E+04

OBJECTIVE FUNCTION FOR VARIABLE 9 ,3028E+04 ,4014E+04 ,5328E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,494	1200,000	,000	12,494
305	5430,135	5000,000	,548	430,135

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	1	9	,676E+04	,596E+04	,548	797,527	249,265	,162E+04

VAR 9 ADJ FROM 5818,71 TO 5964,73

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,365	1200,000	,000	12,365
305	5453,915	5000,000	,679	453,915

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
2	1	9	,669E+04	,596E+04	,679	795,780	250,624	,176E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,268	1200,000	,000	12,268
305	5477,721	5000,000	,833	477,721

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
3	1	9	,662E+04	,596E+04	,833	794,039	251,997	,192E+04

OBJECTIVE FUNCTION FOR VARIABLE 1 ,1620E+04 ,1757E+04 ,1918E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1213,339	1200,000	,000	13,339

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5315,366	5000,000	,158	315,366

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	9	1	,596E+04	,712E+04	,158	806,049	242,842	,122E+04

VAR 1 ADJ FROM 6757,05 TO 7116,73

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1213,339	1200,000	,000	13,339

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5379,462	5000,000	,332	379,462

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
2	9	1	,591E+04	,712E+04	,332	801,999	245,064	,139E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1213,339	1200,000	,000	13,339

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5443,534	5000,000	,619	443,534

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
3	9	1	,585E+04	,712E+04	,619	797,949	247,286	,169E+04

OBJECTIVE FUNCTION FOR VARIABLE 9 ,1215E+04 ,1395E+04 ,1693E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1213,339	1200,000	,000	13,339

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5250,302	5000,000	,063	250,302

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	1	9	,712E+04	,603E+04	,063	810,168	240,612	,112E+04

VAR 9 ADJ FROM 5964,73 TO 6025,26

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1213,339	1200,000	,000	13,339

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5250,302	5000,000	,063	250,302

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	1	9	,712E+04	,603E+04	,063	810,168	240,612	,112E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212,866	1200,000	,000	12,866

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5272,249	5000,000	,088	272,249

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	9	.705E+04	.603E+04	.088	808.501	241.846	.114E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1212.424	1200.000	.000	12.424

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5294.204	5000.000	.120	294.204

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	9	.697E+04	.603E+04	.120	806.835	243.082	.118E+04

OBJECTIVE FUNCTION FOR VARIABLE 1 .1117E+04 .1143E+04 .1176E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.815	1200.000	.000	14.815

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5182.446	5000.000	.018	182.446

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	1	.603E+04	.734E+04	.018	815.324	236.794	.107E+04

VAR 1 ADJ FROM 7116.73 TO 7336.88

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.815	1200.000	.000	14.815

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5182.446	5000.000	.018	182.446

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	1	.603E+04	.734E+04	.018	815.324	236.794	.107E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.815	1200.000	.000	14.815

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5247.090	5000.000	.060	247.090

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	9	1	.597E+04	.734E+04	.060	811.224	239.021	.111E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.815	1200.000	.000	14.815

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5311.713	5000.000	.151	311.713

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	9	1	.590E+04	.734E+04	.151	807.133	241.265	.121E+04

OBJECTIVE FUNCTION FOR VARIABLE 9 .1071E+04 .1113E+04 .1207E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.815	1200.000	.000	14.815

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5162.435	5000.000	.011	162.435

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.754E+04	.604E+04	.011	816.613	236.138	.106E+04

VAR 9 ADJ FROM 6025.26 TO 6044.14

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.815	1200.000	.000	14.815

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5162.435	5000.000	.011	162.435

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.754E+04	.604E+04	.011	816.613	236.138	.106E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.389	1200.000	.000	14.389

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5184.776	5000.000	.019	184.776

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	9	.726E+04	.604E+04	.019	814.895	237.413	.107E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1213.868	1200.000	.000	13.868

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5207.377	5000.000	.030	207.377

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	9	.719E+04	.604E+04	.030	813.176	238.682	.108E+04

OBJECTIVE FUNCTION FOR VARIABLE 1 .1065E+04 .1072E+04 .1083E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1215.736	1200.000	.000	15.736

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5128.678	5000.000	.005	128.678

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	1	.604E+04	.745E+04	.005	819.310	234.183	.106E+04

VAR 1 ADJ FROM 7336.88 TO 7452.02

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1215.736	1200.000	.000	15.736

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5128.678	5000.000	.005	128.678

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.745E+04	.745E+04	.005	819.310	234.183	.106E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1215.130	1200.000	.000	15.130

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5150.515	5000.000	.008	150.515

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.738E+04	.738E+04	.008	817.564	235.447	.106E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1214.613	1200.000	.000	14.613

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5172.619	5000.000	.014	172.619

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.730E+04	.730E+04	.014	815.819	236.723	.107E+04

OBJECTIVE FUNCTION FOR VARIABLE 1 .1058E+04 .1062E+04 .1068E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1216.320	1200.000	.000	16.320

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
305	5106.498	5000.000	.002	106.498

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	1	.604E+04	.753E+04	.002	821.091	232.898	.106E+04

VAR 1 ADJ FROM 7452.02 TO 7528.06

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

POTENTIAL RESERVOIR INFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
10	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

PROPOSED RESERVOIR

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
110	1	0	0	0	2	1	0	0

PLAN 1 ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	-1	0	0	0	0	0

PLAN 2 ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	1	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

RESERVOIR DATA

CAPMX	CAPMN	COQL	ELEVL	EXPL	COQW	RANCST	RDSCNT	COQT	ELEVT	EXPT
25000.	0.	200.00	975.00	.50	100.00	.0230	.0504	0.00	975.00	0.00

CAPACITY=	0.	2500.	4000.	5200.	6800.	9000.	11500.	15500.	21000.	30000.
ELEVATION=	965.	1000.	1015.	1030.	1045.	1060.	1075.	1090.	1105.	1120.
COST=	0.	1500.	2400.	3000.	3600.	4350.	4950.	5550.	6000.	7200.

OUTLET CREST ELEVATION IS 1049.96 AT STORAGE OF 7528.

SYNTHETIC STORAGE OUTFLOW FUNCTION

STORAGE=	714.	1049.	2053.	4173.	7528.	11320.	14965.	19092.	24199.	30000.
OUTFLOW=	0.	433.	866.	1299.	1732.	13711.	25570.	37401.	49216.	61020.

STATION 110, PLAN 2, RTIO 1

OUTFLOW

6.	6.	6.	6.	7.	8.	10.	16.	26.	37.
50.	62.	74.	86.	99.	111.	124.	141.	168.	213.
280.	360.	437.	468.	498.	527.	551.	569.	581.	587.
588.	585.	580.	571.	561.	549.	536.	522.	508.	493.
477.	462.	447.	432.	391.	353.	319.	288.	260.	235.
212.	191.	173.	156.	141.	128.	115.	104.	94.	85.

STOR

719.	719.	719.	719.	719.	720.	722.	727.	734.	743.
753.	762.	772.	781.	790.	800.	810.	823.	844.	879.
930.	992.	1059.	1130.	1201.	1267.	1322.	1365.	1393.	1407.
1409.	1402.	1389.	1370.	1347.	1319.	1289.	1256.	1222.	1187.
1152.	1117.	1083.	1049.	1016.	987.	961.	937.	915.	896.
878.	862.	848.	835.	823.	813.	803.	795.	787.	780.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	588.	582.	512.	278.	16671.
CMS	17.	16.	14.	8.	472.
INCHES		.15	.54	.74	.74
MM		3.92	13.78	18.70	18.70
AC-FT		289.	1016.	1378.	1378.
THOUS CU M		356.	1255.	1700.	1700.

MAXIMUM STORAGE = 1409.

Several pages of printout deleted

STATION 110, PLAN 2, RTIO 9

RESERVOIR	CAP COST	TOT ANN $
7528.1	3848.	282.

OUTFLOW

106.	106.	106.	108.	116.	134.	182.	290.	442.	542.
590.	675.	764.	858.	908.	957.	1013.	1082.	1182.	1327.
1475.	1659.	4684.	8907.	12302.	14808.	16357.	16954.	16747.	15932.
14722.	13348.	11983.	10633.	9318.	8065.	6904.	5856.	4927.	4117.
3418.	2819.	2310.	1886.	1723.	1708.	1693.	1677.	1662.	1646.
1631.	1615.	1600.	1584.	1569.	1554.	1539.	1524.	1509.	1494.

STOR

796.	796.	796.	798.	804.	818.	855.	938.	1070.	1231.
1413.	1610.	1818.	2034.	2260.	2501.	2774.	3111.	3601.	4392.
5540.	6965.	8463.	9799.	10874.	11657.	12133.	12316.	12253.	12005.
11630.	11205.	10773.	10346.	9929.	9533.	9165.	8833.	8540.	8283.
8062.	7872.	7711.	7577.	7459.	7345.	7226.	7107.	6987.	6867.
6747.	6627.	6507.	6388.	6269.	6151.	6034.	5917.	5801.	5686.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	16954.	15920.	8768.	4122.	247316.
CMS	480.	451.	248.	117.	7003.
INCHES		4.22	9.29	10.92	10.92
MM		107.17	236.09	277.47	277.47
AC-FT		7898.	17400.	20450.	20450.
THOUS CU M		9742.	21462.	25225.	25225.

MAXIMUM STORAGE = 12316.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL CHANNEL MODIFICATION REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 1030, PLAN 1, RTIO 1

Several pages of printout deleted

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
1030	16	3	1	1200.	1.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 1030 PLAN 1

FREQ	PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
6.000	1030.	0.000	0.000	0.000	0.000
5.500	1130.	0.000	0.000	0.000	0.000
4.500	1380.	1.600	.100	.500	1.000
3.500	1740.	2.400	.200	.700	1.500
2.500	2280.	5.000	.300	1.500	3.200
1.500	3200.	7.200	.300	2.200	4.700
.900	4220.	9.800	.400	2.900	6.500
.700	4800.	11.800	.500	3.500	7.800
.500	5620.	13.900	.600	4.000	9.300
.350	6480.	16.400	.700	4.700	11.000
.250	7340.	20.300	.800	5.800	13.700
.150	8540.	23.100	.900	6.600	15.600
.100	10000.	28.000	1.000	8.000	19.000
.050	12100.	34.500	1.200	10.300	23.000
.020	15100.	44.300	1.500	15.000	27.800
.005	21000.	50.100	1.800	18.100	30.200

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.98	.07	.30	.61
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.31	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.49
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97

FLOOD DAMAGES FOR STATION 1030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	526.	6.000	.284	0.00	0.00	0.00	0.00
2	593.	5.462	1.752	0.00	0.00	0.00	0.00
3	847.	3.097	1.776	0.00	0.00	0.00	0.00
4	1008.	1.769	1.072	0.00	0.00	0.00	0.00
5	1257.	.867	.785	.62	.04	.19	.38
6	1548.	.323	.391	1.12	.07	.34	.71
7	4177.	.095	.136	1.37	.06	.40	.91
8	9277.	.020	.037	.90	.03	.26	.61
9	14506.	.006	.014	.54	.02	.17	.35
	AVG ANN DMG			4.54	.22	1.37	2.96
	AVG ANN BFT			29.03	1.37	8.65	19.01

EXCEEDENCE FREQUENCY = 1.000 TARGET FLOW/STOR = 1200. REGULATED FLOW/STOR = 1216.

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	0	0	2	0	0	0	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL LEVEE AND/OR BYPASS REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS.	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	*1.

STORAGE=	0.	50.	475.	940.	2135.	5080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 2030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	269.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 2030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

Several pages of printout deleted

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
2030	16	1	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 2030 PLAN 1

FREQ	PEAK	SUM	TYPE 1
6.000	1036.	0.000	0.000
5.500	1130.	0.000	0.000
4.500	1380.	1.600	1.600
3.500	1740.	2.400	2.400
2.500	2280.	5.000	5.000
1.500	3200.	7.200	7.200
.900	4220.	9.800	9.800
.700	4800.	11.800	11.800
.500	5620.	13.900	13.900
.350	6480.	16.400	16.400
.250	7340.	20.300	20.300
.150	8540.	23.100	23.100
.100	10000.	28.000	28.000
.050	12100.	34.500	34.500
.020	15100.	44.300	44.300
.005	21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58

FLOOD DAMAGES FOR STATION 2030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58
	AVG ANN BFT			.00	0.00

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

2.	2.	2.	3.	4.	7.	16.	31.	43.	49.
55.	58.	64.	66.	70.	76.	88.	108.	160.	250.
330.	385.	413.	450.	453.	423.	383.	333.	278.	225.
183.	154.	129.	104.	83.	64.	50.	39.	30.	23.
18.	14.	10.	8.	7.	6.	5.	5.	4.	4.
3.	3.	3.	3.	3.	3.	3.	2.	2.	2.

********** ********** ********** ********** **********

COMBINE HYDROGRAPHS

COMBINED INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	3	0	0	0	0	1	0	0

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2219.	2137.	1433.	675.	40523.
CMS	63.	61.	41.	19.	1147.
INCHES		.25	.66	.78	.78
MM		6.30	16.89	19.90	19.90
AC-FT		1060.	2844.	3351.	3351.
THOUS CU M		1308.	3508.	4133.	4133.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2676.	2571.	1713.	810.	48626.
CMS	76.	73.	49.	23.	1377.
INCHES		.30	.79	.94	.94
MM		7.57	20.19	23.88	23.88
AC-FT		1275.	3400.	4021.	4021.
THOUS CU M		1573.	4194.	4960.	4960.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4563.	4375.	2851.	1351.	81034.
CMS	129.	124.	81.	38.	2295.
INCHES		.51	1.32	1.57	1.57
MM		12.89	33.60	39.79	39.79
AC-FT		2171.	5658.	6700.	6700.
THOUS CU M		2678.	6980.	8265.	8265.

Several pages of printout deleted

HYDROGRAPH ROUTING

PROPOSED PUMPING PLANT SITE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
305	1	1	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IOVR	LSTR
0.0	0.000	0.00	1	0	0	0	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

STATION 305, PLAN 1, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	17.	22.	33.	53.	81.
114.	150.	187.	225.	262.	298.	335.	374.	421.	492.
597.	735.	897.	1078.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1069.	855.
684.	546.	437.	350.	280.	225.	181.	147.	119.	97.

STOR

5.	5.	5.	5.	5.	6.	7.	11.	18.	27.
38.	50.	62.	75.	87.	99.	112.	125.	140.	164.
199.	245.	299.	359.	425.	499.	581.	665.	746.	821.
885.	939.	981.	1011.	1030.	1036.	1032.	1017.	992.	958.
916.	867.	811.	749.	681.	606.	525.	439.	356.	285.
228.	182.	146.	117.	93.	75.	60.	49.	40.	32.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	670.	40227.
CMS	34.	34.	34.	19.	1139.
INCHES		.14	.56	.78	.78
MM		3.54	14.14	19.75	19.75
AC-FT		595.	2381.	3326.	3326.
THOUS CU M		734.	2937.	4103.	4103.

MAXIMUM STORAGE = 1036.

Several pages of printout deleted

PLAN 2

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	9	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

PUMPING PLANT DATA

PMPMX	PMPMN	PMPON	PWRCST	PANCST	PDSCNT
10000.	0.	1500.	100.	.02300	.05040

CAPACITY=	0.	250.	500.	1000.	2000.	6000.	8000.	10000.	0.	0.
COST=	0.	670.	1000.	1600.	2300.	6000.	7860.	8670.	0.	0.

STATION 305, PLAN 2, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	16.	20.	28.	42.	60.
83.	108.	135.	162.	190.	219.	249.	282.	323.	384.
472.	583.	709.	845.	984.	1116.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1132.	1019.	919.	831.	753.	685.
624.	569.	521.	477.	437.	402.	369.	339.	311.	284.

STOR

5.	5.	5.	5.	5.	5.	7.	9.	14.	20.
28.	36.	45.	54.	63.	73.	83.	94.	108.	128.
157.	194.	236.	282.	328.	372.	412.	450.	487.	521.
549.	572.	590.	602.	608.	608.	601.	590.	572.	550.
523.	492.	457.	418.	377.	340.	306.	277.	251.	228.
208.	190.	174.	159.	146.	134.	123.	113.	104.	95.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1151.	639.	38355.
CMS	34.	34.	33.	18.	1086.
INCHES		.14	.53	.74	.74
MM		3.54	13.56	18.83	18.83
AC-FT		595.	2284.	3171.	3171.
THOUS CU M		734.	2817.	3912.	3912.

MAXIMUM STORAGE = 608.

Several pages of printout deleted

STATION 305, PLAN 2, RTIO 9

VPMP=1991223.
VOLP=2091197.

PUMPING	CAP COST	PWR COST	TOT ANN $
6044.1	6041.	95.	539.

OUTFLOW

246.	246.	247.	250.	259.	283.	338.	458.	654.	905.
1196.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

82.	82.	82.	83.	86.	94.	113.	153.	218.	302.
399.	519.	674.	864.	1091.	1361.	1677.	1557.	1549.	1750.
2261.	3120.	4299.	5801.	7640.	9769.	12119.	14596.	17079.	19469.
21694.	23718.	25522.	27096.	28435.	29542.	30432.	31129.	31652.	32018.
32242.	32348.	32355.	32277.	32129.	31922.	31668.	31377.	31056.	30711.
30348.	29971.	29583.	29185.	28779.	28365.	27944.	27518.	27086.	26649.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	6044.	6044.	6044.
6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.
6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.
6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.
6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.	6044.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1065.	63883.
CMS	34.	34.	34.	30.	1809.
INCHES		.14	.56	1.23	1.23
MM		3.54	14.14	31.37	31.37
AC-FT		595.	2381.	5282.	5282.
THOUS CU M		734.	2937.	6516.	6516.

MAXIMUM STORAGE = 32355.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
305	10	2	1	5000.	.050	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 305 PLAN 1

FREQ	STOR	SUM	TYPE 1	TYPE 2
.700	1500.	0.000	0.000	0.000
.600	2300.	48.000	37.500	10.500
.450	4000.	90.000	75.000	15.000
.250	7000.	1177.500	1125.000	52.500
.100	12500.	3255.000	3150.000	105.000
.050	20000.	6052.500	5850.000	202.500
.020	28000.	7350.000	7050.000	300.000
.010	37000.	9390.000	9000.000	390.000
.005	50000.	11190.000	10650.000	540.000
.002	76000.	11835.000	11250.000	585.000

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 305 PLAN 1

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	1036.	.700	0.000	0.00	0.00	0.00
2	1486.	.700	.152	2.02	1.58	.44
3	3587.	.480	.197	21.19	18.50	2.69
4	5904.	.311	.150	112.78	107.26	5.51
5	9557.	.169	.119	240.14	231.56	8.58
6	15876.	.075	.075	311.36	300.95	10.41
7	24937.	.030	.037	232.61	223.56	9.06
8	38699.	.009	.013	110.98	106.13	4.85
9	53876.	.004	.008	79.14	75.28	3.86
	AVG ANN DMG			1110.21	1064.81	45.40

FLOOD DAMAGES FOR STATION 305 PLAN 2

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	608.	.700	0.000	0.00	0.00	0.00
2	898.	.700	.152	0.00	0.00	0.00
3	1628.	.480	.197	.85	.66	.19
4	1672.	.311	.150	1.44	1.12	.32
5	1775.	.169	.119	2.65	2.06	.58
6	3021.	.075	.075	9.80	8.75	1.06
7	7774.	.030	.037	59.38	57.12	2.26
8	19064.	.009	.013	64.27	62.01	2.26
9	32355.	.004	.008	56.38	54.05	2.34
	AVG ANN DMG			194.78	185.77	9.01
	AVG ANN BFT			915.43	879.04	36.39

EXCEEDENCE FREQUENCY = .050 TARGET FLOW/STOR = 5000. REGULATED FLOW/STOR = 5106.

********** ********** ********** ********** **********

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS RATIO 1 .25	RATIO 2 .30	RATIO 3 .50	RATIO 4 .70	RATIO 5 1.00	RATIO 6 1.50	RATIO 7 2.20	RATIO 8 3.25	RATIO 9 4.40
HYDROGRAPH AT	10	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
			(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	110	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	588.	663.	919.	1086.	1329.	1622.	5264.	11126.	16954.
			(	16.66)(	18.78)(	26.03)(	30.74)(	37.63)(	45.93)(	149.06)(	315.06)(	480.08)
ROUTED TO	1030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
	(	90.91)	(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	526.	593.	847.	1008.	1257.	1548.	4177.	9277.	14506.
			(	14.90)(	16.80)(	23.99)(	28.54)(	35.58)(	43.83)(	118.27)(	262.70)(	410.77)
HYDROGRAPH AT	20	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
			(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	2030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
	(	90.91)	(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
			(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
HYDROGRAPH AT	30	10.00	1	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
	(	25.90)	(	12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
			2	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
			(	12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
3 COMBINED	30	80.20	1	2219.	2676.	4563.	6859.	10154.	15693.	23748.	35345.	48011.
	(	207.72)	(	62.84)(	75.79)(	129.21)(	194.23)(	287.53)(	444.39)(	672.47)(	1000.86)(	1359.53)
			2	1664.	1968.	3201.	4613.	6620.	9953.	14768.	24899.	37599.
			(	47.12)(	55.74)(	90.64)(	130.61)(	187.46)(	281.84)(	418.19)(	705.06)(	1064.69)
ROUTED TO	305	80.20	1	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
	(	207.72)	(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			2	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
			(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			PEAK STORAGES IN ACRE FEET (1000 CUBIC METERS)									
			1	1036.	1486.	3587.	5904.	9557.	15876.	24937.	38699.	53876.
			(	1278.)(	1833.)(	4424.)(	7283.)(	11788.)(	19583.)(	30760.)(	47734.)(	66455.)
			2	608.	898.	1628.	1672.	1775.	3021.	7774.	19064.	32355.
			(	750.)(	1108.)(	2008.)(	2062.)(	2189.)(	3727.)(	9589.)(	23515.)(	39909.)

SYSTEM OPTIMIZATION RESULTS

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
7528.	0.	0.	0.	0.	0.	0.	0.	6044.	0.

SYSTEM COST AND PERFORMANCE SUMMARY
(UNITS SAME AS INPUT - NORMALLY 1000'S OF DOLLARS)

TOTAL SYSTEM CAPITAL COST * * * * * * * * * * * * * * *	9889.	
TOTAL SYSTEM AMORTIZED CAPITAL COST * * * * * * * * * *	498.	
TOTAL SYSTEM ANNUAL O,M,POWER AND REPLACEMENT COST *	323.	
TOTAL SYSTEM ANNUAL COST * * * * * * * * * * * * * * *		821.
AVERAGE ANNUAL DAMAGES -- EXISTING CONDITIONS * * * *	1177.	
AVERAGE ANNUAL DAMAGES -- OPTIMIZED SYSTEM * * * * *	233.	
AVERAGE ANNUAL DAMAGE REDUCTION (BENEFITS) * * * * *		944.
AVERAGE ANNUAL SYSTEM NET BENEFITS * * * * * * * * *		123.

***** OPTIMIZATION OBJECTIVE = MAXIMIZE SYSTEM NET BENEFITS FOR TARGET PROTECTION LEVEL *****

TFCST	ANFCST	ANOMPR	TANCST	ANDGBS	ANDMG	TBNFTS	NTBNFT
7975.	402.	283.	685.	1177.	334.	843.	158.

EXHIBIT 5

SIZING RESERVOIR, PUMPING PLANT AND DIVERSION

(Unconstrained)

```
  A        FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
R-A        SIZING RESERVOIR, PUMPING PLANT AND DIVERSION
R-A        UNCONSTRAINED
  B      60       1                                                   3
R-1      (6)
  J       2       9       1
  1    0.25    0.30    0.50    0.70    1.00    1.50    2.20    3.25    4.40
R-2   -4000                                            -500           -1000
  4
  K       0      10                                       1
  1        POTENTIAL RESERVOIR INFLOW
  M      -1            35.1                                             1
  N      24      24      26      33      50      85     190     375     515     590
  N     660     710     760     800     840     910    1040    1290    1920    3000
  N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N    2200    1840    1540    1250     995     775     605     470     365     280
  N     215     160     120      95      77      66      59      53      49      42
  N      40      38      35      33      30      30      29      27      25      25
  K       1     110                                2       1
  1        PROPOSED RESERVOIR
  Y                              -1       0
  Y                               1       0       1
  1       1                                              -1
  S   25000       0     200   975.0      .5   100.0    .023   .0504
  1       0    2500    4000    5200    6800    9000   11500   15500   21000   30000
  2     965    1000    1015    1030    1045    1060    1075    1090    1105    1120
  3       0    1500    2400    3000    3600    4350    4950    5550    6000    7200
  K       1    1030       1                                1
  1        POTENTIAL CHANNEL MODIFICATION REACH
  Y                               1       1                               0
  1       1                                              -1
  2       0      50     475     940    2135    3080    6300
  3       0     200    1020    2050    6100   10250   24000
  Z    1030      16       3       1
  1       6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
  1     .25     .15     .10     .05     .02    .005
  2    1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  2    7340    8540   10000   12100   15100   21000
  3
  4       0       0      .1      .2      .3      .3      .4      .5      .6      .7
  4      .8      .9     1.0     1.2     1.5     1.8
  4       0       0      .5      .7     1.5     2.2     2.9     3.5     4.0     4.7
  4     5.8     6.6     8.0    10.3    15.0    18.1
  4       0       0     1.0     1.5     3.2     4.7     6.5     7.8     9.3    11.0
  4    13.7    15.6    19.0    23.0    27.8    30.2
  K       0      20
  M      -1            35.1                                             1
  N      24      24      26      33      50      85     190     375     515     590
  N     660     710     760     800     840     910    1040    1290    1920    3000
  N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N    2200    1840    1540    1250     995     775     605     470     365     280
  N     215     160     120      95      77      66      59      53      49      42
  N      40      38      35      33      30      30      29      27      25      25
N-K       1      20                                2       1
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA

```
N-1        DUMMY RESERVOIR TO ACCOMODATE DIVERSION
 Y                                  -1       0
 Y                                   1       0                          7
 1       1                                                   -1
 2       0    2000
 3       0  100000
 +   20000       0    1500    .015   .0504
 1       0    1250    2500    3750    5000    7500   10000   15000   20000
N-2      0    1500    2600    3400    4200    5200    6100    7500    8300
 K       1    2030       1                                1
 1        POTENTIAL LEVEE AND/OR BYPASS REACH
 Y                                   1       1                                0
 1       1                                                   -1
 2       0      50     475     940    2135    3080    6300
 3       0     200    1020    2050    6100   10250   24000
 Z    2030      16       1       1
 1       6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
 1     .25     .15     .10     .05     .02    .005
 2    1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
 2    7340    8540   10000   12100   15100   21000
 3
 4       0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
 4    20.3    23.1    28.0    34.5    44.3    50.1
 K       0      30                                        1
 1        LOCAL INFLOW TO FOREBAY POOL
 M      -1            10.0                                                  1
 N       8       8       9      11      17      28      63     125     170     195
 N     220     230     255     265     280     305     350     430     640    1000
 N    1320    1540    1650    1800    1810    1690    1530    1330    1110     900
 N     730     615     515     415     330     255     200     155     120      93
 N      72      54      41      32      26      22      20      18      16      14
 N      13      12      11      11      11      10      10       9       9       9
 K       3      30                                        1
 1        COMBINED INFLOW TO FOREBAY POOL
 K       1     305       1                       2       1
 1        PROPOSED PUMPING PLANT SITE
 Y                                   1       0                                1
 1       1                                                   -1
 2       0     400  100000
 3       0    1200    1200
 Y                                   1       0                9               1
 1       1                                                   -1
 2       0     400  100000
 3       0    1200    1200
 *   10000       0    1500     100    .023   .0504
 1       0     250     500    1000    2000    6000    8000   10000
 2       0     670    1000    1600    2300    6000    7860    8670
 Z     305      10       2       1
 1     .70     .60     .45     .25     .10     .05     .02     .01    .005    .002
 2    1500    2300    4000    7000   12500   20000   28000   37000   50000   76000
 3
 4       0    37.5     75.    1125    3150    5850    7050    9000   10650   11250
 4       0    10.5      15    52.5     105   202.5     300     390     540     585
 K      99
 A
 A
 A
 A
 A
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA

FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
SIZING RESERVOIR, PUMPING PLANT AND DIVERSION
UNCONSTRAINED

JOB SPECIFICATION

NQ	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
60	1	0	0	0	0	0	0	3	0

JOPER	NWT	LROPT	TRACE
6	0	0	0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 2 NRTIO= 9 LRTIO= 1

RTIOS=	.25	.30	.50	.70	1.00	1.50	2.20	3.25	4.40

SYSTEM OPTIMIZATION

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
-4000.	0.	0.	0.	0.	0.	-500.	0.	-1000.	0.

FIXED COST INPUT

FCAP	FDCNT	FAN
0.	0.0000	0.0000
0.	0.	0.

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.400E+04	.400E+04	0.000	432.840	631.578	.106E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.396E+04	.396E+04	0.000	431.170	634.120	.107E+04

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.392E+04	.392E+04	0.000	429.500	636.695	.107E+04

OBJECTIVE FUNCTION FOR VARIABLE 1	.1064E+04	.1065E+04	.1066E+04

			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
VAR 1 ADJ FROM	4000.00 TO	5055.27	1	7	1	.500E+03	.506E+04	0.000	469.391	582.004	.105E+04
			2	7	1	.495E+03	.506E+04	0.000	469.027	582.496	.105E+04
			3	7	1	.490E+03	.506E+04	0.000	468.664	582.991	.105E+04
OBJECTIVE FUNCTION FOR VARIABLE 7		.1051E+04	.1052E+04			.1052E+04					
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
VAR 7 ADJ FROM	500.00 TO	750.00	1	9	7	.100E+04	.750E+03	0.000	487.619	558.766	.105E+04
			2	9	7	.990E+03	.750E+03	0.000	486.738	559.987	.105E+04
			3	9	7	.980E+03	.750E+03	0.000	485.857	561.207	.105E+04
OBJECTIVE FUNCTION FOR VARIABLE 9		.1046E+04	.1047E+04			.1047E+04					
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
VAR 9 ADJ FROM	1000.00 TO	1500.00	1	1	9	.506E+04	.150E+04	0.000	513.309	505.468	.102E+04
			2	1	9	.500E+04	.150E+04	0.000	511.556	507.597	.102E+04
			3	1	9	.495E+04	.150E+04	0.000	509.803	509.724	.102E+04
OBJECTIVE FUNCTION FOR VARIABLE 1		.1019E+04	.1019E+04			.1020E+04					
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
VAR 1 ADJ FROM	5055.27 TO	7582.91	1	7	1	.750E+03	.758E+04	0.000	577.444	427.657	.101E+04
			2	7	1	.743E+03	.758E+04	0.000	576.896	428.296	.101E+04
			3	7	1	.735E+03	.758E+04	0.000	576.349	428.938	.101E+04
OBJECTIVE FUNCTION FOR VARIABLE 7		.1005E+04	.1005E+04			.1005E+04					

			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	7	.150E+04	.113E+04	0.000	604.961	400.764 .101E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
VAR 7 ADJ FROM	750.00 TO	862.50	1	9	7	.150E+04	.863E+03	0.000	585.680	418.435 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	9	7	.149E+04	.863E+03	0.000	584.910	419.866 .100E+04
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	9	7	.147E+04	.863E+03	0.000	584.139	421.302 .101E+04
OBJECTIVE FUNCTION FOR VARIABLE 9		.1004E+04	.1005E+04				.1005E+04			
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	1	9	.758E+04	.225E+04	0.000	628.344	357.691 .986E+03
VAR 9 ADJ FROM	1500.00 TO	2250.00								
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	1	9	.751E+04	.225E+04	0.000	626.570	359.038 .986E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	1	9	.743E+04	.225E+04	0.000	624.795	360.389 .985E+03
OBJECTIVE FUNCTION FOR VARIABLE 1		.9860E+03	.9856E+03				.9852E+03			
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	7	1	.863E+03	.506E+04	0.000	564.209	432.969 .997E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
VAR 1 ADJ FROM	7582.91 TO	6824.62	1	7	1	.863E+03	.682E+04	0.000	610.603	371.331 .982E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	7	1	.854E+03	.682E+04	0.000	609.970	371.968 .982E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	7	1	.845E+03	.682E+04	0.000	609.337	372.543 .982E+03
OBJECTIVE FUNCTION FOR VARIABLE 7		.9819E+03	.9819E+03				.9819E+03			
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	7	.225E+04	.129E+04	0.000	641.426	346.294 .988E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	7	.225E+04	.992E+03	0.000	620.095	364.329 .984E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	7	.225E+04	.901E+03	0.000	613.450	369.048 .982E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	9	7	.225E+04	.863E+03	0.000	610.603	371.331 .982E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	9	7	.223E+04	.863E+03	0.000	609.075	372.993 .982E+03
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	9	7	.221E+04	.863E+03	0.000	607.547	374.569 .982E+03
OBJECTIVE FUNCTION FOR VARIABLE 9		.9819E+03	.9821E+03				.9821E+03			

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.682E+04	.338E+04	0.000	686.984	307.995	.995E+03
1	1	9	.682E+04	.259E+04	0.000	633.517	350.327	.984E+03
1	1	9	.682E+04	.235E+04	0.000	617.477	364.816	.982E+03
1	1	9	.682E+04	.225E+04	0.000	610.603	371.331	.982E+03
2	1	9	.676E+04	.225E+04	0.000	608.900	372.610	.982E+03
3	1	9	.669E+04	.225E+04	0.000	607.137	373.910	.981E+03

OBJECTIVE FUNCTION FOR VARIABLE 1 .9819E+03 .9815E+03 .9810E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	1	.863E+03	.455E+04	0.000	546.666	454.123	.100E+04
1	7	1	.863E+03	.614E+04	0.000	593.204	390.554	.984E+03
1	7	1	.863E+03	.662E+04	0.000	605.380	375.403	.981E+03

VAR 1 ADJ FROM 6824.62 TO 6619.88

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	7	1	.854E+03	.662E+04	0.000	604.747	376.040	.981E+03
3	7	1	.845E+03	.662E+04	0.000	604.114	376.619	.981E+03

OBJECTIVE FUNCTION FOR VARIABLE 7 .9808E+03 .9808E+03 .9807E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	7	.225E+04	.129E+04	0.000	636.203	350.384	.987E+03
1	9	7	.225E+04	.992E+03	0.000	614.872	368.428	.983E+03
1	9	7	.225E+04	.901E+03	0.000	608.227	373.110	.981E+03
1	9	7	.225E+04	.863E+03	0.000	605.380	375.403	.981E+03
2	9	7	.223E+04	.863E+03	0.000	603.852	377.068	.981E+03
3	9	7	.221E+04	.863E+03	0.000	602.325	378.649	.981E+03

OBJECTIVE FUNCTION FOR VARIABLE 9 .9808E+03 .9809E+03 .9810E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.662E+04	.338E+04	0.000	681.762	312.015	.994E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.662E+04	.259E+04	0.000	628.294	354.389	.983E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.662E+04	.235E+04	0.000	612.254	368.885	.981E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.662E+04	.662E+04	0.000	605.380	375.403	.981E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.655E+04	.655E+04	0.000	603.688	377.223	.981E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.649E+04	.649E+04	0.000	601.999	379.187	.981E+03

OBJECTIVE FUNCTION FOR VARIABLE 1 .9808E+03 .9809E+03 .9812E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	1	.863E+03	.664E+04	0.000	606.020	374.796	.981E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	1	.863E+03	.663E+04	0.000	605.572	375.221	.981E+03

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	1	.863E+03	.662E+04	0.000	605.438	375.348	.981E+03

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

POTENTIAL RESERVOIR INFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
10	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

PROPOSED RESERVOIR

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
110	1	0	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	-1	0	0	0	0	0

PLAN 2
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	1	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

RESERVOIR DATA

CAPMX	CAPMN	COQL	ELEVL	EXPL	COQW	RANCST	RDSCNT	COQT	ELEVT	EXPT
25000.	0.	200.00	975.00	.50	100.00	.0230	.0504	0.00	975.00	0.00

CAPACITY=	0.	2500.	4000.	5200.	6800.	9000.	11500.	15500.	21000.	30000.
ELEVATION=	965.	1000.	1015.	1030.	1045.	1060.	1075.	1090.	1105.	1120.
COST=	0.	1500.	2400.	3000.	3600.	4350.	4950.	5550.	6000.	7200.

OUTLET CREST ELEVATION IS 1043.31 AT STORAGE OF 6620.

SYNTHETIC STORAGE OUTFLOW FUNCTION

STORAGE=	714.	1019.	1934.	3843.	6620.	10590.	14154.	18388.	23648.	30000.
OUTFLOW=	0.	413.	827.	1240.	1653.	15376.	28960.	42512.	56045.	69566.

STATION 110, PLAN 2, RTIO 1

OUTFLOW

6.	6.	6.	6.	7.	8.	11.	17.	27.	39.
51.	64.	77.	89.	101.	114.	128.	145.	172.	219.
288.	371.	429.	461.	494.	524.	549.	568.	581.	587.
588.	585.	579.	571.	560.	548.	534.	519.	504.	489.
473.	457.	442.	427.	409.	367.	330.	297.	266.	239.
215.	193.	174.	156.	141.	126.	114.	102.	92.	83.

STOR

719.	719.	719.	719.	719.	720.	722.	727.	734.	743.
752.	761.	771.	780.	789.	798.	808.	821.	841.	876.
927.	988.	1055.	1126.	1197.	1263.	1319.	1362.	1390.	1404.
1406.	1400.	1386.	1368.	1344.	1317.	1286.	1254.	1220.	1186.
1151.	1117.	1082.	1049.	1016.	985.	958.	933.	911.	891.
873.	857.	843.	830.	818.	808.	798.	790.	782.	776.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	588.	582.	510.	279.	16724.
CMS	17.	16.	14.	8.	474.
INCHES		.15	.54	.74	.74
MM		3.92	13.74	18.76	18.76
AC-FT		289.	1013.	1383.	1383.
THOUS CU M		356.	1249.	1706.	1706.

MAXIMUM STORAGE = 1406.

Several pages of printout deleted

STATION 110, PLAN 2, RTIO 8

OUTFLOW

78.	78.	78.	80.	86.	100.	137.	220.	350.	444.
502.	566.	632.	702.	774.	838.	879.	931.	1007.	1131.
1289.	1443.	1618.	4763.	7931.	10201.	11591.	12179.	12104.	11536.
10651.	9630.	8596.	7580.	6598.	5667.	4811.	4045.	3373.	2792.
2295.	1874.	1646.	1631.	1614.	1597.	1580.	1563.	1546.	1529.
1512.	1495.	1478.	1461.	1445.	1428.	1412.	1396.	1380.	1364.

STOR

772.	772.	772.	773.	778.	788.	815.	876.	972.	1088.
1217.	1357.	1505.	1659.	1818.	1987.	2177.	2416.	2767.	3339.
4172.	5208.	6381.	7520.	8436.	9093.	9495.	9665.	9644.	9479.
9223.	8928.	8629.	8335.	8050.	7781.	7534.	7312.	7118.	6949.
6806.	6684.	6576.	6469.	6358.	6245.	6130.	6016.	5901.	5786.
5671.	5558.	5444.	5332.	5221.	5110.	5000.	4892.	4784.	4678.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	12179.	11377.	6097.	2988.	179258.
CMS	345.	322.	173.	85.	5076.
INCHES		3.02	6.46	7.92	7.92
MM		76.58	164.16	201.12	201.12
AC-FT		5644.	12099.	14822.	14822.
THOUS CU M		6962.	14924.	18283.	18283.

MAXIMUM STORAGE = 9665.

STATION 110, PLAN 2, RTIO 9

RESERVOIR	CAP COST	TOT ANN $
6619.9	3532.	259.

OUTFLOW

106.	106.	106.	109.	116.	136.	185.	298.	434.	507.
589.	678.	772.	847.	896.	949.	1008.	1081.	1187.	1321.
1492.	2688.	7339.	11245.	14335.	16610.	17897.	18164.	17597.	16430.
14943.	13430.	11931.	10483.	9098.	7797.	6607.	5547.	4620.	3820.
3137.	2559.	2074.	1673.	1638.	1622.	1606.	1589.	1572.	1555.
1539.	1522.	1505.	1489.	1472.	1456.	1440.	1424.	1408.	1392.

STOR

792.	792.	793.	794.	800.	814.	851.	934.	1065.	1227.
1409.	1606.	1813.	2030.	2256.	2498.	2772.	3109.	3599.	4390.
5537.	6919.	8265.	9395.	10289.	10914.	11252.	11322.	11173.	10867.
10465.	10027.	9594.	9175.	8774.	8398.	8053.	7746.	7478.	7247.
7049.	6882.	6742.	6626.	6520.	6412.	6301.	6189.	6077.	5964.
5851.	5739.	5627.	5516.	5405.	5295.	5186.	5078.	4970.	4864.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	18164.	16940.	9236.	4286.	257174.
CMS	514.	480.	262.	121.	7282.
INCHES		4.49	9.79	11.36	11.36
MM		114.03	248.69	288.53	288.53
AC-FT		8404.	18329.	21265.	21265.
THOUS CU M		10367.	22608.	26230.	26230.

MAXIMUM STORAGE = 11322.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL CHANNEL MODIFICATION REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 1030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 1030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

Several pages of printout deleted

MAXIMUM STORAGE = 4302.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	IRGT	DGPRT	IAGST	ADSCNT	AANCST	ILPR
1030	16	3	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 1030 PLAN 1

FREQ	PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
6.000	1030.	0.000	0.000	0.000	0.000
5.500	1130.	0.000	0.000	0.000	0.000
4.500	1380.	1.600	.100	.500	1.000
3.500	1740.	2.400	.200	.700	1.500
2.500	2280.	5.000	.300	1.500	3.200
1.500	3200.	7.200	.300	2.200	4.700
.900	4220.	9.800	.400	2.900	6.500
.700	4800.	11.800	.500	3.500	7.800
.500	5620.	13.900	.600	4.000	9.300
.350	6480.	16.400	.700	4.700	11.000
.250	7340.	20.300	.800	5.800	13.700
.150	8540.	23.100	.900	6.600	15.600
.100	10000.	28.000	1.000	8.000	19.000
.050	12100.	34.500	1.200	10.300	23.000
.020	15100.	44.300	1.500	15.000	27.800
.005	21000.	50.100	1.800	18.100	30.200

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.98	.07	.30	.61
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.31	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.49
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97

FLOOD DAMAGES FOR STATION 1030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	525.	6.000	.284	0.00	0.00	0.00	0.00
2	594.	5.462	1.752	0.00	0.00	0.00	0.00
3	838.	3.097	1.776	0.00	0.00	0.00	0.00
4	1005.	1.769	1.072	0.00	0.00	0.00	0.00
5	1252.	.867	.785	.62	.04	.19	.38
6	1583.	.323	.391	1.26	.08	.38	.80
7	5038.	.095	.136	1.67	.07	.48	1.11
8	10185.	.020	.037	1.00	.04	.29	.67
9	15470.	.006	.014	.58	.02	.19	.36
	AVG ANN DMG			5.11	.24	1.54	3.33
	AVG ANN BFT			28.46	1.35	8.48	18.63

SUB-AREA RUNOFF COMPUTATION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	0	0	2	0	0	0	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

DUMMY RESERVOIR TO ACCOMODATE DIVERSION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	1	0	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	-1	0	0	0	0	0

PLAN 2
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	0	7	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	2000.	0.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	100000.	0.	0.	0.	0.	0.	0.	0.	0.

DIVERSION DATA

DVRMX	DVRMN	THDVR	DANCST	DDSCNT
20000.	0.	1500.	.01500	.05040

CAPACITY=	0.	1250.	2500.	3750.	5000.	7500.	10000.	15000.	20000.	0.
COST=	0.	1500.	2600.	3400.	4200.	5200.	6100.	7500.	8300.	0.

STATION 20, PLAN 2, RTIO 1

OUTFLOW

6.	6.	6.	8.	11.	19.	40.	81.	122.	144.
161.	175.	187.	198.	207.	223.	251.	305.	435.	678.
935.	1115.	1243.	1327.	1346.	1296.	1184.	1034.	872.	716.
580.	479.	403.	330.	263.	207.	161.	125.	97.	75.
57.	43.	32.	25.	20.	17.	15.	14.	12.	11.
10.	10.	9.	8.	8.	7.	7.	7.	6.	6.

STOR

0.	0.	0.	0.	0.	0.	1.	2.	2.	3.
3.	3.	4.	4.	4.	4.	5.	6.	9.	14.
19.	22.	25.	27.	27.	26.	24.	21.	17.	14.
12.	10.	8.	7.	5.	4.	3.	3.	2.	1.
1.	1.	1.	1.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1346.	1252.	659.	290.	17375.
CMS	38.	35.	19.	8.	492.
INCHES		.33	.70	.77	.77
MM		8.43	17.74	19.49	19.49
AC-FT		621.	1307.	1437.	1437.
THOUS CU M		766.	1613.	1772.	1772.

MAXIMUM STORAGE = 27.

STATION 20, PLAN 2, RTIO 2

OUTFLOW

7.	7.	8.	9.	14.	23.	48.	98.	146.	173.
193.	210.	224.	237.	249.	267.	301.	366.	522.	813.
1122.	1338.	1492.	1446.	1517.	1549.	1422.	1240.	1047.	859.
696.	575.	483.	396.	316.	248.	193.	150.	117.	90.
69.	52.	39.	30.	24.	20.	18.	16.	15.	13.
12.	12.	11.	10.	9.	9.	9.	8.	8.	7.

STOR

0.	0.	0.	0.	0.	0.	1.	2.	3.	3.
4.	4.	4.	5.	5.	5.	6.	7.	10.	16.
22.	27.	30.	29.	30.	31.	28.	25.	21.	17.
14.	11.	10.	8.	6.	5.	4.	3.	2.	2.
1.	1.	1.	1.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	108.	111.	30.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1549.	1461.	780.	343.	20601.
CMS	44.	41.	22.	10.	583.
INCHES		.39	.83	.91	.91
MM		9.83	21.01	23.11	23.11
AC-FT		725.	1548.	1703.	1703.
THOUS CU M		894.	1910.	2101.	2101.

MAXIMUM STORAGE = 31.

STATION 20, PLAN 2, RTIO 3

OUTFLOW

12.	12.	13.	15.	23.	38.	80.	163.	243.	288.
321.	350.	374.	396.	415.	445.	502.	610.	869.	1355.
1230.	1375.	1621.	1791.	1830.	1729.	1589.	1678.	1657.	1462.
1149.	962.	804.	660.	527.	413.	321.	250.	194.	150.
115.	86.	64.	50.	41.	34.	30.	27.	25.	22.
20.	19.	18.	17.	15.	15.	15.	14.	13.	12.

STOR

0.	0.	0.	0.	0.	1.	2.	3.	5.	6.
6.	7.	7.	8.	8.	9.	10.	12.	17.	27.
25.	27.	32.	36.	37.	35.	32.	34.	33.	29.
23.	19.	16.	13.	11.	8.	6.	5.	4.	3.
2.	2.	1.	1.	1.	1.	1.	1.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
475.	800.	863.	863.	863.	863.	800.	490.	165.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1830.	1712.	1060.	476.	28570.
CMS	52.	48.	30.	13.	809.
INCHES		.45	1.12	1.26	1.26
MM		11.53	28.55	32.05	32.05
AC-FT		850.	2104.	2362.	2362.
THOUS CU M		1048.	2595.	2914.	2914.

MAXIMUM STORAGE = 37.

STATION 20, PLAN 2, RTIO 4

OUTFLOW

17.	17.	18.	22.	32.	53.	111.	228.	341.	403.
450.	490.	523.	554.	581.	623.	703.	855.	1217.	1898.
1456.	2364.	2582.	2865.	2903.	2767.	2451.	2033.	1621.	1746.
1660.	1328.	1132.	922.	738.	578.	450.	351.	272.	210.
161.	121.	90.	70.	57.	48.	42.	38.	35.	31.
28.	27.	25.	23.	22.	21.	21.	19.	18.	17.

STOR

0.	0.	0.	0.	1.	1.	2.	5.	7.	8.
9.	10.	10.	11.	12.	12.	14.	17.	24.	38.
29.	47.	52.	57.	58.	55.	49.	41.	32.	35.
33.	27.	23.	18.	15.	12.	9.	7.	5.	4.
3.	2.	2.	1.	1.	1.	1.	1.	1.	1.
1.	1.	1.	0.	0.	0.	0.	0.	0.	0.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
863.	863.	863.	863.	863.	863.	863.	863.	831.	404.
40.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2903.	2655.	1504.	675.	40475.
CMS	82.	75.	43.	19.	1146.
INCHES		.70	1.59	1.79	1.79
MM		17.87	40.50	45.41	45.41
AC-FT		1317.	2985.	3347.	3347.
THOUS CU M		1625.	3682.	4128.	4128.

MAXIMUM STORAGE = 58.

STATION 20, PLAN 2, RTIO 5

OUTFLOW

24.	24.	25.	31.	45.	75.	159.	325.	487.	575.
642.	700.	747.	791.	830.	891.	1004.	1221.	1739.	1548.
2982.	3562.	4122.	4439.	4524.	4320.	3872.	3273.	2625.	2002.
1676.	1681.	1639.	1310.	1057.	825.	643.	501.	389.	300.
229.	173.	129.	100.	81.	68.	61.	54.	50.	44.
40.	39.	36.	33.	31.	30.	29.	28.	25.	25.

STOR

0.	0.	1.	1.	1.	2.	3.	7.	10.	12.
13.	14.	15.	16.	17.	18.	20.	24.	35.	31.
60.	71.	82.	89.	90.	86.	77.	65.	53.	40.
34.	34.	33.	26.	21.	17.	13.	10.	8.	6.
5.	3.	3.	2.	2.	1.	1.	1.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	0.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	863.
863.	863.	863.	863.	863.	863.	863.	863.	863.	863.
700.	340.	40.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4524.	4140.	2195.	982.	58932.
CMS	128.	117.	62.	28.	1669.
INCHES		1.10	2.33	2.60	2.60
MM		27.87	59.11	66.12	66.12
AC-FT		2054.	4356.	4873.	4873.
THOUS CU M		2533.	5373.	6011.	6011.

MAXIMUM STORAGE = 90.

STATION 20, PLAN 2, RTIO 6

OUTFLOW

36.	36.	38.	46.	68.	113.	239.	488.	730.	863.
963.	1050.	1121.	1187.	1245.	1336.	1506.	1245.	1649.	3237.
4737.	5833.	6594.	7097.	7215.	6912.	6239.	5341.	4369.	3434.
2617.	2011.	1625.	1750.	1661.	1212.	974.	748.	584.	449.
344.	259.	193.	150.	122.	102.	91.	82.	75.	66.
60.	58.	54.	50.	46.	45.	44.	41.	38.	37.

STOR

1.	1.	1.	1.	1.	2.	5.	10.	15.	17.
19.	21.	22.	24.	25.	27.	30.	25.	33.	65.
95.	117.	132.	142.	144.	138.	125.	107.	87.	69.
52.	40.	33.	35.	33.	24.	19.	15.	12.	9.
7.	5.	4.	3.	2.	2.	2.	2.	1.	1.
1.	1.	1.	1.	1.	1.	1.	1.	1.	1.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	435.	863.	863.
863.	863.	863.	863.	863.	863.	863.	863.	863.	863.
863.	863.	810.	375.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	7215.	6648.	3382.	1509.	90555.
CMS	204.	188.	96.	43.	2564.
INCHES		1.76	3.59	4.00	4.00
MM		44.75	91.07	101.60	101.60
AC-FT		3298.	6712.	7488.	7488.
THOUS CU M		4069.	8279.	9236.	9236.

MAXIMUM STORAGE = 144.

STATION 20, PLAN 2, RTIO 7

OUTFLOW

53.	53.	56.	68.	99.	166.	350.	716.	1070.	1266.
1413.	1540.	1412.	1471.	1451.	1413.	1337.	1827.	2961.	5102.
7367.	8951.	10076.	10811.	10985.	10539.	9553.	8236.	6811.	5438.
4240.	3352.	2683.	2041.	1690.	1760.	1434.	1095.	857.	658.
505.	380.	283.	220.	178.	150.	133.	120.	110.	97.
88.	85.	79.	73.	68.	65.	65.	61.	56.	55.

STOR

1.	1.	1.	1.	2.	3.	7.	14.	21.	25.
28.	31.	28.	29.	29.	28.	27.	37.	59.	102.
147.	179.	202.	216.	220.	211.	191.	165.	136.	109.
85.	67.	54.	41.	34.	35.	29.	22.	17.	13.
10.	8.	6.	4.	4.	3.	3.	2.	2.	2.
2.	2.	2.	1.	1.	1.	1.	1.	1.	1.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	172.	260.	348.	502.	788.	863.	863.	863.
863.	863.	863.	863.	863.	863.	863.	863.	863.	863.
863.	863.	863.	863.	689.	205.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	10985.	10153.	5064.	2255.	135273.
CMS	311.	287.	143.	64.	3831.
INCHES		2.69	5.37	5.98	5.98
MM		68.34	136.35	151.77	151.77
AC-FT		5037.	10049.	11185.	11185.
THOUS CU M		6213.	12395.	13797.	13797.

MAXIMUM STORAGE = 220.

STATION 20, PLAN 2, RTIO 8

OUTFLOW

78.	78.	82.	101.	147.	245.	517.	1058.	1581.	1307.
1414.	1421.	1563.	1711.	1834.	2032.	2402.	3105.	4788.	7948.
11295.	13635.	15296.	16383.	16640.	15981.	14524.	12578.	10473.	8446.
6676.	5364.	4375.	3427.	2563.	1823.	1760.	1705.	1236.	983.
742.	563.	417.	326.	263.	222.	197.	177.	162.	143.
130.	126.	116.	109.	100.	97.	96.	89.	83.	81.

STOR

2.	2.	2.	2.	3.	5.	10.	21.	32.	26.
28.	28.	31.	34.	37.	41.	48.	62.	96.	159.
226.	273.	306.	328.	333.	320.	290.	252.	209.	169.
134.	107.	87.	69.	51.	36.	35.	34.	25.	20.
15.	11.	8.	7.	5.	4.	4.	4.	3.	3.
3.	3.	2.	2.	2.	2.	2.	2.	2.	2.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	418.
645.	608.	863.	863.	863.	863.	863.	863.	863.	863.
863.	863.	863.	863.	863.	863.	863.	863.	863.	863.
863.	863.	863.	863.	863.	863.	466.	28.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	16640.	15410.	7711.	3380.	202810.
CMS	471.	436.	218.	96.	5743.
INCHES		4.08	8.17	8.96	8.96
MM		103.73	207.62	227.54	227.54
AC-FT		7645.	15302.	16770.	16770.
THOUS CU M		9430.	18875.	20685.	20685.

MAXIMUM STORAGE = 333.

STATION 20, PLAN 2, RTIO 9

DIVERSION	CAP COST	TOT ANN $
862.5	1035.	68.

OUTFLOW

106.	106.	112.	136.	199.	331.	700.	1432.	1109.	1728.
1943.	2224.	2423.	2621.	2789.	3057.	3556.	4509.	6787.	11065.
15597.	18765.	21014.	22485.	22833.	21941.	19968.	17334.	14484.	11739.
9343.	7567.	6228.	4944.	3775.	2773.	1965.	1739.	1728.	1511.
1012.	760.	566.	441.	357.	300.	266.	239.	219.	194.
176.	170.	157.	147.	136.	131.	129.	121.	112.	109.

STOR

2.	2.	2.	3.	4.	7.	14.	29.	22.	35.
39.	44.	48.	52.	56.	61.	71.	90.	136.	221.
312.	375.	420.	450.	457.	439.	399.	347.	290.	235.
187.	151.	125.	99.	75.	55.	39.	35.	35.	26.
20.	15.	11.	9.	7.	6.	5.	5.	4.	4.
4.	3.	3.	3.	3.	3.	3.	2.	2.	2.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	766.	863.
863.	863.	863.	863.	863.	863.	863.	863.	863.	863.
863.	863.	863.	863.	863.	863.	863.	863.	863.	863.
863.	863.	863.	863.	863.	863.	863.	568.	106.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	22833.	21168.	10733.	4670.	280209.
CMS	647.	599.	304.	132.	7935.
INCHES		5.61	11.38	12.38	12.38
MM		142.49	289.01	314.38	314.38
AC-FT		10502.	21300.	23170.	23170.
THOUS CU M		12954.	26273.	28579.	28579.

MAXIMUM STORAGE = 457.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL LEVEE AND/OR BYPASS REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 2030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 2030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

STATION 2030, PLAN 1, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1940.	1859.	1220.	579.	34733.
CMS	55.	53.	35.	16.	984.
INCHES		.49	1.29	1.53	1.53
MM		12.52	32.84	38.97	38.97
AC-FT		922.	2420.	2872.	2872.
THOUS CU M		1138.	2985.	3543.	3543.

MAXIMUM STORAGE = 890.

Several pages of printout deleted

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAGST	ADSCNT	AANCST	ILPR
2030	16	1	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 2030 PLAN 1

FREQ	PEAK	SUM	TYPE 1
6.000	1030.	0.000	0.000
5.500	1130.	0.000	0.000
4.500	1380.	1.600	1.600
3.500	1740.	2.400	2.400
2.500	2280.	5.000	5.000
1.500	3200.	7.200	7.200
.900	4220.	9.800	9.800
.700	4800.	11.800	11.800
.500	5620.	13.900	13.900
.350	6480.	16.400	16.400
.250	7340.	20.300	20.300
.150	8540.	23.100	23.100
.100	10000.	28.000	28.000
.050	12100.	34.500	34.500
.020	15100.	44.300	44.300
.005	21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.98	.98
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58

FLOOD DAMAGES FOR STATION 2030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	940.	6.000	.284	0.00	0.00
2	1115.	5.462	1.752	.33	.33
3	1430.	3.097	1.776	2.86	2.86
4	2080.	1.769	1.072	4.28	4.28
5	3507.	.867	.785	6.06	6.06
6	5756.	.323	.391	5.48	5.48
7	9253.	.095	.136	3.33	3.33
8	14254.	.020	.037	1.43	1.43
9	19694.	.006	.014	.65	.65
	AVG ANN DMG			24.42	24.42
	AVG ANN BFT			9.16	9.16

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

2.	2.	2.	3.	4.	7.	16.	31.	43.	49.
55.	58.	64.	66.	70.	76.	88.	108.	160.	250.
330.	385.	413.	450.	453.	423.	383.	333.	278.	225.
183.	154.	129.	104.	83.	64.	50.	39.	30.	23.
18.	14.	10.	8.	7.	6.	5.	5.	4.	4.
3.	3.	3.	3.	3.	3.	3.	2.	2.	2.

********** ********** ********** ********** **********

COMBINE HYDROGRAPHS

COMBINED INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	3	0	0	0	0	1	0	0

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2219.	2117.	1433.	675.	40523.
CMS	63.	61.	41.	19.	1147.
INCHES		.25	.66	.78	.78
MM		6.30	16.89	19.90	19.90
AC-FT		1060.	2844.	3351.	3351.
THOUS CU M		1308.	3508.	4133.	4133.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2676.	2571.	1713.	810.	48626.
CMS	76.	73.	49.	23.	1377.
INCHES		.30	.79	.94	.94
MM		7.57	20.19	23.88	23.88
AC-FT		1275.	3400.	4021.	4021.
THOUS CU M		1573.	4194.	4960.	4960.

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	4563.	4375.	2851.	1351.	81034.
CMS	129.	124.	81.	38.	2295.
INCHES		.51	1.32	1.57	1.57
MM		12.89	33.60	39.79	39.79
AC-FT		2171.	5658.	6700.	6700.
THOUS CU M		2678.	6980.	8265.	8265.

Several pages of printout deleted

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

PROPOSED PUMPING PLANT SITE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
305	1	1	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	0	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

STATION 305, PLAN 1, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	17.	22.	33.	53.	81.
114.	150.	187.	225.	262.	298.	335.	374.	421.	492.
597.	735.	897.	1078.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1069.	855.
683.	546.	437.	350.	280.	225.	181.	147.	119.	97.

STOR

5.	5.	5.	5.	5.	6.	7.	11.	18.	27.
38.	50.	62.	75.	87.	99.	112.	125.	140.	164.
199.	245.	299.	359.	425.	499.	581.	665.	746.	821.
885.	939.	981.	1011.	1030.	1036.	1032.	1017.	992.	958.
916.	867.	811.	749.	681.	606.	525.	439.	356.	285.
228.	182.	146.	117.	93.	75.	60.	49.	40.	32.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	670.	40227.
CMS	34.	34.	34.	19.	1139.
INCHES		.14	.56	.78	.78
MM		3.54	14.14	19.75	19.75
AC-FT		595.	2381.	3326.	3326.
THOUS CU M		734.	2937.	4103.	4103.

MAXIMUM STORAGE = 1036.

Several pages of printout deleted

PLAN 2

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	9	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

PUMPING PLANT DATA

PMPMX	PMPMN	PMPON	PWRCST	PANCST	PDSCNT
10000.	0.	1500.	100.	.02300	.05040

CAPACITY=	0.	250.	500.	1000.	2000.	6000.	8000.	10000.	0.	0.
COST=	0.	670.	1000.	1600.	2300.	6000.	7860.	8670.	0.	0.

STATION 305, PLAN 2, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	16.	19.	27.	40.	58.
80.	105.	131.	159.	188.	216.	247.	280.	321.	381.
466.	574.	697.	831.	968.	1099.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1150.	1035.	934.	845.	766.	696.
634.	578.	529.	484.	444.	407.	374.	344.	315.	287.

STOR

5.	5.	5.	5.	5.	5.	6.	9.	13.	19.
27.	35.	44.	53.	63.	72.	82.	93.	107.	127.
155.	191.	232.	277.	323.	366.	406.	443.	480.	514.
543.	568.	586.	600.	607.	607.	602.	592.	575.	554.
528.	497.	462.	424.	383.	345.	311.	282.	255.	232.
211.	193.	176.	161.	148.	136.	125.	115.	105.	96.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1151.	640.	38396.
CMS	34.	34.	33.	18.	1087.
INCHES		.14	.53	.74	.74
MM		3.54	13.57	18.85	18.85
AC-FT		595.	2285.	3175.	3175.
THOUS CU M		734.	2818.	3916.	3916.

MAXIMUM STORAGE = 607.

Several pages of printout deleted

STATION 305, PLAN 2, RTIO 8

OUTFLOW

182.	182.	182.	184.	191.	207.	248.	337.	480.	660.
857.	1056.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

61.	61.	61.	61.	64.	69.	83.	112.	160.	220.
286.	352.	421.	501.	599.	717.	860.	1041.	1290.	1680.
2091.	2731.	3605.	4716.	6052.	7589.	9291.	11100.	12946.	14752.
16458.	18024.	19432.	20669.	21737.	22645.	23405.	24030.	24540.	24949.
25265.	25500.	25666.	25773.	25831.	25851.	25840.	25805.	25753.	25686.
25607.	25518.	25419.	25312.	25198.	25077.	24951.	24819.	24683.	24543.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1039.	62366.
CMS	34.	34.	34.	29.	1766.
INCHES		.14	.56	1.21	1.21
MM		3.54	14.14	30.62	30.62
AC-FT		595.	2381.	5157.	5157.
THOUS CU M		734.	2937.	6361.	6361.

MAXIMUM STORAGE = 25851.

STATION 305, PLAN 2, RTIO 9

VPMP=1917028.
VOLP=2069869.

PUMPING	CAP COST	PWR COST	TOT ANN $
2250.0	2531.	93.	278.

OUTFLOW

246.	246.	247.	250.	258.	280.	333.	447.	626.	839.
1073.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

82.	82.	82.	83.	86.	93.	111.	149.	209.	280.
358.	446.	557.	698.	865.	1063.	1298.	1591.	1807.	2219.
2913.	3940.	5312.	7058.	9193.	11666.	14395.	17260.	20134.	22907.
25502.	27875.	30009.	31892.	33524.	34909.	36071.	37034.	37823.	38458.
38960.	39350.	39645.	39858.	40004.	40093.	40137.	40146.	40126.	40085.
40028.	39958.	39876.	39785.	39685.	39577.	39462.	39342.	39216.	39085.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.
2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.	2250.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1061.	63646.
CMS	34.	34.	34.	30.	1802.
INCHES		.14	.56	1.23	1.23
MM		3.54	14.14	31.25	31.25
AC-FT		595.	2381.	5263.	5263.
THOUS CU M		734.	2937.	6491.	6491.

MAXIMUM STORAGE = 40146.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	OGPRT	IAGST	ADSCNT	AANCST	ILPR
305	10	2	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 305 PLAN 1

FREQ	STOR	SUM	TYPE 1	TYPE 2
.700	1500.	0.000	0.000	0.000
.600	2300.	48.000	37.500	10.500
.450	4000.	90.000	75.000	15.000
.250	7000.	1177.500	1125.000	52.500
.100	12500.	3255.000	3150.000	105.000
.050	20000.	6052.500	5850.000	202.500
.020	28000.	7350.000	7050.000	300.000
.010	37000.	9390.000	9000.000	390.000
.005	50000.	11190.000	10650.000	540.000
.002	76000.	11835.000	11250.000	585.000

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 305 PLAN 1

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	1036.	.700	0.000	0.00	0.00	0.00
2	1486.	.700	.152	2.02	1.58	.44
3	3587.	.480	.197	21.19	18.50	2.69
4	5904.	.311	.150	112.78	107.26	5.51
5	9557.	.169	.119	240.14	231.56	8.58
6	15876.	.075	.075	311.36	300.95	10.41
7	24937.	.030	.037	232.61	223.56	9.06
8	38699.	.009	.013	110.98	106.13	4.85
9	53876.	.004	.008	79.14	75.28	3.86
	AVG ANN DMG			1110.21	1064.81	45.40

FLOOD DAMAGES FOR STATION 305 PLAN 2

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	607.	.700	0.000	0.00	0.00	0.00
2	882.	.700	.152	0.00	0.00	0.00
3	1552.	.480	.197	.35	.27	.08
4	1596.	.311	.150	1.80	1.40	.40
5	2659.	.169	.119	6.64	5.36	1.28
6	5855.	.075	.075	60.99	58.15	2.84
7	13353.	.030	.037	126.39	122.15	4.24
8	25851.	.009	.013	82.30	79.08	3.23
9	40146.	.004	.008	67.39	64.48	2.91
	AVG ANN DMG			345.87	330.89	14.98
	AVG ANN BET			764.34	733.92	30.42

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS RATIO 1 .25	RATIO 2 .30	RATIO 3 .50	RATIO 4 .70	RATIO 5 1.00	RATIO 6 1.50	RATIO 7 2.20	RATIO 8 3.25	RATIO 9 4.40
HYDROGRAPH AT	10	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
			(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	110	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	588.	666.	909.	1085.	1324.	1758.	6435.	12179.	18164.
			(	16.65)(	18.86)(	25.73)(	30.72)(	37.48)(	49.78)(	182.21)(	344.86)(	514.34)
ROUTED TO	1030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
	(	90.91)	(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	525.	594.	838.	1005.	1252.	1583.	5038.	10185.	15470.
			(	14.86)(	16.83)(	23.73)(	28.47)(	35.46)(	44.83)(	142.65)(	288.41)(	438.05)
HYDROGRAPH AT	20	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
			(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	20	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
	(	90.91)	(	38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1346.	1549.	1830.	2903.	4524.	7215.	10985.	16640.	22833.
			(	38.12)(	43.86)(	51.82)(	82.20)(	128.12)(	204.32)(	311.07)(	471.20)(	646.57)
ROUTED TO	2030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
	(	90.91)	(	26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	940.	1115.	1430.	2080.	3507.	5756.	9253.	14254.	19694.
			(	26.61)(	31.56)(	40.49)(	58.90)(	99.31)(	162.98)(	262.02)(	403.64)(	557.67)
HYDROGRAPH AT	30	10.00	1	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
	(	25.90)	(	12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
			2	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
			(	12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
3 COMBINED	30	80.20	1	2219.	2676.	4563.	6859.	10154.	15693.	23748.	35345.	48011.
	(	207.72)	(	62.84)(	75.79)(	129.21)(	194.23)(	287.53)(	444.39)(	672.47)(	1000.86)(	1359.53)
			2	1660.	1939.	2602.	3752.	5793.	8998.	14293.	25799.	38535.
			(	46.99)(	54.90)(	73.67)(	106.25)(	164.05)(	254.81)(	404.74)(	730.54)(	1091.19)
ROUTED TO	305	80.20	1	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
	(	207.72)	(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			2	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
			(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			PEAK STORAGES IN ACRE FEET (1000 CUBIC METERS)									
			1	1036.	1486.	3587.	5904.	9557.	15876.	24937.	38699.	53876.
			(	1278.)(	1833.)(	4424.)(	7283.)(	11788.)(	19583.)(	30760.)(	47734.)(	66455.)
			2	607.	882.	1552.	1596.	2659.	5655.	13353.	25851.	40146.
			(	749.)(	1088.)(	1914.)(	1968.)(	3280.)(	6975.)(	16471.)(	31887.)(	49519.)

SYSTEM OPTIMIZATION RESULTS

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
6620.	0.	0.	0.	0.	0.	663.	0.	2250.	0.

SYSTEM COST AND PERFORMANCE SUMMARY
(UNITS SAME AS INPUT - NORMALLY 1000'S OF DOLLARS)

TOTAL SYSTEM CAPITAL COST * * * * * * * * * * * * * * *	7099.	
TOTAL SYSTEM AMORTIZED CAPITAL COST * * * * * * * * * *	358.	
TOTAL SYSTEM ANNUAL O,M,POWER AND REPLACEMENT COST *	248.	
TOTAL SYSTEM ANNUAL COST * * * * * * * * * * * * * * *		605.
AVERAGE ANNUAL DAMAGES -- EXISTING CONDITIONS * * * *	1177.	
AVERAGE ANNUAL DAMAGES -- OPTIMIZED SYSTEM * * * * * *	375.	
AVERAGE ANNUAL DAMAGE REDUCTION (BENEFITS) * * * * * *		802.
AVERAGE ANNUAL SYSTEM NET BENEFITS * * * * * * * * * *		197.

***** OPTIMIZATION OBJECTIVE - MAXIMIZE SYSTEM NET BENEFITS *****

TFCST	ANFCST	ANOMPR	TANCST	ANDGBS	ANDMG	TBNFTS	NTBNFT
4600.	232.	201.	433.	1177.	632.	546.	113.

EXHIBIT 6

SIZING LEVEE AND CHANNEL MODIFICATION

(Unconstrained)

```
  A        FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
R-A        SIZING LEVEE AND CHANNEL MODIFICATION
R-A        UNCONSTRAINED
  B     60       1                                                   3
  1      6
  J      2       9       1
  1   0.25    0.30    0.50    0.70    1.00    1.50    2.20    3.25    4.40
R-2           -2000   -2000
  4
  K      0      10                                    1
  1        POTENTIAL RESERVOIR INFLOW
  M     -1              35.1                                        1
  N     24      24      26      33      50      85     190     375     515     590
  N    660     710     760     800     840     910    1040    1290    1920    3000
  N   3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
  N   2200    1840    1540    1250     995     775     605     470     365     280
  N    215     160     120      95      77      66      59      53      49      42
  N     40      38      35      33      30      30      29      27      25      25
  K      1    1030       1                                    1
  1        POTENTIAL CHANNEL MODIFICATION REACH
  Y                               1       1                           0
  1      1                                                  -1
  2      0      50     475     940    2135    3080    6300
  3      0     200    1020    2050    6100   10250   24000
  Z   1030      16       3       0                                           2
  1      6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
  1    .25     .15     .10     .05     .02    .005
  2   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  2   7340    8540   10000   12100   15100   21000
  3
  4      0       0      .1      .2      .3      .3      .4      .5      .6      .7
  4     .8      .9     1.0     1.2     1.5     1.8
  4      0       0      .5      .7     1.5     2.2     2.9     3.5     4.0     4.7
  4    5.8     6.6     8.0    10.3    15.0    18.1
  4      0       0     1.0     1.5     3.2     4.7     6.5     7.8     9.3    11.0
  4   13.7    15.6    19.0    23.0    27.8    30.2
N-7   8300    1700    .023   .0504
  1   1700    5000    5500    7000    8300    9300
  2     42     103     149     222     283     340
  3   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
  3   7340    8540   10000   12100   15100   21000
  4      0       0       0     .01     .14     .25     .36     .43     .53     .62
  4    .69     .82     .97    1.17    1.43    1.76
  4      0       0       0     .08     .95    1.73    2.53    2.73    3.53    4.08
  4   5.01    6.16    7.70    9.90   14.08   17.51
  4      0       0       0     .13    1.73    3.44    5.85    7.23    8.91   10.63
  4  13.11   15.03   18.61   22.09   27.00   29.32
  5      0       0       0       0       0       0       0       0       0       0
  5      0     .04     .25     .42     .64     .99
  5      0       0       0       0       0       0       0       0       0       0
  5      0     .25    1.75    3.18    5.04    7.98
  5      0       0       0       0       0       0       0       0       0       0
N-5      0     .44    3.50    7.15   12.29   16.86
  K      0      20
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA

```
M     -1            35.1                                                  1
N     24      24      26      33      50      85     190     375     515     590
N    660     710     760     800     840     910    1040    1290    1920    3000
N   3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
N   2200    1840    1540    1250     995     775     605     470     365     280
N    215     160     120      95      77      66      59      53      49      42
N     40      38      35      33      30      30      29      27      25      25
K      1    2030       1                                1
1       POTENTIAL LEVEE AND/OR BYPASS REACH
Y                                1       1                                0
1      1                                                -1
2      0      50     475     940    2135    3080    6300
3      0     200    1020    2050    6100   10250   24000
Z   2030      16       1       (0)                                                (3)
1      6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     .35
1    .25     .15     .10     .05     .02    .005
2   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
2   7340    8540   10000   12100   15100   21000
3
4      0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
4   20.3    23.1    28.0    34.5    44.3    50.1
N- /  8300    1700    .023   .0504
1   1700    5000    5500    7000    8300    9300
2     42     103     149     222     283     340
3   1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
3   7340    8540   10000   12100   15100   21000
4      0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
4   20.3    23.1    28.0    34.5    44.3    50.1
5      0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
N- 5  20.3    23.1    28.0    34.5    44.3    50.1
K      0      30                                        1
1       LOCAL INFLOW TO FOREBAY POOL
M     -1            10.0                                                  1
N      8       8       9      11      17      28      63     125     170     195
N    220     230     255     265     280     305     350     430     640    1000
N   1320    1540    1650    1800    1810    1690    1530    1330    1110     900
N    730     615     515     415     330     255     200     155     120      93
N     72      54      41      32      26      22      20      18      16      14
N     13      12      11      11      11      10      10       9       9       9
K      3      30                                        1
1       COMBINED INFLOW TO FOREBAY POOL
K      1     305                                        1
1       GRAVITY OUTLET THROUGH LEVEE
Y                                1       1
1      1                                                -1
2      0     400  100000
3      0    1200    1200
K     99
A
A
A
A
A
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

( ) = REVISED INPUT DATA

NOTE: DAMAGE REACH 305 OMITTED IN ORDER TO COMPARE THE RELATIVE EFFECTS OF THE CHANNEL AND LEVEE IN REDUCING DOWNSTREAM DAMAGES.

FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
SIZING LEVEE AND CHANNEL MODIFICATION
UNCONSTRAINED

JOB SPECIFICATION

NO	NHR	NMIN	IDAY	IHR	IMIN	METRC	IPLT	IPRT	NSTAN
60	1	0	0	0	0	0	0	3	0

JOPER	NWT	LROPT	TRACE
6	0	0	0

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 2 NRTIO= 9 LRTIO= 1

RTIOS= .25 .30 .50 .70 1.00 1.50 2.20 3.25 4.40

SYSTEM OPTIMIZATION

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
0.	-2000.	-2000.	0.	0.	0.	0.	0.	0.	0.

FIXED COST INPUT

FCAP	FDCNT	FAN
0.	0.0000	0.0000
0.	0.	0.

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	2	.200E+04	.200E+04	0.000	6.980	52.791	.598E+02
2	2	2	.198E+04	.198E+04	0.000	6.953	52.965	.599E+02
3	2	2	.196E+04	.196E+04	0.000	6.925	53.165	.601E+02

OBJECTIVE FUNCTION FOR VARIABLE 2 .5977E+02 .5992E+02 .6009E+02

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	3	2	.200E+04	.210E+04	0.000	7.121	51.766	.589E+02
2	3	2	.198E+04	.210E+04	0.000	7.094	51.766	.589E+02
3	3	2	.196E+04	.210E+04	0.000	7.067	51.912	.590E+02

VAR 2 ADJ FROM 2000.00 TO 2104.43

OBJECTIVE FUNCTION FOR VARIABLE 3 .5889E+02 .5886E+02 .5898E+02

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	3	.210E+04	.199E+04	0.000	7.103	51.766	.589E+02
2	2	3	.208E+04	.199E+04	0.000	7.074	51.972	.590E+02
3	2	3	.206E+04	.199E+04	0.000	7.046	52.179	.592E+02

VAR 3 ADJ FROM 2000.00 TO 1986.30

OBJECTIVE FUNCTION FOR VARIABLE 2 .5887E+02 .5905E+02 .5922E+02

				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	3	2	.199E+04	.316E+04	0.000	8.530	43.966 .525E+02
VAR 2 ADJ FROM	2104.43 TO	3156.65									
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				2	3	2	.197E+04	.316E+04	0.000	8.503	44.112 .526E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				3	3	2	.195E+04	.316E+04	0.000	8.477	44.254 .527E+02
OBJECTIVE FUNCTION FOR VARIABLE 3		.5250E+02	.5262E+02				.5273E+02				
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	2	3	.316E+04	.298E+04	0.000	9.878	37.239 .471E+02
VAR 3 ADJ FROM	1986.30 TO	2979.44									
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				2	2	3	.313E+04	.298E+04	0.000	9.835	37.416 .473E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				3	2	3	.309E+04	.298E+04	0.000	9.792	37.596 .474E+02
OBJECTIVE FUNCTION FOR VARIABLE 2		.4712E+02	.4725E+02				.4739E+02				
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	3	2	.298E+04	.473E+04	0.000	12.019	30.881 .429E+02
VAR 2 ADJ FROM	3156.65 TO	4734.97									
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				2	3	2	.295E+04	.473E+04	0.000	11.979	31.047 .430E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				3	3	2	.292E+04	.473E+04	0.000	11.938	31.211 .431E+02
OBJECTIVE FUNCTION FOR VARIABLE 3		.4290E+02	.4303E+02				.4315E+02				
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	2	3	.473E+04	.447E+04	0.000	14.041	23.604 .376E+02
VAR 3 ADJ FROM	2979.44 TO	4469.17									
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				2	2	3	.469E+04	.447E+04	0.000	13.976	23.744 .377E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				3	2	3	.464E+04	.447E+04	0.000	13.912	23.885 .378E+02
OBJECTIVE FUNCTION FOR VARIABLE 2		.3764E+02	.3772E+02				.3780E+02				
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	3	2	.447E+04	.701E+04	0.000	23.176	19.277 .425E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	3	2	.447E+04	.542E+04	0.000	17.223	21.880 .391E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				1	3	2	.447E+04	.494E+04	0.000	14.319	23.053 .374E+02
VAR 2 ADJ FROM	4734.97 TO	4939.90									
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				2	3	2	.442E+04	.494E+04	0.000	14.258	23.247 .375E+02
				NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
				3	3	2	.438E+04	.494E+04	0.000	14.197	23.438 .376E+02
OBJECTIVE FUNCTION FOR VARIABLE 3		.3737E+02	.3751E+02				.3764E+02				

			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	2	3	.494E+04	.670E+04	0.000	22.715	16.449 .392E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	2	3	.494E+04	.514E+04	0.000	15.981	20.683 .367E+02
VAR 3 ADJ FROM	4469.17 TO	5139.54								
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	3	3	.514E+04	.514E+04	0.000	15.981	20.683 .367E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	3	3	.509E+04	.509E+04	0.000	15.634	20.913 .365E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	3	3	.504E+04	.504E+04	0.000	15.287	21.141 .364E+02
OBJECTIVE FUNCTION FOR VARIABLE 3	.3666E+02	.3655E+02				.3643E+02				
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	2	3	.494E+04	.343E+04	0.000	12.904	28.100 .410E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	2	3	.494E+04	.463E+04	0.000	14.531	22.653 .372E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	2	3	.494E+04	.499E+04	0.000	15.019	21.366 .364E+02
VAR 3 ADJ FROM	5139.54 TO	4985.36								
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	2	2	.494E+04	.494E+04	0.000	15.019	21.366 .364E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			2	2	2	.489E+04	.489E+04	0.000	14.952	21.481 .364E+02
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			3	2	2	.484E+04	.484E+04	0.000	14.885	21.619 .365E+02
OBJECTIVE FUNCTION FOR VARIABLE 2	.3639E+02	.3643E+02				.3650E+02				
			NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)
			1	3	2	.499E+04	.502E+04	0.000	15.210	21.154 .364E+02
VAR 2 ADJ FROM	4939.90 TO	5016.16								

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

POTENTIAL RESERVOIR INFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
10	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL CHANNEL MODIFICATION REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 1030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 1030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1464.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

STATION 1030, PLAN 1, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1940.	1859.	1220.	579.	34733.
CMS	55.	53.	35.	16.	984.
INCHES		.49	1.29	1.53	1.53
MM		12.52	32.84	38.97	38.97
AC-FT		922.	2420.	2872.	2872.
THOUS CU M		1138.	2985.	3543.	3543.

MAXIMUM STORAGE = 890.

Several pages of printout deleted

STATION 1030, PLAN 2, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	20603.	19364.	11267.	5087.	305199.
CMS	583.	548.	319.	144.	8642.
INCHES		5.13	11.94	13.48	13.48
MM		130.35	303.38	342.41	342.41
AC-FT		9607.	22359.	25236.	25236.
THOUS CU M		11850.	27580.	31128.	31128.

MAXIMUM STORAGE = 5505.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
1030	16	3	0	0.	0.000	0	0.00000	0.00000	2

ECONOMIC DATA FOR STATION 1030 PLAN 1

FREQ	PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
6.000	1030.	0.000	0.000	0.000	0.000
5.500	1130.	0.000	0.000	0.000	0.000
4.500	1380.	1.600	.100	.500	1.000
3.500	1740.	2.400	.200	.700	1.500
2.500	2280.	5.000	.300	1.500	3.200
1.500	3200.	7.200	.300	2.200	4.700
.900	4220.	9.800	.400	2.900	6.500
.700	4800.	11.800	.500	3.500	7.800
.500	5620.	13.900	.600	4.000	9.300
.350	6480.	16.400	.700	4.700	11.000
.250	7340.	20.300	.800	5.800	13.700
.150	8540.	23.100	.900	6.600	15.600
.100	10000.	28.000	1.000	8.000	19.000
.050	12100.	34.500	1.200	10.300	23.000
.020	15100.	44.300	1.500	15.000	27.800
.005	21000.	50.100	1.800	18.100	30.200

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.99	.07	.30	.62
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.31	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.48
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97

LOCAL PROTECTION DATA

XLPMX	XLPMN	XANCST	XDSCNT
8300.	1700.	.02300	.05040

CAPACITY=	1700.	5000.	5500.	7000.	8300.	9300.	0.	0.	0.	0.
COST=	42.	103.	149.	222.	283.	340.	0.	0.	0.	0.

MINIMUM DESIGN DAMAGE FUNCTION

PEAK = = =	CATEGORY DAMAGES		
1030.	0.00	0.00	0.00
1130.	0.00	0.00	0.00
1380.	0.00	0.00	0.00
1740.	.01	.08	.13
2280.	.14	.95	1.73
3200.	.25	1.73	3.44
4220.	.36	2.53	5.85
4800.	.43	2.73	7.23
5620.	.53	3.53	8.91
6480.	.62	4.08	10.63
7340.	.69	5.01	13.11
8540.	.82	6.16	15.03
10000.	.97	7.70	18.61
12100.	1.17	9.90	22.09
15100.	1.43	14.08	27.00
21000.	1.76	17.51	29.32

MAXIMUM DESIGN DAMAGE FUNCTION

PEAK = = =	CATEGORY DAMAGES		
1030.	0.00	0.00	0.00
1130.	0.00	0.00	0.00
1380.	0.00	0.00	0.00
1740.	0.00	0.00	0.00
2280.	0.00	0.00	0.00
3200.	0.00	0.00	0.00
4220.	0.00	0.00	0.00
4800.	0.00	0.00	0.00
5620.	0.00	0.00	0.00
6480.	0.00	0.00	0.00
7340.	0.00	0.00	0.00
8540.	.04	.25	.44
10000.	.25	1.75	3.50
12100.	.42	3.18	7.15
15100.	.64	5.04	12.29
21000.	.99	7.98	16.86

INTERPOLATED ECONOMIC DATA FOR STATION 1030 PLAN 2

PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
1030.	0.000	0.000	0.000	0.000
1130.	0.000	0.000	0.000	0.000
1380.	0.000	0.000	0.000	0.000
1740.	0.000	0.000	0.000	0.000
2280.	0.000	0.000	0.000	0.000
3200.	0.000	0.000	0.000	0.000
5011.	0.000	0.000	0.000	0.000
5016.	1.619	.110	.424	1.086
5620.	3.519	.183	1.013	2.323
6480.	5.879	.273	1.563	4.043
7340.	9.359	.343	2.493	6.523
8540.	11.318	.428	3.191	7.699
10000.	16.337	.608	4.710	11.018
12100.	21.900	.793	6.524	14.583
15100.	30.180	1.033	9.538	19.609
21000.	37.154	1.373	12.722	23.059

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	0.00	0.00	0.00	0.00
3	1940.	3.097	1.776	0.00	0.00	0.00	0.00
4	2921.	1.769	1.072	0.00	0.00	0.00	0.00
5	4312.	.867	.785	.35	.02	.10	.23
6	6699.	.323	.391	2.61	.11	.71	1.79
7	10191.	.095	.136	2.17	.08	.63	1.46
8	15177.	.020	.037	1.02	.04	.33	.66
9	20603.	.006	.014	.48	.02	.16	.30
	AVG ANN DMG			6.63	.27	1.93	4.44
	AVG ANN BFT			26.94	1.32	8.09	17.53

LOCAL PROTECTION CAP COST = 104. TOTAL ANNUAL = 8. DESIGN Q = 5016.

****

SUB-AREA RUNOFF COMPUTATION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	0	0	2	0	0	0	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

****

HYDROGRAPH ROUTING

POTENTIAL LEVEE AND/OR BYPASS REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	*1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 2030, PLAN 1, RTIO 1

Several pages of printout deleted

STATION 2030, PLAN 2, RTIO 9

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	20603.	19364.	11267.	5087.	305199.
CMS	583.	548.	319.	144.	8642.
INCHES		5.13	11.94	13.48	13.48
MM		130.35	303.38	342.41	342.41
AC-FT		9607.	22359.	25236.	25236.
THOUS CU M		11850.	27580.	31128.	31128.

MAXIMUM STORAGE = 5505.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAGST	ADSCNT	AANCST	ILPR
2030	16	1	0	0.	0.000	0	0.00000	0.00000	3

ECONOMIC DATA FOR STATION 2030 PLAN 1

FREQ	PEAK	SUM	TYPE 1
6.000	1030.	0.000	0.000
5.500	1130.	0.000	0.000
4.500	1380.	1.600	1.600
3.500	1740.	2.400	2.400
2.500	2280.	5.000	5.000
1.500	3200.	7.200	7.200
.900	4220.	9.800	9.800
.700	4800.	11.800	11.800
.500	5620.	13.900	13.900
.350	6480.	16.400	16.400
.250	7340.	20.300	20.300
.150	8540.	23.100	23.100
.100	10000.	28.000	28.000
.050	12100.	34.500	34.500
.020	15100.	44.300	44.300
.005	21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.99	.99
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58

LOCAL PROTECTION DATA

XLPMX	XLPMN	XANCST	XDSCNT
8300.	1700.	.02300	.05040

CAPACITY=	1700.	5000.	5500.	7000.	8300.	9300.	0.	0.	0.	0.
COST=	42.	103.	149.	222.	283.	340.	0.	0.	0.	0.

MINIMUM DESIGN DAMAGE FUNCTION

PEAK	CATEGORY DAMAGES
1030.	0.00
1130.	0.00
1380.	1.60
1740.	2.40
2280.	5.00
3200.	7.20
4220.	9.80
4800.	11.80
5620.	13.90
6480.	16.40
7340.	20.30
8540.	23.10
10000.	28.00
12100.	34.50
15100.	44.30
21000.	50.10

MAXIMUM DESIGN DAMAGE FUNCTION

PEAK	CATEGORY DAMAGES
1030.	0.00
1130.	0.00
1380.	1.60
1740.	2.40
2280.	5.00
3200.	7.20
4220.	9.80
4800.	11.80
5620.	13.90
6480.	16.40
7340.	20.30
8540.	23.10
10000.	28.00
12100.	34.50
15100.	44.30
21000.	50.10

INTERPOLATED ECONOMIC DATA FOR STATION 2030 PLAN 2

PEAK	SUM	TYPE 1
1030.	0.000	0.000
1130.	0.000	0.000
1380.	0.000	0.000
1740.	0.000	0.000
2280.	0.000	0.000
3200.	0.000	0.000
4980.	0.000	0.000
4985.	12.275	12.275
5620.	13.900	13.900
6480.	16.400	16.400
7340.	20.300	20.300
8540.	23.100	23.100
10000.	28.000	28.000
12100.	34.500	34.500
15100.	44.300	44.300
21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	0.00	0.00
3	1940.	3.097	1.776	0.00	0.00
4	2921.	1.769	1.072	0.00	0.00
5	4312.	.867	.785	2.13	2.13
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
		AVG ANN DMG		14.52	14.52
		AVG ANN BFT		19.06	19.06

LOCAL PROTECTION CAP COST = .103, TOTAL ANNUAL = 8, DESIGN Q = 4985,

Several pages of printout deleted

EXHIBIT 7

SIZING RESERVOIR, PUMPING PLANT, DIVERSION
AND UNIFORM PROTECTION LOCAL PROJECTS

(Unconstrained)

```
  A        FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
R-A        SIZING RESERVOIR, PUMPING PLANT, DIVERSION AND UNIFORM PROTECTION
R-A        LOCAL PROJECTS (LEVEE AND CHANNEL MODIFICATION)    UNCONSTRAINED
  B     60      1                                                        3
  1      6
  J      2      9      1
  1   0.25   0.30   0.50   0.70   1.00   1.50   2.20   3.25   4.40
R-2  -4000   -200                                -500          -1000
  4
  K      0     10                                   1
  1        POTENTIAL RESERVOIR INFLOW
  M     -1          35.1                                              1
  N     24     24     26     33     50     85    190    375    515    590
  N    660    710    760    800    840    910   1040   1290   1920   3000
  N   3950   4600   5080   5360   5370   5100   4600   3980   3330   2720
  N   2200   1840   1540   1250    995    775    605    470    365    280
  N    215    160    120     95     77     66     59     53     49     42
  N     40     38     35     33     30     30     29     27     25     25
  K      1    110                            2      1
  1        PROPOSED RESERVOIR
  Y                           -1      0
  Y                            1      0      1
  1      1                                          -1
  $  25000      0    200  975.0     .5  100.0   .023  .0504
  1      0   2500   4000   5200   6800   9000  11500  15500  21000  30000
  2    965   1000   1015   1030   1045   1060   1075   1090   1105   1120
  3      0   1500   2400   3000   3600   4350   4950   5550   6000   7200
  K      1   1030      1                            1
  1        POTENTIAL CHANNEL MODIFICATION REACH
  Y                            1      1                              0
  1      1                                          -1
  2      0     50    475    940   2135   3080   6300
  3      0    200   1020   2050   6100  10250  24000
R-Z   1030     16      3      0                                          (-2)
  1      6    5.5    4.5    3.5    2.5    1.5     .9     .7     .5    .35
  1    .25    .15    .10    .05    .02   .005
  2   1030   1130   1380   1740   2280   3200   4220   4800   5620   6480
  2   7340   8540  10000  12100  15100  21000
  3
  4      0      0     .1     .2     .3     .3     .4     .5     .6     .7
  4     .8     .9    1.0    1.2    1.5    1.8
  4      0      0     .5     .7    1.5    2.2    2.9    3.5    4.0    4.7
  4    5.8    6.6    8.0   10.3   15.0   18.1
  4      0      0    1.0    1.5    3.2    4.7    6.5    7.8    9.3   11.0
  4   13.7   15.6   19.0   23.0   27.8   30.2
  /   8300   1700   .023  .0504
  1   1700   5000   5500   7000   8300   9300
  2     42    103    149    222    283    340
  3   1030   1130   1380   1740   2280   3200   4220   4800   5620   6480
  3   7340   8540  10000  12100  15100  21000
  4      0      0      0    .01    .14    .25    .36    .43    .53    .62
  4    .69    .82    .97   1.17   1.43   1.76
  4      0      0      0    .08    .95   1.73   2.53   2.73   3.53   4.08
  4   5.01   6.16   7.70   9.90  14.08  17.51
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

( ) = REVISED INPUT DATA

```
4       0       0       0     .13    1.73    3.44    5.85    7.23    8.91   10.63
4   13.11   15.03   18.61   22.09   27.00   29.32
5       0       0       0       0       0       0       0       0       0       0
5       0     .04     .25     .42     .64     .99
5       0       0       0       0       0       0       0       0       0       0
5       0     .25    1.75    3.18    5.04    7.98
5       0       0       0       0       0       0       0       0       0       0
5       0     .44    3.50    7.15   12.29   16.86
K       0      20
M      -1            35.1                                                    1
N      24      24      26      33      50      85     190     375     515     590
N     660     710     760     800     840     910    1040    1290    1920    3000
N    3950    4600    5080    5360    5370    5100    4600    3980    3330    2720
N    2200    1840    1540    1250     995     775     605     470     365     280
N     215     160     120      95      77      66      59      53      49      42
N      40      38      35      33      30      30      29      27      25      25
K       1      20                              2       1
1       DUMMY RESERVOIR TO ACCOMODATE DIVERSION
Y                               -1       0
Y                                1       0                       7
1       1                                                      -1
2       0    2000
3       0  100000
+   20000       0    1500    .015   .0504
1       0    1250    2500    3750    5000    7500   10000   15000   20000
2       0    1500    2600    3400    4200    5200    6100    7500    8300
K       1    2030       1                                    1
1       POTENTIAL LEVEE AND/OR BYPASS REACH
Y                                1       1                               0
1       1                                                      -1
2       0      50     475     940    2135    3080    6300
3       0     200    1020    2050    6100   10250   24000
Z    2030      16       1       0                                          (-2)
1       6     5.5     4.5     3.5     2.5     1.5      .9      .7      .5     (.35)
1     .25      .15     .10     .05     .02     .005
2    1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
2    7340    8540   10000   12100   15100   21000
3
4       0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
4    20.3    23.1    28.0    34.5    44.3    50.1
/    8300    1700    .023   .0504
1    1700    5000    5500    7000    8300    9300
2      42     103     149     222     283     340
3    1030    1130    1380    1740    2280    3200    4220    4800    5620    6480
3    7340    8540   10000   12100   15100   21000
4       0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
4    20.3    23.1    28.0    34.5    44.3    50.1
5       0       0     1.6     2.4     5.0     7.2     9.8    11.8    13.9    16.4
5    20.3    23.1    28.0    34.5    44.3    50.1
K       0      30                                    1
1       LOCAL INFLOW TO FOREBAY POOL
M      -1            10.0                                                    1
N       8       8       9      11      17      28      63     125     170     195
N     220     230     255     265     280     305     350     430     640    1000
N    1320    1540    1650    1800    1810    1690    1530    1330    1110     900
N     730     615     515     415     330     255     200     155     120      93
N      72      54      41      32      26      22      20      18      16      14
N      13      12      11      11      11      10      10       9       9       9
K       3      30                                    1
1       COMBINED INFLOW TO FOREBAY POOL
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

(-) = REVISED INPUT DATA



```
K      1     305       1                        2       1
1       PROPOSED PUMPING PLANT SITE
Y                                1       0                                1
1      1                                                 -1
2      0     400  100000
3      0    1200    1200
Y                                1       0                9                1
1      1                                                 -1
2      0     400  100000
3      0    1200    1200
*  10000       0    1500     100    .023   .0504
1      0     250     500    1000    2000    6000    8000   10000
2      0     670    1000    1600    2300    6000    7860    8670
Z    305      10       2       1
1    .70     .60     .45     .25     .10     .05     .02     .01    .005    .002
2   1500    2300    4000    7000   12500   20000   28000   37000   50000   76000
3
4      0    37.5     75.    1125    3150    5850    7050    9000   10650   11250
4      0    10.5      15    52.5     105   202.5     300     390     540     585
K     99
A
A
A
A
A
```

LEGEND

N = NEW INPUT DATA

R = REVISED INPUT DATA

◯ = REVISED INPUT DATA

FLOOD CONTROL SYSTEM COMPONENT OPTIMIZATION
SIZING RESERVOIR, PUMPING PLANT, DIVERSION AND UNIFORM PROTECTION
LOCAL PROJECTS(LEVEE AND CHANNEL MODIFICATION) UNCONSTRAINED

JOB SPECIFICATION

NQ	NHR	NMIN	IDAY	IHR	JMIN	METRC	IPLT	IPRT	NSTAN
60	1	0	0	0	0	0	0	3	0
			JOPER	NWT	LROPT	TRACE			
			6	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 2 NRTIO= 9 LRTIO= 1

RTIOS= .25 .30 .50 .70 1.00 1.50 2.20 3.25 4.40

SYSTEM OPTIMIZATION

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
-4000.	-200.	0.	0.	0.	0.	-500.	0.	-1000.	0.

FIXED COST INPUT

FCAP	FDCNT	FAN
0.	0.0000	0.0000
0.	0.	0.

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	6015.571	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7808.356	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.400E+04	.400E+04	0.000	464.697	600.574	.107E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	6054.577	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7808.356	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.396E+04	.396E+04	0.000	463.166	602.957	.107E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	6099.605	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7808.356	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.392E+04	.392E+04	0.000	461.657	605.347	.107E+04

OBJECTIVE FUNCTION FOR VARIABLE 1	.1065E+04	.1066E+04	.1067E+04

				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4615.376	0.000	0.000	0.000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7808.356	0.000	0.000	0.000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
VAR 1 ADJ FROM	4000.00 TO	5190.33	1	2 1	.200E+03	.519E+04	0.000	500.189	548.857	.105E+04
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4646.889	0.000	0.000	0.000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7839.689	0.000	0.000	0.000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			2	2 1	.198E+03	.519E+04	0.000	500.340	548.643	.105E+04
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4678.617	0.000	0.000	0.000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7871.148	0.000	0.000	0.000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			3	2 1	.196E+03	.519E+04	0.000	500.491	548.624	.105E+04
OBJECTIVE FUNCTION FOR VARIABLE 2	.1049E+04	.1049E+04			.1049E+04					
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4641.270	0.000	0.000	0.000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7834.109	0.000	0.000	0.000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			1	7 2	.500E+03	.198E+03	0.000	500.313	548.647	.105E+04
VAR 2 ADJ FROM	200.00 TO	198.36								
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4641.270	0.000	0.000	0.000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7839.954	0.000	0.000	0.000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			2	7 2	.495E+03	.198E+03	0.000	499.969	549.094	.105E+04
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4641.270	0.000	0.000	0.000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7845.800	0.000	0.000	0.000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			3	7 2	.490E+03	.198E+03	0.000	499.626	549.541	.105E+04
OBJECTIVE FUNCTION FOR VARIABLE 7	.1049E+04	.1049E+04			.1049E+04					

				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				1030	4641.270	0.000	0.000	0.000	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				2030	7578.270	0.000	0.000	0.000	
			NC	M M1	VAR(M) VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
VAR 7 ADJ FROM	500.00 TO	750.00	1	9 7	.100E+04 .750E+03	0.000	517.659	527.738 .105E+04	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				1030	4641.270	0.000	0.000	0.000	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				2030	7578.270	0.000	0.000	0.000	
			NC	M M1	VAR(M) VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
			2	9 7	.990E+03 .750E+03	0.000	516.779	528.959 .105E+04	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				1030	4641.270	0.000	0.000	0.000	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				2030	7578.270	0.000	0.000	0.000	
			NC	M M1	VAR(M) VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
			3	9 7	.980E+03 .750E+03	0.000	515.898	530.182 .105E+04	
OBJECTIVE FUNCTION FOR VARIABLE 9		.1045E+04	.1046E+04		.1046E+04				
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				1030	4641.270	0.000	0.000	0.000	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				2030	7578.270	0.000	0.000	0.000	
			NC	M M1	VAR(M) VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
VAR 9 ADJ FROM	1000.00 TO	1500.00	1	1 9	.519E+04 .150E+04	0.000	543.349	474.233 .102E+04	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				1030	4698.502	0.000	0.000	0.000	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				2030	7578.270	0.000	0.000	0.000	
			NC	M M1	VAR(M) VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
			2	1 9	.514E+04 .150E+04	0.000	541.629	476.321 .102E+04	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				1030	4758.866	0.000	0.000	0.000	
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV	
				2030	7578.270	0.000	0.000	0.000	
			NC	M M1	VAR(M) VAR(M1)	OBJ DEV	TANCST	ANDMG O FTN(NC)	
			3	1 9	.509E+04 .150E+04	0.000	539.912	478.401 .102E+04	
OBJECTIVE FUNCTION FOR VARIABLE 1		.1018E+04	.1018E+04		.1018E+04				

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2570,749	0,000	0,000	0,000
2030	7578,270	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	2	1	,198E+03	,779E+04	0,000	604,746	401,783	,101E+04

VAR 1 ADJ FROM 5190,33 TO 7785,49

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2599,856	0,000	0,000	0,000
2030	7609,217	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
2	2	1	,196E+03	,779E+04	0,000	604,881	401,712	,101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2621,135	0,000	0,000	0,000
2030	7640,290	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
3	2	1	,194E+03	,779E+04	0,000	605,017	401,700	,101E+04

OBJECTIVE FUNCTION FOR VARIABLE 2 ,1007E+04 -,1007E+04 ,1007E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2566,451	0,000	0,000	0,000
2030	7560,181	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	,750E+03	,200E+03	0,000	604,667	401,932	,101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2575,053	0,000	0,000	0,000
2030	7572,839	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	,750E+03	,199E+03	0,000	604,722	401,921	,101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2577,640	0,000	0,000	0,000
2030	7576,641	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	,750E+03	,198E+03	0,000	604,739	401,824	,101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2578,749	0,000	0,000	0,000
2030	7578,270	0,000	0,000	0,000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	2	.750E+03	.198E+03	0.000	604.746	401.783	.101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2578.749	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7585.949	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	7	2	.743E+03	.198E+03	0.000	604.224	402.348	.101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2578.749	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7593.627	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	7	2	.735E+03	.198E+03	0.000	603.703	402.920	.101E+04

OBJECTIVE FUNCTION FOR VARIABLE 7	.1007E+04	.1007E+04	.1007E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2578.749	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7531.575	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	7	.150E+04	.796E+03	0.000	607.922	398.339	.101E+04

VAR 7 ADJ FROM	750.00 TO	795.68

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2578.749	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7531.575	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	9	7	.149E+04	.796E+03	0.000	607.151	399.764	.101E+04

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2578.749	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7531.575	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	9	7	.147E+04	.796E+03	0.000	606.381	401.193	.101E+04

OBJECTIVE FUNCTION FOR VARIABLE 9	.1006E+04	.1007E+04	.1008E+04

				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	2578,749	0,000	0,000	0,000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7531,575	0,000	0,000	0,000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			1	1 9	,779E+04	,225E+04	0,000	650,586	336,824	,987E+03
VAR 9 ADJ FROM	1500,00 TO	2250,00								
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	2606,145	0,000	0,000	0,000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7531,575	0,000	0,000	0,000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			2	1 9	,771E+04	,225E+04	0,000	648,803	338,191	,987E+03
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	2631,587	0,000	0,000	0,000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7531,575	0,000	0,000	0,000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			3	1 9	,763E+04	,225E+04	0,000	647,015	339,542	,987E+03
OBJECTIVE FUNCTION FOR VARIABLE 1	,9874E+03	,9870E+03			,9866E+03					
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	4641,267	0,000	0,000	0,000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7531,575	0,000	0,000	0,000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			1	2 1	,198E+03	,519E+04	0,000	589,190	406,932	,996E+03
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	2846,968	0,000	0,000	0,000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7531,575	0,000	0,000	0,000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			1	2 1	,198E+03	,701E+04	0,000	632,730	350,530	,983E+03
VAR 1 ADJ FROM	7785,49 TO	7006,94								
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	2874,189	0,000	0,000	0,000		
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				2030	7562,481	0,000	0,000	0,000		
			NC	M M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
			2	2 1	,196E+03	,701E+04	0,000	632,874	350,434	,983E+03
				ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV		
				1030	2901,670	0,000	0,000	0,000		

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7593.514	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	2	1	.194E+03	.701E+04	0.000	633.018	350.417	.983E+03

OBJECTIVE FUNCTION FOR VARIABLE 2 .9833E+03 .9833E+03 .9834E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2844.594	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7528.872	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	2	.796E+03	.199E+03	0.000	632.718	350.602	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.256	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7530.764	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	2	.796E+03	.198E+03	0.000	632.726	350.553	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.754	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7531.332	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	2	.796E+03	.198E+03	0.000	632.729	350.537	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7531.575	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	7	2	.796E+03	.198E+03	0.000	632.730	350.530	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7539.649	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	7	2	.788E+03	.198E+03	0.000	632.176	351.059	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7547.796	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	7	2	.780E+03	.198E+03	0.000	631.623	351.596	.983E+03

OBJECTIVE FUNCTION FOR VARIABLE 7 .9833E+03 .9832E+03 .9832E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	9	7	.225E+04	.769E+03	0.000	630.906	352.292	.983E+03

VAR 7 ADJ FROM 795.68 TO 769.45

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	9	7	.223E+04	.769E+03	0.000	629.378	353.881	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	9	7	.221E+04	.769E+03	0.000	627.850	355.468	.983E+03

OBJECTIVE FUNCTION FOR VARIABLE 9 .9832E+03 .9833E+03 .9833E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.701E+04	.338E+04	0.000	707.288	287.788	.995E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.701E+04	.259E+04	0.000	653.820	330.730	.985E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2846.968	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	9	.701E+04	.235E+04	0.000	637.780	345.312	.983E+03

VAR 9 ADJ FROM 2250.00 TO 2351.25

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2871.174	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	9	.694E+04	.235E+04	0.000	636.174	346.555	.983E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2893.548	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	9	.687E+04	.235E+04	0.000	634.567	347.813	.982E+03

OBJECTIVE FUNCTION FOR VARIABLE 1	.9831E+03	.9827E+03	.9824E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	4836.753	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	1	.198E+03	.503E+04	0.000	588.787	407.956	.997E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3177.182	0.000	0.000	0.000
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	1	.198E+03	.641E+04	0.000	623.450	358.293	.982E+03

VAR 1 ADJ FROM 7006.94 TO 6412.47

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3208.106	0.000	0.000	0.000
2030	7589.284	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	2	1	.196E+03	.641E+04	0.000	623.598	358.206	.982E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3239.330	0.000	0.000	0.000
2030	7620.339	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	2	1	.194E+03	.641E+04	0.000	623.748	358.187	.982E+03

OBJECTIVE FUNCTION FOR VARIABLE 2	.9817E+03	.9818E+03	.9819E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3165.333	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7546.458	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	.769E+03	.199E+03	0.000	623.393	358.432	.982E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3173.623	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7554.784	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	.769E+03	.199E+03	0.000	623.433	358.384	.982E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3176.114	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7557.284	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	.769E+03	.198E+03	0.000	623.445	358.320	.982E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3177.182	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7558.355	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
1	7	2	.769E+03	.198E+03	0.000	623.450	358.293	.982E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3177.182	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7566.234	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
2	7	2	.762E+03	.198E+03	0.000	622.915	358.821	.982E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3177.182	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7574.112	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
3	7	2	.754E+03	.198E+03	0.000	622.380	359.350	.982E+03

OBJECTIVE FUNCTION FOR VARIABLE 7	.9817E+03	.9817E+03	.9817E+03

	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	1030	3177,182	0,000	0,000	0,000
	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	2030	7660,243	0,000	0,000	0,000

	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
	1	9	7	,235E+04	,670E+03	0,000	616,535	364,679	,981E+03

VAR 7 ADJ FROM 769,45 TO 669,92

	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	1030	3177,182	0,000	0,000	0,000
	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	2030	7660,243	0,000	0,000	0,000

	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
	2	9	7	,233E+04	,670E+03	0,000	614,938	366,326	,981E+03

	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	1030	3177,182	0,000	0,000	0,000
	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	2030	7660,243	0,000	0,000	0,000

	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
	3	9	7	,230E+04	,670E+03	0,000	613,342	367,972	,981E+03

OBJECTIVE FUNCTION FOR VARIABLE 9 ,9812E+03 ,9813E+03 ,9813E+03

	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	1030	3177,182	0,000	0,000	0,000
	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	2030	7660,243	0,000	0,000	0,000

	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
	1	1	9	,641E+04	,353E+04	0,000	696,354	296,653	,993E+03

	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	1030	3177,182	0,000	0,000	0,000
	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	2030	7660,243	0,000	0,000	0,000

	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
	1	1	9	,641E+04	,270E+04	0,000	640,481	341,930	,982E+03

	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	1030	3177,182	0,000	0,000	0,000
	ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
	2030	7660,243	0,000	0,000	0,000

	NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG O	FTN(NC)
	1	1	9	,641E+04	,246E+04	0,000	623,719	357,326	,981E+03

VAR 9 ADJ FROM 2351,25 TO 2457,06

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3177.182	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7660.243	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	1	1	.641E+04	.641E+04	0.000	623.719	357.326	.981E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3249.430	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7660.243	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
2	1	1	.635E+04	.635E+04	0.000	622.184	359.276	.981E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	3323.478	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7660.243	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
3	1	1	.628E+04	.628E+04	0.000	620.651	361.229	.982E+03

OBJECTIVE FUNCTION FOR VARIABLE 1 .9810E+03 .9815E+03 .9819E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	1822.015	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7660.243	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	1	.198E+03	.962E+04	0.000	693.019	299.569	.993E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2719.713	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7660.243	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	1	.198E+03	.737E+04	0.000	646.474	338.056	.985E+03

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
1030	2946.830	0.000	0.000	0.000

ISTA	INT FLOW	TRG FLOW	FLW OBJ	FLW DEV
2030	7660.243	0.000	0.000	0.000

NC	M	M1	VAR(M)	VAR(M1)	OBJ DEV	TANCST	ANDMG	O FTN(NC)
1	2	1	.198E+03	.670E+04	0.000	630.790	350.087	.981E+03

VAR 1 ADJ FROM 6412.47 TO 6701.03

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

POTENTIAL RESERVOIR INFLOW

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
10	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE

PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	178.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

PROPOSED RESERVOIR

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
110	1	0	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	-1	0	0	0	0	0

PLAN 2
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	1	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	-1.

RESERVOIR DATA

CAPMX	CAPMN	COOL	ELEVL	EXPL	COQW	RANCST	RDSCNT	COQT	ELEVT	EXPT
25000.	0.	200.00	975.00	.50	100.00	.0230	.0504	0.00	975.00	0.00

CAPACITY=	0.	2500.	4000.	5200.	6800.	9000.	11500.	15500.	21000.	30000.
ELEVATION=	965.	1000.	1015.	1030.	1045.	1060.	1075.	1090.	1105.	1120.
COST=	0.	1500.	2400.	3000.	3600.	4350.	4950.	5550.	6000.	7200.

OUTLET CREST ELEVATION IS 1044.07 AT STORAGE OF 6701.

SYNTHETIC STORAGE OUTFLOW FUNCTION

STORAGE=	714.	1023.	1948.	3885.	6701.	10674.	14247.	18469.	23711.	30000.
OUTFLOW=	0.	416.	831.	1247.	1662.	15182.	28565.	41916.	55248.	68569.

STATION 110, PLAN 2, RTIO 1

Several pages of printout deleted

STATION 110, PLAN 2, RTIO 9

RESERVOIR	CAP COST	TOT ANN $
6701.0	3563.	262.

OUTFLOW

106.	106.	106.	109.	116.	135.	185.	297.	435.	508.
589.	678.	771.	849.	897.	949.	1008.	1080.	1185.	1321.
1491.	2442.	7091.	11005.	14112.	16411.	17732.	18039.	17514.	16387.
14919.	13432.	11953.	10519.	9144.	7849.	6662.	5603.	4674.	3872.
3185.	2603.	2113.	1709.	1648.	1632.	1616.	1599.	1582.	1566.
1549.	1532.	1516.	1499.	1483.	1466.	1450.	1434.	1418.	1402.

STOR

793.	793.	793.	795.	801.	815.	852.	934.	1066.	1228.
1410.	1607.	1814.	2031.	2257.	2499.	2772.	3110.	3600.	4391.
5538.	6930.	8296.	9447.	10360.	11002.	11355.	11437.	11297.	10996.
10597.	10160.	9725.	9304.	8899.	8519.	8170.	7859.	7586.	7350.
7149.	6978.	6834.	6715.	6607.	6498.	6386.	6274.	6161.	6047.
5934.	5820.	5708.	5596.	5484.	5373.	5263.	5154.	5046.	4938.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	18039.	16834.	9192.	4271.	256284.
CMS	511.	477.	260.	121.	7257.
INCHES		4.46	9.74	11.32	11.32
MM		113.32	247.52	287.53	287.53
AC-FT		8352.	18242.	21191.	21191.
THOUS CU M		10302.	22502.	26139.	26139.

MAXIMUM STORAGE = 11437.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL CHANNEL MODIFICATION REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	*1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 1030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

Several pages of printout deleted

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAGST	ADSCNT	AANCST	ILPR
1030	16	3	0	0.	0.000	0	0.00000	0.00000	=2

ECONOMIC DATA FOR STATION 1030 PLAN 1

FREQ	PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
6.000	1030.	0.000	0.000	0.000	0.000
5.500	1130.	0.000	0.000	0.000	0.000
4.500	1380.	1.600	.100	.500	1.000
3.500	1740.	2.400	.200	.700	1.500
2.500	2280.	5.000	.300	1.500	3.200
1.500	3200.	7.200	.300	2.200	4.700
.900	4220.	9.800	.400	2.900	6.500
.700	4800.	11.800	.500	3.500	7.800
.500	5620.	13.900	.600	4.000	9.300
.350	6480.	16.400	.700	4.700	11.000
.250	7340.	20.300	.800	5.800	13.700
.150	8540.	23.100	.900	6.600	15.600
.100	10000.	28.000	1.000	8.000	19.000
.050	12100.	34.500	1.200	10.300	23.000
.020	15100.	44.300	1.500	15.000	27.800
.005	21000.	50.100	1.800	18.100	30.200

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	941.	6.000	.284	0.00	0.00	0.00	0.00
2	1139.	5.462	1.752	.99	.07	.30	.62
3	1940.	3.097	1.776	5.81	.40	1.73	3.68
4	2921.	1.769	1.072	6.66	.31	2.02	4.33
5	4312.	.867	.785	7.73	.33	2.28	5.12
6	6699.	.323	.391	6.54	.27	1.87	4.39
7	10191.	.095	.136	3.70	.14	1.08	2.48
8	15177.	.020	.037	1.50	.05	.50	.95
9	20603.	.006	.014	.66	.02	.24	.40
	AVG ANN DMG			33.58	1.59	10.02	21.97

LOCAL PROTECTION DATA

XLPMX	XLPMN	XANCST	XDSCNT
8300.	1700.	.02300	.05040

CAPACITY=	1700.	5000.	5500.	7000.	8300.	9300.	0.	0.	0.	0.
COST=	42.	103.	149.	222.	283.	340.	0.	0.	0.	0.

MINIMUM DESIGN DAMAGE FUNCTION

PEAK	CATEGORY DAMAGES		
1030.	0.00	0.00	0.00
1130.	0.00	0.00	0.00
1380.	0.00	0.00	0.00
1740.	.01	.08	.13
2280.	.14	.95	1.73
3200.	.25	1.73	3.44
4220.	.36	2.53	5.85
4800.	.43	2.73	7.23
5620.	.53	3.53	8.91
6480.	.62	4.08	10.63
7340.	.69	5.01	13.11
8540.	.82	6.16	15.03
10000.	.97	7.70	18.61
12100.	1.17	9.90	22.09
15100.	1.43	14.08	27.00
21000.	1.76	17.51	29.32

MAXIMUM DESIGN DAMAGE FUNCTION

PEAK	CATEGORY DAMAGES		
1030.	0.00	0.00	0.00
1130.	0.00	0.00	0.00
1380.	0.00	0.00	0.00
1740.	0.00	0.00	0.00
2280.	0.00	0.00	0.00
3200.	0.00	0.00	0.00
4220.	0.00	0.00	0.00
4800.	0.00	0.00	0.00
5620.	0.00	0.00	0.00
6480.	0.00	0.00	0.00
7340.	0.00	0.00	0.00
8540.	.04	.25	.44
10000.	.25	1.75	3.50
12100.	.42	3.18	7.15
15100.	.64	5.04	12.29
21000.	.99	7.98	16.86

INTERPOLATED ECONOMIC DATA FOR STATION 1030 PLAN 2

PEAK	SUM	TYPE 1	TYPE 2	TYPE 3
1030.	0.000	0.000	0.000	0.000
1130.	0.000	0.000	0.000	0.000
1380.	0.000	0.000	0.000	0.000
2944.	0.000	0.000	0.000	0.000
2947.	1.151	.089	.569	.493
3200.	1.867	.120	.784	.963
4220.	5.187	.230	1.584	3.373
4800.	6.837	.300	1.784	4.753
5620.	9.417	.400	2.584	6.433
6480.	11.777	.490	3.134	8.153
7340.	15.257	.560	4.064	10.633
8540.	17.990	.673	5.044	12.274
10000.	23.165	.834	6.576	15.756
12100.	28.926	1.028	8.631	19.268
15100.	37.874	1.281	12.372	24.221
21000.	44.290	1.615	15.710	26.966

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 1030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2	TYPE 3
1	525.	6.000	.284	0.00	0.00	0.00	0.00
2	594.	5.462	1.752	0.00	0.00	0.00	0.00
3	839.	3.097	1.776	0.00	0.00	0.00	0.00
4	1005.	1.769	1.072	0.00	0.00	0.00	0.00
5	1252.	.867	.785	0.00	0.00	0.00	0.00
6	1574.	.323	.391	.06	.00	.03	.03
7	4949.	.095	.136	1.02	.04	.28	.69
8	10079.	.020	.037	.80	.03	.23	.54
9	15369.	.006	.014	.49	.02	.16	.31
	AVG ANN DMG			2.37	.09	.70	1.58
	AVG ANN BFT			31.21	1.50	9.52	20.39

UNIFORM PROTECTION LEVEL = .198

LOCAL PROTECTION CAP COST. = 65. TOTAL ANNUAL = 5. DESIGN Q = 2947.

****

SUB-AREA RUNOFF COMPUTATION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	0	0	2	0	0	0	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

6.	6.	7.	8.	13.	21.	48.	94.	129.	148.
165.	176.	190.	200.	210.	228.	260.	323.	480.	750.
987.	1150.	1270.	1340.	1343.	1275.	1150.	995.	833.	680.
550.	460.	385.	313.	249.	194.	151.	118.	91.	70.
54.	40.	30.	24.	19.	17.	15.	13.	12.	11.
10.	10.	9.	8.	8.	8.	7.	7.	6.	6.

****

HYDROGRAPH ROUTING

DUMMY RESERVOIR TO ACCOMODATE DIVERSION

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
20	1	0	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	-1	0	0	0	0	0

PLAN 2

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	0	7	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	=1.

STORAGE=	0.	2000.	0.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	100000.	0.	0.	0.	0.	0.	0.	0.	0.

DIVERSION DATA

DVRMX	DVRMN	THDVR	DANCST	DDSCNT
20000.	0.	1500.	.01500	.05040

CAPACITY=	0.	1250.	2500.	3750.	5000.	7500.	10000.	15000.	20000.	0.
COST=	0.	1500.	2600.	3400.	4200.	5200.	6100.	7500.	8300.	0.

STATION 20, PLAN 2, RTIO 1

OUTFLOW

6.	6.	6.	8.	11.	19.	40.	81.	122.	144.
161.	175.	187.	198.	207.	223.	251.	305.	435.	678.
935.	1115.	1243.	1327.	1346.	1296.	1184.	1034.	872.	716.
580.	479.	403.	330.	263.	207.	161.	125.	97.	75.
57.	43.	32.	25.	20.	17.	15.	14.	12.	11.
10.	10.	9.	8.	8.	7.	7.	7.	6.	6.

STOR

0.	0.	0.	0.	0.	0.	1.	2.	2.	3.
3.	3.	4.	4.	4.	4.	5.	6.	9.	14.
19.	22.	25.	27.	27.	26.	24.	21.	17.	14.
12.	10.	8.	7.	5.	4.	3.	3.	2.	1.
1.	1.	1.	1.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1346.	1252.	659.	290.	17375.
CMS	38.	35.	19.	8.	492.
INCHES		.33	.70	.77	.77
MM		8.43	17.74	19.49	19.49
AC-FT		621.	1307.	1437.	1437.
THOUS CU M		766.	1613.	1772.	1772.

MAXIMUM STORAGE = 27.

Several pages of printout deleted

STATION 20, PLAN 2, RTIO 9

DIVERSION 669.9 CAP COST 804. YOT ANN $ 53.

OUTFLOW

106.	106.	112.	136.	199.	331.	700.	1432.	1238.	1943.
2128.	2419.	2614.	2813.	2981.	3249.	3749.	4702.	6980.	11258.
15789.	18958.	21206.	22678.	23026.	22134.	20161.	17526.	14677.	11932.
9536.	7760.	6421.	5137.	3967.	2966.	2158.	1672.	1752.	1303.
1014.	759.	566.	441.	357.	300.	266.	239.	219.	194.
176.	170.	157.	147.	136.	131.	129.	121.	112.	109.

STOR

2.	2.	2.	3.	4.	7.	14.	29.	25.	39.
43.	48.	52.	56.	60.	65.	75.	94.	140.	225.
316.	379.	424.	454.	461.	443.	403.	351.	294.	239.
191.	155.	128.	103.	79.	59.	43.	33.	35.	26.
20.	15.	11.	9.	7.	6.	5.	5.	4.	4.
4.	3.	3.	3.	3.	3.	3.	2.	2.	2.

DIVERSION

0.	0.	0.	0.	0.	0.	0.	0.	670.	670.
670.	670.	670.	670.	670.	670.	670.	670.	670.	670.
670.	670.	670.	670.	670.	670.	670.	670.	670.	670.
670.	670.	670.	670.	670.	670.	670.	568.	106.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	23026.	21360.	10926.	4762.	285697.
CMS	652.	605.	309.	135.	8090.
INCHES		5.66	11.58	12.62	12.62
MM		143.79	294.19	320.53	320.53
AC-FT		10597.	21682.	23624.	23624.
THOUS CU M		13072.	26745.	29139.	29139.

MAXIMUM STORAGE = 461.

********** ********** ********** ********** **********

HYDROGRAPH ROUTING

POTENTIAL LEVEE AND/OR BYPASS REACH

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2030	1	1	0	0	0	1	0	0

ALL PLANS HAVE SAME ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	1	0	0	0	0

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	=1.

STORAGE=	0.	50.	475.	940.	2135.	3080.	6300.	0.	0.	0.
OUTFLOW=	0.	200.	1020.	2050.	6100.	10250.	24000.	0.	0.	0.

STATION 2030, PLAN 1, RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	941.	907.	613.	289.	17369.
CMS	27.	26.	17.	8.	492.
INCHES		.24	.65	.77	.77
MM		6.10	16.51	19.49	19.49
AC-FT		450.	1217.	1436.	1436.
THOUS CU M		555.	1501.	1772.	1772.

MAXIMUM STORAGE = 434.

STATION 2030, PLAN 1, RTIO 2

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1139.	1091.	733.	347.	20842.
CMS	32.	31.	21.	10.	590.
INCHES		.29	.78	.92	.92
MM		7.34	19.73	23.38	23.38
AC-FT		541.	1454.	1723.	1723.
THOUS CU M		668.	1794.	2126.	2126.

MAXIMUM STORAGE = 529.

STATION 2030, PLAN 1, RTIO 3

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1940.	1859.	1220.	579.	34733.
CMS	55.	53.	35.	16.	984.
INCHES		.49	1.29	1.53	1.53
MM		12.52	32.84	38.97	38.97
AC-FT		922.	2420.	2872.	2872.
THOUS CU M		1138.	2985.	3543.	3543.

MAXIMUM STORAGE = 890.

Several pages of printout deleted

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAGST	ADSCNT	AANCST	ILPR
2030	16	1	0	0.	0.000	0	0.00000	0.00000	-2

ECONOMIC DATA FOR STATION 2030 PLAN 1

FREQ	PEAK	SUM	TYPE 1
6.000	1030.	0.000	0.000
5.500	1130.	0.000	0.000
4.500	1380.	1.600	1.600
3.500	1740.	2.400	2.400
2.500	2280.	5.000	5.000
1.500	3200.	7.200	7.200
.900	4220.	9.800	9.800
.700	4600.	11.800	11.800
.500	5620.	13.900	13.900
.350	6480.	16.400	16.400
.250	7340.	20.300	20.300
.150	8540.	23.100	23.100
.100	10000.	28.000	28.000
.050	12100.	34.500	34.500
.020	15100.	44.300	44.300
.005	21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 1

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	941.	6.000	.284	0.00	0.00
2	1139.	5.462	1.752	.99	.99
3	1940.	3.097	1.776	5.81	5.81
4	2921.	1.769	1.072	6.66	6.66
5	4312.	.867	.785	7.73	7.73
6	6699.	.323	.391	6.54	6.54
7	10191.	.095	.136	3.70	3.70
8	15177.	.020	.037	1.50	1.50
9	20603.	.006	.014	.66	.66
	AVG ANN DMG			33.58	33.58

LOCAL PROTECTION DATA

XLPMX	XLPMN	XANCST	XDSCNT
8300.	1700.	.02300	.05040

CAPACITY=	1700.	5000.	5500.	7000.	8300.	9300.	0.	0.	0.	0.
COST=	42.	103.	149.	222.	283.	340.	0.	0.	0.	0.

MINIMUM DESIGN DAMAGE FUNCTION

PEAK	CATEGORY DAMAGES
1030.	0.00
1130.	0.00
1380.	1.60
1740.	2.40
2280.	5.00
3200.	7.20
4220.	9.80
4800.	11.80
5620.	13.90
6480.	16.40
7340.	20.30
8540.	23.10
10000.	28.00
12100.	34.50
15100.	44.30
21000.	50.10

MAXIMUM DESIGN DAMAGE FUNCTION

PEAK	CATEGORY DAMAGES
1030.	0.00
1130.	0.00
1380.	1.60
1740.	2.40
2280.	5.00
3200.	7.20
4220.	9.80
4800.	11.80
5620.	13.90
6480.	16.40
7340.	20.30
8540.	23.10
10000.	28.00
12100.	34.50
15100.	44.30
21000.	50.10

INTERPOLATED ECONOMIC DATA FOR STATION 2030 PLAN 2

PEAK	SUM	TYPE 1
1030.	0.000	0.000
1130.	0.000	0.000
1380.	0.000	0.000
1740.	0.000	0.000
2280.	0.000	0.000
3200.	0.000	0.000
4220.	0.000	0.000
4800.	0.000	0.000
5620.	0.000	0.000
7653.	0.000	0.000
7660.	21.047	21.047
8540.	23.100	23.100
10000.	28.000	28.000
12100.	34.500	34.500
15100.	44.300	44.300
21000.	50.100	50.100

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 2030 PLAN 2

NO.	FLOW	EXCD FREQ	PROB INT	SUM	TYPE 1
1	940.	6.000	.284	0.00	0.00
2	1115.	5.462	1.752	0.00	0.00
3	1500.	3.097	1.776	0.00	0.00
4	2280.	1.769	1.072	0.00	0.00
5	3691.	.867	.785	0.00	0.00
6	5939.	.323	.391	.01	.01
7	9455.	.095	.136	3.41	3.41
8	14455.	.020	.037	1.45	1.45
9	19892.	.006	.014	.65	.65
	AVG ANN DMG			5.51	5.51
	AVG ANN BFT			28.07	28.07

UNIFORM PROTECTION LEVEL = .198

LOCAL PROTECTION CAP COST = 253. TOTAL ANNUAL = 19. DESIGN Q = 7660.

********** ********** ********** ********** **********

SUB-AREA RUNOFF COMPUTATION

LOCAL INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	0	0	2	0	0	1	0	0

PREVIOUSLY GENERATED HYDROGRAPHS READ FROM TAPE
PLAN 1,RATIO 1

2.	2.	2.	3.	4.	7.	16.	31.	43.	49.
55.	58.	64.	66.	70.	76.	88.	108.	160.	250.
330.	385.	413.	450.	453.	423.	383.	333.	278.	225.
183.	154.	129.	104.	83.	64.	50.	39.	30.	23.
18.	14.	10.	8.	7.	6.	5.	5.	4.	4.
3.	3.	3.	3.	3.	3.	3.	2.	2.	2.

********** ********** ********** ********** **********

COMBINE HYDROGRAPHS

COMBINED INFLOW TO FOREBAY POOL

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
30	3	0	0	0	0	1	0	0

SUM OF 3 HYDROGRAPHS AT 30 PLAN 1 RTIO 1

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	2219.	2137.	1433.	675.	40523.
CMS	63.	61.	41.	19.	1147.
INCHES		.25	.66	.78	.78
MM		6.30	16.89	19.90	19.90
AC-FT		1060.	2844.	3351.	3351.
THOUS CU M		1308.	3508.	4133.	4133.

Several pages of printout deleted

HYDROGRAPH ROUTING

PROPOSED PUMPING PLANT SITE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
305	1	1	0	0	2	1	0	0

PLAN 1
ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	0	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	=1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

STATION 305, PLAN 1, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	17.	22.	33.	53.	81.
114.	150.	187.	225.	262.	298.	335.	374.	421.	492.
597.	735.	897.	1078.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1069.	855.
683.	546.	437.	350.	280.	225.	181.	147.	119.	97.

STOR

5.	5.	5.	5.	5.	6.	7.	11.	18.	27.
38.	50.	62.	75.	87.	99.	112.	125.	140.	164.
199.	245.	299.	359.	425.	499.	581.	665.	746.	821.
885.	939.	981.	1011.	1030.	1036.	1032.	1017.	992.	958.
916.	867.	811.	749.	681.	606.	525.	439.	356.	285.
228.	182.	146.	117.	93.	75.	60.	49.	40.	32.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	670.	40227.
CMS	34.	34.	34.	19.	1139.
INCHES		.14	.56	.78	.78
MM		3.54	14.14	19.75	19.75
AC-FT		595.	2381.	3326.	3326.
THOUS CU M		734.	2937.	4103.	4103.

MAXIMUM STORAGE = 1036.

STATION 305, PLAN 1, RTIO 2

OUTFLOW

17.	17.	17.	17.	18.	20.	26.	40.	64.	97.
137.	180.	225.	270.	314.	355.	394.	435.	489.	572.
698.	863.	1059.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1105.	870.	685.	541.	427.	338.

STOR

6.	6.	6.	6.	6.	7.	9.	13.	21.	32.
46.	60.	75.	90.	105.	118.	131.	145.	163.	191.
233.	288.	353.	429.	521.	629.	747.	869.	988.	1098.
1195.	1278.	1347.	1403.	1444.	1471.	1485.	1486.	1475.	1454.
1423.	1384.	1337.	1283.	1223.	1156.	1083.	1003.	919.	831.
740.	648.	554.	460.	368.	290.	228.	180.	142.	113.

Several pages of printout deleted

PLAN 2

ROUTING DATA

QLOSS	CLOSS	AVG	IRES	ISAME	IOPT	IPMP	IDVR	LSTR
0.0	0.000	0.00	1	0	0	9	0	1

NSTPS	NSTDL	LAG	AMSKK	X	TSK	STORA
1	0	0	0.000	0.000	0.000	=1.

STORAGE=	0.	400.	100000.	0.	0.	0.	0.	0.	0.	0.
OUTFLOW=	0.	1200.	1200.	0.	0.	0.	0.	0.	0.	0.

PUMPING PLANT DATA

PMPMX	PMPMN	PMPON	PWRCST	PANCST	PDSCNT
10000.	0.	1500.	100.	.02300	.05040

CAPACITY=	0.	250.	500.	1000.	2000.	6000.	8000.	10000.	0.	0.
COST=	0.	670.	1000.	1600.	2300.	6000.	7860.	8670.	0.	0.

STATION 305, PLAN 2, RTIO 1

OUTFLOW

14.	14.	14.	14.	15.	16.	19.	27.	40.	58.
80.	105.	131.	159.	187.	216.	247.	280.	321.	381.
466.	574.	697.	830.	968.	1099.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1150.	1036.	934.	845.	766.	696.
634.	578.	529.	484.	444.	407.	374.	343.	315.	287.

STOR

5.	5.	5.	5.	5.	5.	6.	9.	13.	19.
27.	35.	44.	53.	62.	72.	82.	93.	107.	127.
155.	191.	232.	277.	323.	366.	406.	443.	480.	514.
543.	568.	586.	600.	607.	607.	602.	592.	575.	554.
528.	497.	462.	424.	383.	345.	311.	282.	255.	232.
211.	193.	176.	161.	148.	136.	125.	114.	105.	96.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1151.	640.	38391.
CMS	34.	34.	33.	18.	1087.
INCHES		.14	.53	.74	.74
MM		3.54	13.57	18.85	18.85
AC-FT		595.	2285.	3174.	3174.
THOUS CU M		734.	2818.	3916.	3916.

MAXIMUM STORAGE = 607.

Several pages of printout deleted

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1039.	62367.
CMS	34.	34.	34.	29.	1766.
INCHES		.14	.56	1.21	1.21
MM		3.54	14.14	30.62	30.62
AC-FT		595.	2381.	5157.	5157.
THOUS CU M		734.	2937.	6361.	6361.

MAXIMUM STORAGE = 25706.

STATION 305, PLAN 2, RTIO 9

VPMP=1935416.
VOLP=2069889.

PUMPING	CAP COST	PWR COST	TOT ANN $
2457.1	2723.	94.	293.

OUTFLOW

246.	246.	247.	250.	258.	280.	333.	447.	627.	845.
1088.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.

STOR

82.	82.	82.	83.	86.	93.	111.	149.	209.	282.
363.	456.	575.	725.	903.	1112.	1363.	1674.	1889.	2302.
2998.	4027.	5397.	7136.	9258.	11716.	14428.	17276.	20135.	22895.
25479.	27844.	29972.	31851.	33480.	34865.	36025.	36986.	37770.	38399.
38893.	39273.	39556.	39757.	39890.	39965.	39996.	39990.	39956.	39899.
39826.	39740.	39643.	39535.	39419.	39295.	39165.	39028.	38886.	38739.

PUMPING

0.	0.	0.	0.	0.	0.	0.	0.	0.	0.
0.	0.	0.	0.	0.	0.	0.	0.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.
2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.	2457.

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	1200.	1200.	1200.	1061.	63666.
CMS	34.	34.	34.	30.	1803.
INCHES		.14	.56	1.23	1.23
MM		3.54	14.14	31.26	31.26
AC-FT		595.	2381.	5264.	5264.
THOUS CU M		734.	2937.	6494.	6494.

MAXIMUM STORAGE = 39996.

EXPECTED ANNUAL FLOOD DAMAGE COMPUTATION

ISTA	NFLOD	NDMG	ISAME	TRGT	DGPRT	IAQST	ADSCNT	AANCST	ILPR
305	10	2	1	0.	0.000	0	0.00000	0.00000	0

ECONOMIC DATA FOR STATION 305 PLAN 1

FREQ	STOR	SUM	TYPE 1	TYPE 2
.700	1500.	0.000	0.000	0.000
.600	2300.	48.000	37.500	10.500
.450	4000.	90.000	75.000	15.000
.250	7000.	1177.500	1125.000	52.500
.100	12500.	3255.000	3150.000	105.000
.050	20000.	6052.500	5850.000	202.500
.020	28000.	7350.000	7050.000	300.000
.010	37000.	9390.000	9000.000	390.000
.005	50000.	11190.000	10650.000	540.000
.002	76000.	11835.000	11250.000	585.000

NO ADJUSTMENT OF AVERAGE ANNUAL DAMAGES FOR THIS DATA

FLOOD DAMAGES FOR STATION 305 PLAN 1

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	1036.	.700	0.000	0.00	0.00	0.00
2	1486.	.700	.152	2.02	1.58	.44
3	3587.	.480	.197	21.19	18.50	2.69
4	5904.	.311	.150	112.78	107.26	5.51
5	9557.	.169	.119	240.14	231.56	8.58
6	15876.	.075	.075	311.36	300.95	10.41
7	24937.	.030	.037	232.61	223.56	9.06
8	38699.	.009	.013	110.98	106.13	4.85
9	53876.	.004	.008	79.14	75.28	3.86
	AVG ANN DMG			1110.21	1064.81	45.40

FLOOD DAMAGES FOR STATION 305 PLAN 2

NO.	STOR	EXCD FREQ	PROB INT	SUM	TYPE 1	TYPE 2
1	607.	.700	0.000	0.00	0.00	0.00
2	882.	.700	.152	0.00	0.00	0.00
3	1554.	.480	.197	.41	.32	.09
4	1630.	.311	.150	2.00	1.56	.44
5	2654.	.169	.119	6.61	5.33	1.28
6	5603.	.075	.075	59.48	56.68	2.79
7	13184.	.030	.037	124.50	120.32	4.18
8	25706.	.009	.013	81.99	78.78	3.21
9	39996.	.004	.008	67.22	64.32	2.90
	AVG ANN DMG			342.21	327.31	14.90
	AVG ANN BFT			768.00	737.50	30.50

********** ********** ********** ********** **********

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS RATIO 1 .25	RATIO 2 .30	RATIO 3 .50	RATIO 4 .70	RATIO 5 1.00	RATIO 6 1.50	RATIO 7 2.20	RATIO 8 3.25	RATIO 9 4.40
HYDROGRAPH AT	10	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
		(90.91)		(38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
				(38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	110	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
		(90.91)		(38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	588.	666.	910.	1084.	1324.	1656.	6328.	12033.	18039.
				(16.65)(	18.85)(	25.76)(	30.70)(	37.48)(	46.89)(	179.20)(	340.73)(	510.80)
ROUTED TO	1030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
		(90.91)		(26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	525.	594.	839.	1005.	1252.	1574.	4949.	10079.	15369.
				(14.87)(	16.83)(	23.76)(	28.46)(	35.47)(	44.58)(	140.13)(	285.41)(	435.19)
HYDROGRAPH AT	20	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
		(90.91)		(38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
				(38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
ROUTED TO	20	35.10	1	1343.	1611.	2685.	3759.	5370.	8055.	11814.	17453.	23628.
		(90.91)		(38.02)(	45.62)(	76.03)(	106.44)(	152.06)(	228.09)(	334.54)(	494.20)(	669.07)
			2	1346.	1549.	2023.	3096.	4717.	7408.	11178.	16833.	23026.
				(38.12)(	43.86)(	57.29)(	87.68)(	133.56)(	209.78)(	316.53)(	476.65)(	652.02)
ROUTED TO	2030	35.10	1	941.	1139.	1940.	2921.	4312.	6699.	10191.	15177.	20603.
		(90.91)		(26.65)(	32.24)(	54.94)(	82.71)(	122.10)(	189.70)(	288.58)(	429.77)(	583.42)
			2	940.	1115.	1500.	2280.	3691.	5939.	9455.	14455.	19892.
				(26.61)(	31.56)(	42.46)(	64.57)(	104.51)(	168.16)(	267.74)(	409.31)(	563.28)
HYDROGRAPH AT	30	10.00	1	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
		(25.90)		(12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
			2	453.	543.	905.	1267.	1810.	2715.	3982.	5883.	7964.
				(12.81)(	15.38)(	25.63)(	35.88)(	51.25)(	76.88)(	112.76)(	166.57)(	225.52)
3 COMBINED	30	80.20	1	2219.	2676.	4563.	6859.	10154.	15693.	23748.	35345.	48011.
		(207.72)		(62.84)(	75.79)(	129.21)(	194.23)(	287.53)(	444.39)(	672.47)(	1000.86)(	1359.53)
			2	1660.	1939.	2712.	3947.	5974.	9178.	14377.	25809.	38550.
				(46.99)(	54.90)(	76.81)(	111.75)(	169.15)(	259.89)(	407.11)(	730.83)(	1091.60)
ROUTED TO	305	80.20	1	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
		(207.72)		(33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
			2	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.	1200.
				(33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)(	33.98)
				PEAK STORAGES IN ACRE FEET (1000 CUBIC METERS)								
			1	1036.	1486.	3587.	5904.	9557.	15876.	24937.	38699.	53876.
				(1278.)(	1833.)(	4424.)(	7283.)(	11788.)(	19583.)(	30760.)(	47734.)(	66455.)
			2	607.	882.	1554.	1630.	2654.	5603.	13184.	25706.	39996.
				(749.)(	1088.)(	1917.)(	2011.)(	3274.)(	6911.)(	16263.)(	31708.)(	49334.)

SYSTEM OPTIMIZATION RESULTS

VAR 1	VAR 2	VAR 3	VAR 4	VAR 5	VAR 6	DIV 7	DIV 8	PMP 9	PMP 10
6701.	198.	0.	0.	0.	0.	670.	0.	2457.	0.

SYSTEM COST AND PERFORMANCE SUMMARY
(UNITS SAME AS INPUT - NORMALLY 1000'S OF DOLLARS)

TOTAL SYSTEM CAPITAL COST * * * * * * * * * * * * * * *	7408.	
TOTAL SYSTEM AMORTIZED CAPITAL COST * * * * * * * * *	373.	
TOTAL SYSTEM ANNUAL O,M,POWER AND REPLACEMENT COST *	257.	
TOTAL SYSTEM ANNUAL COST * * * * * * * * * * * * * * *		631.
AVERAGE ANNUAL DAMAGES -- EXISTING CONDITIONS * * * *	1177.	
AVERAGE ANNUAL DAMAGES -- OPTIMIZED SYSTEM * * * * *	350.	
AVERAGE ANNUAL DAMAGE REDUCTION (BENEFITS) * * * * *		827.
AVERAGE ANNUAL SYSTEM NET BENEFITS * * * * * * * * *		196.

***** OPTIMIZATION OBJECTIVE - MAXIMIZE SYSTEM NET BENEFITS *****

TFCST	ANFCST	ANOMPR	TANCST	ANDGBS	ANDMG	TBNFTS	NTBNFT
5034.	254.	211.	465.	1177.	601.	577.	112.

GPO 689-166/052